



JUNE 19, 2017

**SMART BUS TURNOUT - GUERNEVILLE ROAD  
CONTRACT NO. C01964  
ADDENDUM NO. 1**

Specifications:

1. Pages 2 and 61 shall be replaced with 2R and 61R respectively.

2. Insert the following paragraph after the last paragraph in Section 5-1.20:

**Pacific Gas and Electric (PG&E) will be relocating SMART's electrical service. Contractor shall coordinate their work with PG&E.**

3. Section 86-1.01 Description, remove the following words from the first sentence:

"Sonoma Marin Area Rail Transit (SMART) electrical service"

4. Insert the following paragraph after the last paragraph in Section 86-2.03 Foundations:

**Contractor shall pothole the storm drain at the proposed street light location. Contractor shall relocate the street light to STA 1+51 if it is determined that inadequate room is available.**

5. Delete Section 86-2.11 SMART Service in its entirety.

6. Section 86-8.10 Payment, delete payment items **SMART Electrical Service** and **Lower SMART Electrical Service** in their entirety.

7. Replace the first sentence of Section 86-8.10 Payment with the following:

**Relocate Street Light** shall be paid for at the contract **lump sum** price, which price shall include full compensation for furnishing all labor, materials, tools, and equipment, and doing all work including furnishing and installing foundation, No. 5 pull box, conduit, conductors, excavation, backfilling, disposal of spoils, pothole storm drain, relocate street light to STA 1+51 if needed and no additional allowance will be made therefor

Plans:

1. Sheet 3, Delete note 6 and note 9 in their entirety.



---

DAVID MONTAGUE  
Supervising Engineer

**CITY OF SANTA ROSA ESTIMATED QUANTITIES  
C01964 - SMART BUS TURNOUT - GUERNEVILLE ROAD**

<u>No.</u>	<u>Item</u>	<u>Quantity</u>	<u>Units</u>
1	TRAFFIC CONTROL	1	LS
2	WATER POLLUTION CONTROL	1	LS
3	DEMOLITION	1	LS
4	INSTALL SIGN POLE	1	EA
5	CURB	193	LF
6	GUTTER	1750	SF
7	SIDEWALK	1450	SF
8	THERMOPLASTIC BIKE LANE SYMBOL AND BIKE LANE ARROW	1	EA
9	6" THERMOPLASTIC BIKE LANE	255	LF
10	THERMOPLASTIC BIKE LOOP DETECTOR SYMBOL	1	EA
11	RELOCATE STREET LIGHT	1	LS
12	PRE-EMPTION CABLE	1	LS

**CITY OF SANTA ROSA UNIT PRICE SCHEDULE  
C01964 - SMART BUS TURNOUT - GUERNEVILLE ROAD**

No.	Item	Quantity	Units	Unit Price	Total Price
1	TRAFFIC CONTROL	1	LS	\$_____	\$_____
2	WATER POLLUTION CONTROL	1	LS	\$_____	\$_____
3	DEMOLITION	1	LS	\$_____	\$_____
4	INSTALL SIGN POLE	1	EA	\$_____	\$_____
5	CURB	193	LF	\$_____	\$_____
6	GUTTER	1750	SF	\$_____	\$_____
7	SIDEWALK	1450	SF	\$_____	\$_____
8	THERMOPLASTIC BIKE LANE SYMBOL AND BIKE LANE ARROW	1	EA	\$_____	\$_____
9	6" THERMOPLASTIC BIKE LANE	255	LF	\$_____	\$_____
10	THERMOPLASTIC BIKE LOOP DETECTOR SYMBOL	1	EA	\$_____	\$_____
11	RELOCATE STREET LIGHT	1	LS	\$_____	\$_____
12	PRE-EMPTION CABLE	1	LS	\$_____	\$_____
	<b>TOTAL</b>				\$_____