

INVITATION FOR BIDS



FOR CONSTRUCTION OF

Sonoma Avenue Pavement Rehabilitation
Farmers Lane to Hahman Drive

CITY CONTRACT NUMBER
C02261

ISSUED BY
CAPITAL PROJECTS ENGINEERING DIVISION
CITY OF SANTA ROSA, CALIFORNIA

2025

TABLE OF CONTENTS

Notice Inviting Bids.....	1
Instructions to Bidders.....	3
Bid Proposal.....	9
Bid Schedule.....	11
Subcontractor List.....	14
Noncollusion Declaration.....	15
Bid Bond.....	16
Bidder's Questionnaire.....	18
Contractor Agreement To Be Bound.....	21
Contract.....	22
Payment Bond.....	26
Performance Bond.....	28
General Conditions.....	30
Article 1 - Definitions.....	30
Definitions.....	30
Article 2 - Roles and Responsibilities.....	33
2.1 City.....	33
2.2 Contractor.....	33
2.3 Subcontractors.....	37
2.4 Coordination of Work.....	37
2.5 Submittals.....	38
2.6 Shop Drawings.....	39
2.7 Material List.....	39
2.8 Access to Work.....	39
2.9 Personnel.....	39
Article 3 - Contract Documents.....	39
3.1 Interpretation of Contract Documents.....	39
3.2 Order of Precedence.....	40
3.3 Caltrans Standard Specifications and Standard Plans.....	41
3.4 For Reference Only.....	41
3.5 Current Versions.....	42
3.6 Conformed Copies.....	42
3.7 Ownership.....	42
Article 4 - Bonds, Indemnity, and Insurance.....	42
4.1 Payment and Performance Bonds.....	42
4.2 Indemnity.....	42
4.3 Insurance.....	42
Article 5 - Contract Time.....	45
5.1 Time is of the Essence.....	45
5.2 Schedule Requirements.....	45
5.3 Delay and Extensions of Contract Time.....	47
5.4 Liquidated Damages.....	50
Article 6 - Contract Modification.....	50
6.1 Contract Modification.....	50
6.2 Contractor Change Order Requests.....	52
6.3 Adjustments to Contract Price.....	52
6.4 Unilateral Change Order.....	53
6.5 Non-Compliance Deemed Waiver.....	53
Article 7 - General Construction Provisions.....	53
7.1 Permits, Fees, Licenses, Certificates, and Taxes.....	53
7.2 Temporary Facilities.....	53
7.3 Noninterference and Site Management.....	54
7.4 Signs.....	55
7.5 Project Site and Nearby Property Protections.....	55
7.6 Materials and Equipment.....	56
7.7 Substitutions.....	57

7.8	Testing and Inspection.....	58
7.9	Project Site Conditions and Maintenance.....	59
7.10	Instructions and Manuals	60
7.11	As-built Drawings	61
7.12	Existing Utilities	61
7.13	Notice of Excavation	61
7.14	Trenching and Excavations of Four Feet or More	62
7.15	Trenching of Five Feet or More	62
7.16	New Utility Connections	62
7.17	Lines and Grades.....	62
7.18	Historic or Archeological Items	63
7.19	Environmental Control	63
7.20	Noise Control.	64
7.21	Mined Materials.....	64
7.22	Water Department Notification.....	64
7.23	Public Safety and Traffic Control.	64
Article 8	- Payment.....	65
8.1	Schedule of Values	65
8.2	Progress Payments.....	65
8.3	Adjustment of Payment Application	66
8.4	Early Occupancy.....	67
8.5	Retention.....	67
8.6	Payment to Subcontractors and Suppliers	67
8.7	Final Payment.....	68
8.8	Release of Claims.....	68
8.9	Warranty of Title.....	68
Article 9	- Labor Provisions	68
9.1	Discrimination Prohibited	68
9.2	Labor Code Requirements.....	68
9.3	Prevailing Wages	69
9.4	Payroll Records.....	69
9.5	Labor Compliance.....	69
Article 10	- Safety Provisions	69
10.1	Safety Precautions and Programs	69
10.2	Hazardous Materials	70
10.3	Material Safety	70
10.4	Hazardous Condition	70
10.5	Emergencies	71
10.6	Confined Space Operations.....	71
Article 11	- Completion and Warranty Provisions	71
11.1	Final Completion	71
11.2	Warranty	72
11.3	Use Prior to Final Completion	73
11.4	Substantial Completion.....	73
Article 12	- Dispute Resolution	73
12.1	Claims	73
12.2	Claims Submission	73
12.3	City's Response	75
12.4	Meet and Confer	75
12.5	Mediation and Government Code Claims.....	76
12.6	Tort Claims.....	76
12.7	Arbitration.....	76
12.8	Burden of Proof and Limitations	76
12.9	Legal Proceedings	76
12.10	Other Disputes	77
Article 13	- Suspension and Termination	77
13.1	Suspension for Cause	77
13.2	Suspension for Convenience	77
13.3	Termination for Default	78
13.4	Termination for Convenience.....	79

13.5	Actions Upon Termination for Default or Convenience	79
Article 14 - Miscellaneous Provisions.....		80
14.1	Assignment of Unfair Business Practice Claims.....	80
14.2	Provisions Deemed Inserted.....	80
14.3	Waiver	80
14.4	Titles, Headings, and Groupings	80
14.5	Statutory and Regulatory References.....	80
14.6	Survival.	80
Special Conditions		81
Technical Specifications.....		83

Notice Inviting Bids

1. **Bid Submission.** City of Santa Rosa ("City") will accept sealed bids for its Sonoma Avenue Pavement Rehabilitation Farmers Lane to Hahman Drive Project ("Project"), before **November 20, 2025, at 2:00 p.m.**, at its Transportation and Public Works office, located at 69 Stony Circle, Santa Rosa, California, at which time the bids will be publicly opened and read aloud. Bidders may attend the public opening in person.
2. **Project Information.**
 - 2.1 **Location and Description.** The Project is located on Sonoma Avenue between Farmers Lane and Hahman Drive. The project will rehabilitate approximately 570 linear feet of this roadway to address failing and deteriorating pavement conditions while implementing shared bike/bus lanes and upgrading pedestrian curb ramps to current ADA standards. Portland cement concrete overlay technology will be utilized to reduce costs, construction time and associated traffic impacts while extending pavement life. Water services within the project limits will be replaced. Sidewalk will be added to fill missing gaps on both sides of Sonoma Avenue.
 - 2.2 **Time for Final Completion.** The Project must be fully completed within **60 Working Days** from the start date set forth in the Notice to Proceed. City anticipates that the Work will begin on or about January 2026, but the anticipated start date is provided solely for convenience and is neither certain nor binding.
 - 2.3 **Estimated Cost.** The estimated construction cost is **\$1,922,000**.
3. **License and Registration Requirements.**
 - 3.1 **License.** This Project requires a valid California contractor's license for the following classification(s): **Class A**
 - 3.2 **DIR Registration.** City may not accept a Bid Proposal from, or enter into the Contract with, a bidder without proof that the bidder is registered with the California Department of Industrial Relations ("DIR") to perform public work pursuant to Labor Code § 1725.5, subject to limited legal exceptions.
4. **Contract Documents.** The plans, specifications, bid forms and contract documents for the Project, and any addenda thereto ("Contract Documents") may be downloaded from the City's PlanetBids portal, which may be accessed by selecting the "Bid/Proposal Opportunities" link on the City's website at <https://www.srcity.org/165/Bids-Proposals>. A printed copy of the Contract Documents is not available.
5. **Bid Security.** The Bid Proposal must be accompanied by bid security of ten percent of the maximum bid amount, in the form of a cashier's or certified check made payable to City, or a bid bond executed by a surety licensed to do business in the State of California on the Bid Bond form included with the Contract Documents. The bid security must guarantee that within ten days after City issues the Notice of Award, the successful bidder will execute the Contract and submit the payment and performance bonds, insurance certificates and endorsements, valid Certificates of Reported Compliance as required under the California Air Resources Board's In-Use Off-Road Diesel-Fueled Fleets Regulation (13 CCR § 2449 et seq.) ("Off-Road Regulation"), if applicable, and any other submittals required by the Contract Documents and as specified in the Notice of Award.

6. Prevailing Wage Requirements.

6.1 General. Pursuant to California Labor Code § 1720 et seq., this Project is subject to the prevailing wage requirements applicable to the locality in which the Work is to be performed for each craft, classification or type of worker needed to perform the Work, including employer payments for health and welfare, pension, vacation, apprenticeship and similar purposes.

6.2 Rates. The prevailing rates are on file with the City and are available online at <http://www.dir.ca.gov/DLSR>. Each Contractor and Subcontractor must pay no less than the specified rates to all workers employed to work on the Project. The schedule of per diem wages is based upon a working day of eight hours. The rate for holiday and overtime work must be at least time and one-half.

6.3 Compliance. The Contract will be subject to compliance monitoring and enforcement by the DIR, under Labor Code § 1771.4.

7. Performance and Payment Bonds. The successful bidder will be required to provide performance and payment bonds, each for 100% of the Contract Price, as further specified in the Contract Documents.

8. Substitution of Securities. Substitution of appropriate securities in lieu of retention amounts from progress payments is permitted under Public Contract Code § 22300.

9. Subcontractor List. Each Subcontractor must be registered with the DIR to perform work on public projects. Each bidder must submit a completed Subcontractor List form with its Bid Proposal, including the name, location of the place of business, California contractor license number, DIR registration number, and percentage of the Work to be performed (based on the base bid price) for each Subcontractor that will perform Work or service, or fabricate and install Work, for the prime contractor in excess of one-half of 1% of the bid price, using the Subcontractor List form included with the Contract Documents.

11. Instructions to Bidders. All bidders should carefully review the Instructions to Bidders for more detailed information before submitting a Bid Proposal. The definitions provided in Article 1 of the General Conditions apply to all of the Contract Documents, as defined therein, including this Notice Inviting Bids.

By: *Sara Kozel*
Sara Kozel (Oct 27, 2025 15:51:48 PDT)
Sara Kozel, P.E., Supervising Engineer

Date: 10/27/2025

Publication Date: October 30, 2025

END OF NOTICE INVITING BIDS

Instructions to Bidders

Each Bid Proposal submitted to the City of Santa Rosa ("City") for its Sonoma Avenue Pavement Rehabilitation Farmers Lane to Hahman Drive Project ("Project") must be submitted in accordance with the following instructions and requirements:

1. Bid Submission.

1.1 General. Each Bid Proposal must be completed, using the form provided in the Contract Documents, signed, and submitted to City in a sealed envelope, with all required forms and attachments, before the deadline set forth in Section 1 of the Notice Inviting Bids, or as amended by subsequent addendum. Faxed or emailed Bid Proposals will not be accepted, unless otherwise specified. Late submissions (i.e., submissions at or after the exact hour of bid opening) will be returned unopened. City reserves the right to postpone the date or time for receiving or opening bids. Each bidder is solely responsible for all of its costs to prepare and submit its bid and by submitting a bid waives any right to recover those costs from City. The bid price(s) must include all costs to perform the Work as specified, including all labor, material, supplies, and equipment and all other direct or indirect costs such as applicable taxes, insurance and overhead.

1.2 Vendor Registration. To participate in the bidding process, each bidder must register as a vendor on PlanetBids, download the Contract Documents, and add itself to the "Prospective Bidders" list for the Project. If City issues an addendum, each bidder must log in to PlanetBids and acknowledge the addendum prior to the bid deadline. (See Section 8, below.)

1.3 Bid Envelope. The sealed envelope containing the Bid Proposal and all required forms and attachments must be clearly labeled and addressed as follows:

BID PROPOSAL:

Sonoma Avenue Pavement Rehabilitation
Farmers Lane to Hahman Drive Project
Contract No. 2261

Transportation and Public Works Department
69 Stony Circle
Santa Rosa, California 95401
Attn: Greg Dwyer

The envelope must also be clearly labeled, as follows, with the bidder's name, address, and its registration number with the California Department of Industrial Relations ("DIR") for bidding on public works contracts (Labor Code §§ 1725.5 and 1771.1):

[Contractor company name]

[street address]

[city, state, zip code]

DIR Registration No: _____

1.4 DIR Registration. Subject to limited legal exceptions for joint venture bids and federally-funded projects, City may not accept a Bid Proposal from a bidder without proof that the bidder is registered with the DIR to perform public work under Labor Code § 1725.5. If the City is unable to confirm that the bidder is currently registered with the DIR, City may disqualify the bidder and return its bid unopened. (Labor Code §§ 1725.5 and 1771.1(a).)

1.5 Bid Tabulation. To access the bid tabulation when available, visit www.srcity.org/bids. Click the link to "Capital Projects Bid Results" under the Capital Projects heading.

2. **Bid Proposal Form and Enclosures.** Each Bid Proposal must be completed legibly using the Bid Proposal form included with the Contract Documents. The Bid Proposal form must be fully completed without interlineations, alterations, or erasures. Any necessary corrections must be clear and legible and must be initialed by the bidder's authorized representative. A Bid Proposal submitted with exceptions or terms such as "negotiable," "will negotiate," or similar, will be considered nonresponsive. Each Bid Proposal must be accompanied by bid security, as set forth in Section 4 below, and by a completed Bid Schedule, Subcontractor List, and Non-Collusion Declaration using the forms included with the Contract Documents, and any additional forms required by the Notice Inviting Bids or Instructions to Bidders.
3. **Authorization and Execution.** Each Bid Proposal must be signed by the bidder's authorized representative. A Bid Proposal submitted by a partnership must be signed in the partnership name by a general partner with authority to bind the partnership. A Bid Proposal submitted by a corporation must be signed with the legal name of the corporation, followed by the signature and title of two officers of the corporation with full authority to bind the corporation to the terms of the Bid Proposal under California Corporations Code § 313 or as otherwise authorized by law.
4. **Bid Security.** Each Bid Proposal must be accompanied by bid security of ten percent of the maximum bid amount, in the form of a cashier's check or certified check, made payable to the City, or bid bond using the form included in the Contract Documents and executed by a surety licensed to do business in the State of California. The bid security must guarantee that, within ten days after issuance of the Notice of Award, the bidder will: execute and submit the enclosed Contract for the bid price; submit payment and performance bonds for 100% of the maximum Contract Price; submit the insurance certificates and endorsements; and submit valid Certificates of Reported Compliance as required by the Off-Road Regulation, if applicable, and any other submittals, if any, required by the Contract Documents or the Notice of Award.
5. **Requests for Information.** Questions or requests for clarifications regarding the Project, the bid procedures, or any of the Contract Documents must be submitted in writing to City via the PlanetBids portal. Oral responses are not authorized and are not binding on the City. Bidders should submit any such written inquiries at least five Working Days before the scheduled bid opening. Questions received any later might not be addressed before the bid deadline. An interpretation or clarification by City in response to a written inquiry will be issued in an addendum.
6. **Pre-Bid Investigation.**
 - 6.1 **General.** Each bidder is solely responsible at its sole expense for diligent and thorough review of the Contract Documents, examination of the Project site, and reasonable and prudent inquiry concerning known and potential site and area conditions prior to submitting a Bid Proposal. Each bidder is responsible for knowledge of conditions and requirements which reasonable review and investigation would have disclosed. However, except for any areas that are open to the public at large, bidders may not enter property owned or leased by the City or the Project site without prior written authorization from City.
 - 6.2 **Document Review.** Each bidder is responsible for review of the Contract Documents and any informational documents provided "For Reference Only," e.g., as-builts, technical reports, test data, and the like. A bidder is responsible for notifying City of any errors, omissions, inconsistencies, or conflicts it discovers in the Contract Documents, acting solely in its capacity as a contractor and subject to the limitations of Public Contract Code § 1104. Notification of any such errors, omissions, inconsistencies, or conflicts must be submitted in writing to the City no later than five Working Days before the scheduled bid opening. (See Section 5, above.) City expressly disclaims responsibility for assumptions a bidder might draw from the presence or absence of information provided by City.
 - 6.3 **Project Site.** Questions regarding the availability of soil test data, water table elevations, and the like should be submitted to the City in writing, as specified in Section 5, above. Any subsurface exploration at the Project site must be done at the bidder's expense, but only

with prior written authorization from City. All soil data and analyses available for inspection or provided in the Contract Documents apply only to the test hole locations. Any water table elevation indicated by a soil test report existed on the date the test hole was drilled. The bidder is responsible for determining and allowing for any differing soil or water table conditions during construction. Because groundwater levels may fluctuate, difference(s) in elevation between ground water shown in soil boring logs and ground water actually encountered during construction will not be considered changed Project site conditions. Actual locations and depths must be determined by bidder's field investigation. The bidder may request access to underlying or background information on the Project site in City's possession that is necessary for the bidder to form its own conclusions, including, if available, record drawings or other documents indicating the location of subsurface lines, utilities, or other structures.

- 6.4 Utility Company Standards.** The Project must be completed in a manner that satisfies the standards and requirements of any affected utility companies or agencies (collectively, "utility owners"). The successful bidder may be required by the third party utility owners to provide detailed plans prepared by a California registered civil engineer showing the necessary temporary support of the utilities during coordinated construction work. Bidders are directed to contact the affected third party utility owners about their requirements before submitting a Bid Proposal.
- 7. Bidders Interested in More Than One Bid.** No person, firm, or corporation may submit or be a party to more than one Bid Proposal unless alternate bids are specifically called for. However, a person, firm, or corporation that has submitted a subcontract proposal or quote to a bidder may submit subcontract proposals or quotes to other bidders.
- 8. Addenda.** Subject to the limitations of Public Contract Code § 4104.5, City reserves the right to issue addenda prior to bid time. Any addenda issued prior to the bid opening are part of the Contract Documents. Bidders should check City's PlanetBids portal periodically for any addenda or updates on the Project, which may be accessed via City's website at: <https://www.srcity.org/165/Bids-Proposals>. Each bidder is solely responsible for ensuring it has received and reviewed all addenda prior to submitting its bid and must acknowledge each addendum in the PlanetBids portal.
- 9. Brand Designations and "Or Equal" Substitutions.** Any specification designating a material, product, thing, or service by specific brand or trade name, followed by the words "or equal," is intended only to indicate quality and type of item desired, and bidders may request use of any equal material, product, thing, or service. All data substantiating the proposed substitute as an equal item must be submitted with the written request for substitution. A request for substitution must be submitted within 35 days after Notice of Award unless otherwise provided in the Contract Documents. This provision does not apply to materials, products, things, or services that may lawfully be designated by a specific brand or trade name under Public Contract Code § 3400(c).
- 10. Bid Protest.** Any bid protest against another bidder must be submitted in writing and received by City at Transportation and Public Works Department, 69 Stony Circle, Santa Rosa, CA 95401 or sent via email at gdwyer@srcity.org before 5:00 p.m. no later than two Working Days following bid opening ("Bid Protest Deadline") and must comply with the following requirements:
- 10.1 General.** Only a bidder who has actually submitted a Bid Proposal is eligible to submit a bid protest against another bidder. Subcontractors are not eligible to submit bid protests. A bidder may not rely on the bid protest submitted by another bidder but must timely pursue its own protest. For purposes of this Section 10, a "Working Day" means a day that City is open for normal business, and excludes weekends and holidays observed by City. Pursuant to Public Contract Code § 4104, inadvertent omission of a Subcontractor's DIR registration number on the Subcontractor List form is not grounds for a bid protest, provided it is corrected within 24 hours of the bid opening or as otherwise provided under Labor Code § 1771.1(b).

- 10.2 Protest Contents.** The bid protest must contain a complete statement of the basis for the protest and must include all supporting documentation. Material submitted after the Bid Protest Deadline will not be considered. The protest must refer to the *specific* portion or portions of the Contract Documents upon which the protest is based. The protest must include the name, address, email address, and telephone number of the protesting bidder and any person submitting the protest on behalf of or as an authorized representative of the protesting bidder.
- 10.3 Copy to Protested Bidder.** Upon submission of its bid protest to City, the protesting bidder must also concurrently transmit the protest and all supporting documents to the protested bidder, and to any other bidder who has a reasonable prospect of receiving an award depending upon the outcome of the protest, by email or hand delivery to ensure delivery before the Bid Protest Deadline.
- 10.4 Response to Protest.** The protested bidder may submit a written response to the protest, provided the response is received by City before 5:00 p.m., within two Working Days after the Bid Protest Deadline or after actual receipt of the bid protest, whichever is sooner (the "Response Deadline"). The response must attach all supporting documentation. Material submitted after the Response Deadline will not be considered. The response must include the name, address, email address, and telephone number of the person responding on behalf of or representing the protested bidder if different from the protested bidder.
- 10.5 Copy to Protesting Bidder.** Upon submission of its response to the bid protest to the City, the protested bidder must also concurrently transmit by email or hand delivery, by or before the Response Deadline, a copy of its response and all supporting documents to the protesting bidder and to any other bidder who has a reasonable prospect of receiving an award depending upon the outcome of the protest.
- 10.6 Exclusive Remedy.** The procedure and time limits set forth in this Section are mandatory and are the bidder's sole and exclusive remedy in the event of a bid protest. A bidder's failure to comply with these procedures will constitute a waiver of any right to further pursue a bid protest, including filing a Government Code Claim or initiation of legal proceedings.
- 10.7 Right to Award.** City reserves the right, acting in its sole discretion, to reject any bid protest that it determines lacks merit, to award the Contract to the bidder it has determined to be the responsible bidder submitting the lowest responsive bid, and to issue a Notice to Proceed with the Work notwithstanding any pending or continuing challenge to its determination.
- 11. Reservation of Rights.** Subject to the provisions of its charter and the Santa Rosa City Code ("City Code"), City reserves the unfettered right, acting in its sole discretion, to waive or to decline to waive any immaterial bid irregularities; to accept or reject any or all bids; to cancel or reschedule the bid; to postpone or abandon the Project entirely; or to perform all or part of the Work with its own forces. The Contract will be awarded, if at all, within 90 days after opening of bids or as otherwise specified in the Special Conditions, to the responsible bidder that submitted the lowest responsive bid. Any planned start date for the Project represents the City's expectations at the time the Notice Inviting Bids was first issued. City is not bound to issue a Notice to Proceed by or before such planned start date, and it reserves the right to issue the Notice to Proceed when the City determines, in its sole discretion, the appropriate time for commencing the Work. The City expressly disclaims responsibility for any assumptions a bidder might draw from the presence or absence of information provided by the City in any form. Each bidder is solely responsible for its costs to prepare and submit a bid, including site investigation costs.
- 12. Bonds.** Within ten calendar days following issuance of the Notice of Award, the successful bidder must submit payment and performance bonds to City as specified in the Contract Documents using the bond forms included in the Contract Documents. All required bonds must be calculated on the maximum total Contract Price as awarded, including additive alternates, if applicable.

- 13. License(s) and Certificate(s).** The successful bidder and its Subcontractor(s) must possess the California contractor's license(s) in the classification(s) required by law to perform the Work. The successful bidder must also obtain a City business tax certificate, issued pursuant to Chapter 6.04 of the City Code before performing any Work on the Project. Subcontractors must also obtain a City business tax certificate before performing any Work.
- 14. Ineligible Subcontractor.** Any Subcontractor who is ineligible to perform work on a public works project under Labor Code §§ 1777.1 or 1777.7 is prohibited from performing work on the Project.
- 15. Safety Orders.** If the Project includes construction of a pipeline, sewer, sewage disposal system, boring and jacking pits, or similar trenches or open excavations, which are five feet or deeper, each bid must include a bid item for adequate sheeting, shoring, and bracing, or equivalent method, for the protection of life or limb, which comply with safety orders as required by Labor Code § 6707.
- 16. In-Use Off-Road Diesel-Fueled Fleets.** If the Project involves the use of vehicles subject to the California Air Resources Board's In-Use Off-Road Diesel-Fueled Fleets Regulation (13 CCR § 2449 et seq.) ("Off-Road Regulation"), then within ten calendar days following City's issuance of the Notice of Award, the successful bidder must submit to City valid Certificates of Reported Compliance for its fleet and its listed Subcontractors, if applicable, in accordance with the Off-Road Regulation, unless exempt under the Off-Road Regulation.
- 17. Community Workforce Agreement.** If checked below, the Project is subject to the City's Community Workforce Agreement ("CWA") and the successful bidder must comply with the requirements therein.

Select One:

- ☒ This Project is subject to the City's CWA, which is available on the City's website at <https://www.srcity.org/165/Bids-Proposals> and incorporated herein by reference, except for that concrete contractors shall not be Covered Work under the Community Workforce Agreement as described in the Letter dated October 8, 2025 from Maraskeshia Smith, City Manager to North Bay Building and Construction Trades Council. Within three Working Days following a request from City, the apparent low bidder must submit to City an executed Appendix A, Contractor Agreement to be Bound, using the form provided with the Contract Documents. Each bidder must provide a copy of the CWA to its Subcontractors, and the successful bidder and its Subcontractors must comply with the CWA. Entering into the CWA is a condition of award of the Contract for the Project.
- ☐ This Project is not subject to the City's CWA.

- 18. Bid Schedule.** Each bidder must complete the Bid Schedule form with unit prices as indicated and submit the completed Bid Schedule with its Bid Proposal.
- 18.1 Incorrect Totals.** In the event a computational error for any bid item (base bid or alternate) results in an incorrect extended total for that item, the submitted base bid or bid alternate total will be adjusted to reflect the corrected amount as the product of the estimated quantity and the unit cost. In the event of a discrepancy between the actual total of the itemized or unit prices shown on the Bid Schedule for the base bid, and the amount entered as the base bid on the Bid Proposal form, the actual total of the itemized or unit prices shown on the Bid Schedule for the base bid will be deemed the base bid price. Likewise, in the event of a discrepancy between the actual total of the itemized or unit prices shown on the Bid Schedule for any bid alternate, and the amount entered for the alternate on the Bid Proposal form, the actual total of the itemized prices shown on the Bid Schedule for that alternate will be deemed the alternate price. Nothing in this provision is intended to prevent a bidder from requesting to withdraw its bid for material error under Public Contract Code § 5100 et seq.

- 18.2 Estimated Quantities.** Unless identified as a “Final Pay Quantity,” the quantities shown on the Bid Schedule are estimated and the actual quantities required to perform the Work may be greater or less than the estimated amount. The Contract Price will be adjusted to reflect the actual quantities required for the Work based on the itemized or unit prices provided in the Bid Schedule, with no allowance for anticipated profit for quantities that are deleted or decreased, and no increase in the unit price, and without regard to the percentage increase or decrease of the estimated quantity and the actual quantity.
- 18.3 Bid Item Description.** The descriptions of bid items in the Specifications are not intended as exclusive descriptions of the Work. Each bidder must determine, and include in its unit pricing, all things necessary and incidental for the timely performance and completion of the Work as specified in the Contract Documents, including, but not limited to, all necessary labor, materials, supplies, tools, equipment, transportation, facilities, and utilities, unless otherwise specified.
- 19. Withdrawal.** A Bid Proposal may not be withdrawn for a period of 90 days after the bid opening without forfeiture of the bid security, except as authorized for material error under Public Contract Code § 5100 et seq. In the event that a bid includes a material error, the bidder may request to withdraw its bid in accordance with Public Contract Code § 5100 et seq. The written request must establish the elements set forth in Public Contract Code § 5103.

END OF INSTRUCTIONS TO BIDDERS

Bid Proposal

Sonoma Avenue Pavement Rehabilitation Farmers Lane to Hahman Drive Project

_____ (“Bidder”) hereby submits this Bid Proposal to the City of Santa Rosa (“City”) for the above-referenced project (“Project”) in response to the Notice Inviting Bids and in accordance with the Contract Documents referenced in the Notice.

1. **Base Bid.** Bidder proposes to perform and fully complete the Work for the Project as specified in the Contract Documents, within the time required for full completion of the Work, including all labor, materials, supplies, and equipment and all other direct or indirect costs including, but not limited to, taxes, insurance and all overhead, for the following price (“Base Bid”):
\$ _____.
2. **Addenda.** Bidder agrees that it has confirmed receipt of or access to, and reviewed, all addenda issued for this bid, as evidenced by its acknowledgement of each addendum on the City’s PlanetBids portal. Bidder waives any claims it might have against the City based on its failure to receive, access, or review any addenda for any reason.
3. **Bidder’s Certifications and Warranties.** By signing and submitting this Bid Proposal, Bidder certifies and warrants the following:
 - 3.1 **Examination of Contract Documents.** Bidder has thoroughly examined the Contract Documents and represents that, to the best of Bidder’s knowledge, there are no errors, omissions, or discrepancies in the Contract Documents, subject to the limitations of Public Contract Code § 1104.
 - 3.2 **Examination of Worksite.** Bidder has had the opportunity to examine the Worksite and local conditions at the Project location.
 - 3.3 **Bidder Responsibility.** Bidder is a responsible bidder, with the necessary ability, capacity, experience, skill, qualifications, workforce, equipment, and resources to perform or cause the Work to be performed in accordance with the Contract Documents and within the Contract Time.
 - 3.4 **Responsibility for Bid.** Bidder has carefully reviewed this Bid Proposal and is solely responsible for any errors or omissions contained in its completed bid. All statements and information provided in this Bid Proposal and enclosures are true and correct to the best of Bidder’s knowledge.
 - 3.5 **Nondiscrimination.** In preparing this bid, the Bidder has not engaged in discrimination against any prospective or present employee or Subcontractor on grounds of race, color, ancestry, national origin, ethnicity, religion, sex, sexual orientation, age, disability, or marital status.
 - 3.6 **Iran Contracting Act.** If the Contract Price exceeds \$1,000,000, Bidder is not identified on a list created under the Iran Contracting Act, Public Contract Code § 2200 et seq. (the “Act”), as a person engaging in investment activities in Iran, as defined in the Act, or is otherwise expressly exempt under the Act.
 - 3.7 **Agreement to be Bound by CWA.** If the Project is subject to the City’s CWA, Bidder will submit an executed Appendix A, Contractor Agreement to be Bound, using the form provided with the Contract Documents, within three Working Days following a request from City. (See Section 17 of the Instructions to Bidders.)

4. **Award of Contract.** By signing and submitting this Bid Proposal, Bidder agrees that, if City issues the Notice of Award to Bidder, then within ten days following issuance of the Notice of Award, Bidder will do all of the following:
- 4.1 **Execute Contract.** Enter into the Contract with City in accordance with the terms of this Bid Proposal, by signing and submitting to City the Contract prepared by City using the form included with the Contract Documents;
- 4.2 **Submit Required Bonds.** Submit to City a payment bond and a performance bond, each for 100% of the Contract Price, using the bond forms provided and in accordance with the requirements of the Contract Documents;
- 4.3 **Insurance Requirements.** Submit to City the insurance certificate(s) and endorsement(s) as required by the Contract Documents; and
- 4.4 **Certificates of Reported Compliance.** Submit to City valid Certificates of Reported Compliance for its fleet and its listed Subcontractors, if applicable, if the Project involves the use of vehicles subject to the Off-Road Regulation.
5. **Bid Security.** As a guarantee that, if awarded the Contract, Bidder will perform its obligations under Section 4 above, Bidder is enclosing bid security in the amount of ten percent of its maximum bid amount in one of the following forms (check one):

_____ A cashier's check or certified check payable to City and issued by
_____ [Bank name] in the amount of
\$_____.

_____ A bid bond, using the Bid Bond form included with the Contract Documents, payable to City and executed by a surety licensed to do business in the State of California.

This Bid Proposal is hereby submitted on _____, 20__.

s/ _____

Name and Title

s/ _____
[See Section 3 of Instructions to Bidders]

Name and Title

Company Name

License #, Expiration Date, and Classification

Address

DIR Registration #

City, State, Zip

Phone

Contact Name

Contact Email

END OF BID PROPOSAL

Bid Schedule

BIDDER NAME: _____

This Bid Schedule must be completed legibly and included with the sealed Bid Proposal. Pricing must be provided for each Bid Item as indicated. If this Bid Schedule requests pricing for Alternates, pricing must be provided for each Alternate Item as indicated. Items marked "(SW)" are Specialty Work that must be performed by a qualified Subcontractor. The lump sum or unit cost for each item must be inclusive of all costs, whether direct or indirect, including profit and overhead.

AL = Allowance
LF = Linear Foot

CF = Cubic Feet
LS = Lump Sum

CY = Cubic Yard
SF = Square Feet

EA = Each LB = Pounds
TON = Ton (2000 lbs)

BASE BID

BID ITEM NO.	ITEM DESCRIPTION	EST. QTY.	UNIT	UNIT COST	EXTENDED TOTAL AMOUNT
1	MOBILIZATION (NOT TO EXCEED 2% OF BID)	1	LS	\$	\$
2	TRAFFIC CONTROL	1	LS	\$	\$
3	WATER POLLUTION CONTROL	1	LS	\$	\$
4	LOWER MANHOLE FRAME AND COVER	2	EA	\$	\$
5	LOWER VALVE BOX OR MONUMENT	8	EA	\$	\$
6	ADJUST MANHOLE FRAME AND COVER	3	EA	\$	\$
7	ADJUST VALVE BOX OR MONUMENT	8	EA	\$	\$
8	ADJUST TELEPHONE VAULT AT CURB RAMP OR SIDEWALK	1	EA	\$	\$
9	ADJUST TELEVISION PULL BOX AT CURB RAMP OR SIDEWALK	1	EA	\$	\$
10	ADJUST ELECTRICAL PULL BOX AT CURB RAMP OR SIDEWALK	2	EA	\$	\$
11	ADJUST TRAFFIC SIGNAL PULL BOX AT CURB RAMP OR SIDEWALK	2	EA	\$	\$
12	RELOCATE TRAFFIC SIGNAL PULL BOX AT CURB RAMP OR SIDEWALK	5	EA	\$	\$
13	UTILITY CLEARANCES	1	LS	\$	\$
14	IRRIGATION MODIFICATIONS	1	LS	\$	\$
15	HOT MIX ASPHALT PAVEMENT SURFACE COURSE (4 INCH DEPTH)	144	TON	\$	\$
16	HOT MIX ASPHALT PAVEMENT BASE COURSE (4 INCH DEPTH)	144	TON	\$	\$
17	COLD MILL ASPHALT PAVEMENT (8 INCH DEPTH)	3,921	SY	\$	\$
18	BONDED CONCRETE OVERLAY ON ASPHALT (8 INCH THICK)	3,338	SY	\$	\$
19	PCC VERTICAL CURB	74	LF	\$	\$
20	PCC CURB AND GUTTER	237	LF	\$	\$
21	PCC VALLEY GUTTER	335	SF	\$	\$

BID ITEM NO.	ITEM DESCRIPTION	EST. QTY.	UNIT	UNIT COST	EXTENDED TOTAL AMOUNT
22	PCC CURB RAMP	1,409	SF	\$	\$
23	PCC SIDEWALK	2,939	SF	\$	\$
24	PCC SIDEWALK BUS STOP	180	SF	\$	\$
25	PCC RETAINING CURB	468	LF	\$	\$
26	REMOVE SIGN AND POST	1	EA	\$	\$
27	INSTALL SIGN ON EXISTING POST	2	EA	\$	\$
28	INSTALL SIGN AND POST	4	EA	\$	\$
29	THERMOPLASTIC TRAFFIC STRIPE - DETAIL 22	475	LF	\$	\$
30	THERMOPLASTIC TRAFFIC STRIPE - DETAIL 38	378	LF	\$	\$
31	THERMOPLASTIC TRAFFIC STRIPE - DETAIL 39	200	LF	\$	\$
32	THERMOPLASTIC TRAFFIC STRIPE - DETAIL 39A	100	LF	\$	\$
33	THERMOPLASTIC TRAFFIC STRIPE - DETAIL 40	160	LF	\$	\$
34	THERMOPLASTIC GREEN BIKE LANE	96	SF	\$	\$
35	THERMOPLASTIC BICYCLE BUFFER	666	LF	\$	\$
36	THERMOPLASTIC BICYCLE BUFFER WITH CHEVRON MARKINGS	140	LF	\$	\$
37	THERMOPLASTIC WHITE BASIC CROSSWALK	470	LF	\$	\$
38	THERMOPLASTIC WHITE CONTINENTAL CROSSWALK	264	SF	\$	\$
39	THERMOPLASTIC PAVEMENT MARKINGS	719	SF	\$	\$
40	4" WHITE STRIPE	13	LF	\$	\$
41	PAINTED PAVEMENT MARKINGS	26	SF	\$	\$
42	FIRE HYDRANT BLUE MARKER	2	EA	\$	\$
43	TRAFFIC SIGNAL DETECTOR LOOP (TYPE A)	3	EA	\$	\$
44	TRAFFIC SIGNAL DETECTOR LOOP (TYPE D)	1	EA	\$	\$
45	RELOCATE PEDESTRIAN LIGHTING	1	EA	\$	\$
46	TRAFFIC SIGNAL MODIFICATIONS (VARIOUS INTERSECTIONS)	1	LS	\$	\$
47	TRAFFIC SIGNAL INTERCONNECT SYSTEM	1	LS	\$	\$
48	1.5" DUAL WATER SERVICE	2	EA	\$	\$
49	1" REDUCED PRESSURE BACKFLOW PREVENTOR	2	EA	\$	\$
50	ADJUST WATER VAULT AND WATER COMPONENTS TO GRADE	1	EA	\$	\$

BID ITEM NO.	ITEM DESCRIPTION	EST. QTY.	UNIT	UNIT COST	EXTENDED TOTAL AMOUNT
51	ABANDON OR REMOVE WATER SYSTEM COMPONENTS	1	LS	\$	\$
52	MODULAR BUS PLATFORM SYSTEM BY ZICLA	2	EA	\$	\$
53	BUS STOP SHELTER	2	EA	\$	\$
54	BUS STOP BENCH	4	EA	\$	\$

* Final Pay Quantity

TOTAL BASE BID: Items 1 through _____ inclusive: \$ _____

Note: The amount entered as the "Total Base Bid" should be identical to the Base Bid amount entered in Section 1 of the Bid Proposal form.

END OF BID SCHEDULE

Subcontractor List

For each Subcontractor that will perform a portion of the Work in an amount in excess of one-half of 1% of the Bidder's total Base Bid,¹ the bidder must list a description of the Work, the name of the Subcontractor, its California contractor license number, the location of its place of business, its DIR registration number, and the portion of the Work that the Subcontractor is performing based on a percentage of the Base Bid price.

DESCRIPTION OF WORK	SUBCONTRACTOR NAME	CALIFORNIA CONTRACTOR LICENSE NO.	LOCATION OF BUSINESS	DIR REG. NO.	PERCENT OF WORK

END OF SUBCONTRACTOR LIST

¹ For street or highway construction, this requirement applies to any subcontract of \$10,000 or more.

Noncollusion Declaration

TO BE EXECUTED BY BIDDER AND SUBMITTED WITH BID

The undersigned declares:

I am the _____ [title] of _____
[business name], the party making the foregoing bid.

The bid is not made in the interest of, or on behalf of, any undisclosed person, partnership, company, association, organization, or corporation. The bid is genuine and not collusive or sham. The bidder has not directly or indirectly induced or solicited any other bidder to put in a false or sham bid. The bidder has not directly or indirectly colluded, conspired, connived, or agreed with any bidder or anyone else to put in a sham bid, or to refrain from bidding. The bidder has not in any manner, directly or indirectly, sought by agreement, communication, or conference with anyone to fix the bid price of the bidder or any other bidder, or to fix any overhead, profit, or cost element of the bid price, or of that of any other bidder. All statements contained in the bid are true. The bidder has not, directly or indirectly, submitted his or her bid price or any breakdown thereof, or the contents thereof, or divulged information or data relative thereto, to any corporation, partnership, company, association, organization, bid depository, or to any member or agent thereof, to effectuate a collusive or sham bid, and has not paid and will not pay, any person or entity for such purpose.

Any person executing this declaration on behalf of a bidder that is a corporation, partnership, joint venture, limited liability company, limited liability partnership, or any other entity, hereby represents that he or she has full power to execute, and does execute, this declaration on behalf of the bidder.

This declaration is intended to comply with California Public Contract Code § 7106 and Title 23 U.S.C § 112.

I declare under penalty of perjury under the laws of the State of California that the foregoing is true and correct and that this declaration is executed on _____ [date], at
_____ [city], _____ [state].

s/ _____

Name [print]

END OF NONCOLLUSION DECLARATION

Bid Bond

_____, 20____ ("Bidder") has submitted a bid, dated _____, 20____ ("Bid"), to the City of Santa Rosa ("City") for work on the Sonoma Avenue Pavement Rehabilitation Farmers Lane to Hahman Drive Project ("Project"). Under this duly executed bid bond ("Bid Bond"), Bidder as Principal and _____, its surety ("Surety"), are bound to City as obligee in the penal sum of ten percent of the maximum amount of the Bid (the "Bond Sum"). Bidder and Surety bind themselves and their respective heirs, executors, administrators, successors and assigns, jointly and severally, as follows:

1. **General.** If Bidder is awarded the Contract for the Project, Bidder will enter into the Contract with City in accordance with the terms of the Bid.
2. **Submittals.** Within ten days following issuance of the Notice of Award to Bidder, Bidder must submit to City the following:
 - 2.1 **Contract.** The executed Contract, using the form provided by City in the Project contract documents ("Contract Documents");
 - 2.2 **Payment Bond.** A payment bond for 100% of the maximum Contract Price, executed by a surety licensed to do business in the State of California using the Payment Bond form included with the Contract Documents;
 - 2.3 **Performance Bond.** A performance bond for 100% of the maximum Contract Price, executed by a surety licensed to do business in the State of California using the Performance Bond form included with the Contract Documents;
 - 2.4 **Insurance.** The insurance certificate(s) and endorsement(s) required by the Contract Documents;
 - 2.5 **Certificates of Reported Compliance.** Valid Certificates of Reported Compliance for its fleet and its listed Subcontractors, if applicable, in accordance with the In-Use Off-Road Diesel-Fueled Fleets Regulation (13 CCR § 2449 et seq.) ("Off-Road Regulation"), if the Project involves the use of vehicles subject to the Off-Road Regulation; and
 - 2.6 **Other Submittals.** Any other documents required by the Instructions to Bidders or Notice of Award.
3. **Enforcement.** If Bidder fails to execute the Contract or to submit the bonds, insurance certificates, and valid Certificates of Reported Compliance as required by the Contract Documents, Surety guarantees that Bidder forfeits the Bond Sum to City. Any notice to Surety may be given in the manner specified in the Contract and delivered or transmitted to Surety as follows:

Attn: _____
Address: _____
City/State/Zip: _____
Phone: _____
Fax: _____
Email: _____
4. **Duration and Waiver.** If Bidder fulfills its obligations under Section 2, above, then this obligation will be null and void; otherwise, it will remain in full force and effect for 90 days following the bid opening or until this Bid Bond is returned to Bidder, whichever occurs first. Surety waives the provisions of Civil Code §§ 2819 and 2845.

This Bid Bond is entered into and effective on _____, 20_____.

SURETY:

Business Name

s/ _____

Date

Name, Title

(Attach Acknowledgment with Notary Seal and Power of Attorney)

BIDDER:

Business Name

s/ _____

Date

Name, Title

END OF BID BOND

Bidder's Questionnaire

Sonoma Avenue Pavement Rehabilitation Farmers Lane to Hahman Drive Project

Within 48 hours following a request by City, a bidder must submit to City a completed, signed Bidder's Questionnaire using this form and all required attachments, including clearly labeled additional sheets as needed. City may request the Questionnaire from one or more of the apparent low bidders following the bid opening and may use the completed Questionnaire as part of its investigation to evaluate a bidder's qualifications for this Project. The Questionnaire must be filled out completely, accurately, and legibly. Any errors, omissions, or misrepresentations in completion of the Questionnaire may be grounds for rejection of the bid or termination of a Contract awarded pursuant to the bid.

Part A: General Information

Bidder Business Name: _____ ("Bidder")

Check One: ☐ Corporation (State of incorporation: _____)
 ☐ Partnership
 ☐ Sole Proprietorship
 ☐ Joint Venture of: _____
 ☐ Other: _____

Main Office Address and Phone: _____

Local Office Address and Phone: _____

Website Address: _____

Owner of Business: _____

Contact Name and Title: _____

Contact Phone and Email: _____

Bidder's California Contractor's License Number(s): _____

Bidder's DIR Registration Number: _____

Part B: Bidder Experience

1. How many years has Bidder been in business under its present business name? _____ years

2. Has Bidder completed projects similar in type and size to this Project as a general contractor?
_____ Yes _____ No

3. Has Bidder ever been disqualified from a bid on grounds that it is not responsible, or otherwise disqualified or debarred from bidding under state or federal law?
_____ Yes _____ No

If yes, provide additional information on a separate sheet regarding the disqualification or debarment, including the name and address of the agency or owner of the project, the type and size of the project,

the reasons that Bidder was disqualified or debarred, and the month and year in which the disqualification or debarment occurred.

4. Has Bidder ever been terminated for cause, alleged default, or legal violation from a construction project, either as a general contractor or as a subcontractor?

_____ Yes _____ No

If yes, provide additional information on a separate sheet regarding the termination, including the name and address of the agency or owner of the subject project, the type and size of the project, whether Bidder was under contract as a general contractor or a subcontractor, the reasons that Bidder was terminated, and the month and year in which the termination occurred.

5. Provide information about Bidder's past projects performed as general contractor as follows:

- 5.1 Six most recently completed public works projects within the last three years;
- 5.2 Three largest completed projects within the last three years; and
- 5.3 Any project which is similar to this Project including scope and character of the work.

6. Use separate sheets to provide all of the following information for each project identified in response to the above three categories:

- 6.1 Project name, location, and description;
- 6.2 Owner (name, address, email, and phone number);
- 6.3 Prime contractor, if applicable (name, address, email, and phone number);
- 6.4 Architect or engineer (name, email, and phone number);
- 6.5 Project and/or construction manager (name, email, and phone number);
- 6.6 Scope of work performed (as general contractor or as subcontractor);
- 6.7 Initial contract price and final contract price (including change orders);
- 6.8 Original scheduled completion date and actual date of completion;
- 6.9 Time extensions granted (number of days);
- 6.10 Number and amount of stop notices or mechanic's liens filed;
- 6.11 Amount of any liquidated damages assessed against Bidder; and
- 6.12 Nature and resolution of any project-related claim, lawsuit, mediation, or arbitration involving Bidder.

Part C: Safety

1. Provide Bidder's Experience Modification Rate (EMR) for the last three years:

Year	EMR

2. Complete the following, based on information provided in Bidder's CalOSHA Form 300 or Form 300A, Annual Summary of Work-Related Illnesses and Injuries, from the most recent past calendar year:

- 2.1 Number of lost workday cases: _____
- 2.2 Number of medical treatment cases: _____
- 2.3 Number of deaths: _____

3. Has Bidder ever been cited, fined, or prosecuted by any local, state, or federal agency, including OSHA, CalOSHA, or EPA, for violation of any law, regulation, or requirements pertaining to health and safety?

_____ Yes _____ No

If yes, provide additional information on a separate sheet regarding each such citation, fine, or prosecution, including the name and address of the agency or owner of the project, the type and size of the project, the reasons for and nature of the citation, fine, or prosecution, and the month and year in which the incident giving rise to the citation, fine, or prosecution occurred.

4. Name, title, and email for person responsible for Bidder's safety program:

_____	_____	_____
Name	Title	Email

Part D: Verification

In signing this document, I, the undersigned, declare that I am duly authorized to sign and submit this Bidder's Questionnaire on behalf of the named Bidder, and that all responses and information set forth in this Bidder's Questionnaire and accompanying attachments are, to the best of my knowledge, true, accurate and complete as of the date of submission. **I declare under penalty of perjury under the laws of the State of California that the foregoing is true and correct.**

Signature: _____ Date: _____

By: _____
Name and Title

END OF BIDDER'S QUESTIONNAIRE

Appendix A

City of Santa Rosa Community Workforce Agreement Contractor Agreement To Be Bound

The undersigned, as a Contractor or Subcontractor ("Contractor") for the _____ Project, (hereinafter the "Covered Project"), for and in consideration of the award to it of a contract to perform work on said Covered Project, and in further consideration of the mutual promises made in the "City of Santa Rosa Community Workforce Agreement" (hereinafter "Agreement"), a copy of which was received and is acknowledged, hereby:

- (1) Accepts and agrees to be bound by the terms and conditions of the Agreement, together with any and all amendments and supplements now existing or which are later made thereto.
- (2) Agrees to be bound by the legally established local trust agreements as set forth in Article 17 of this Agreement.
- (3) Authorizes the parties to such local trust agreements to appoint trustees and successor trustees to administer the trust funds and hereby ratifies and accepts the trustees so appointed as if made by the Contractor;
- (4) Certifies that it has no commitments or agreements which would preclude its full and complete compliance with the terms and conditions of the Agreement.
- (5) Agrees to secure from any Contractor(s) (as defined in said Agreement) which is or becomes a subcontractor (of any tier) to it, a duly executed Agreement to be Bound in form identical to this document.

The obligation to be a party to and bound by the Agreement shall extend to all work for the Covered Project undertaken by the Contractor.

This letter shall constitute a subscription agreement, to the extent of the terms of the letter.

CONTRACTOR/SUBCONTRACTOR: _____

California Contractor State License No. or Motor Carrier (CA) Permit No.: _____

Name of Authorized Person (print): _____


Signature of Authorized Person: _____

Title of Authorized Person: _____

Telephone Number of Authorized Person: _____


Address of Authorized Person: _____

State Public Works Registration Number: _____



MEMORANDUM

Date: October 8, 2025

From: Maraskeshia Smith, City Manager 

To: President and Secretary-Treasurer, North Bay Building and Construction Trades Council
Dan Hennessey, Director of Transportation and Public Works

Subject: Notice of Section 2.6(g) Exclusion for C02261 – Sonoma Avenue Pavement Rehabilitation

Per section 20.6 of the Community Workforce Agreement, this letter provides notice that concrete suppliers shall not be Covered Work under the Community Workforce Agreement for C02261 – Sonoma Avenue Pavement Rehabilitation (Farmers Lane to Hahman Drive) (Project).

To provide additional information in staff report to City Council and to determine a course of action for re-solicitation, Capital Projects Engineering reached out to contractors who attended the pre-bid meeting or who were sent the solicitation, as well as to material suppliers, to determine why no bids were received for this project. Contractors identified challenges finding local subcontractors that met the requirements of the Community Workforce Agreement, either due to no known union representation for certain work categories or no local unionized specialists. Without that qualifying local workforce, prime contractors had issues submitting a compliant, competitive bid. The project requires a number of subcontractors; with an engineer's estimate of \$1,922,000, putting together a competitive, profitable bid that held meaningful work for the prime contractor was challenging.

CPE released the bid opportunity for the Project on September 16, 2025 with a due date of October 8, 2025. No bids were received. An optional pre-bid meeting was conducted on September 25, 2025. Local contractors to whom the bid was directly advertised were contacted on October 8, 2025 to ask why they did not submit a bid. The reasons included:


- Two contractors stated that they could not comply with the Community Workforce Agreement for concrete supply;
- Two contractors stated that while they could put together a team that would comply with the Community Workforce Agreement, not enough work would be left for them to do to be worthwhile; and

- One contractor presumed that they could not put a team together that would be competitive for the low bid and/or meet the requirements of the Community Workforce Agreement.

Section 2.6 of the Community Workforce Agreement defines certain work as excluded from the definition of "Covered Work." Subsection 2.6(g) defines as excluded "Any work that falls within the exclusions set forth in section 4.3 of Council Policy 000-73." Section 4.3 of Council Policy 000-73 in part states that "...this Policy will not apply under the following circumstances to Public Works Projects, where the City Manager reasonably determines that: . . . 4.3.2. A particular construction craft does not have sufficient local presence."

Having issued the bid opportunity, received zero bids, and discussed the limitations and attractiveness of the project with contractors, there is insufficient local contractor density of concrete suppliers associated with the local unions listed in the Community Workforce Agreement. Exercising the referenced exclusion will allow contractors to incorporate non-unionized local companies necessary to support the rehabilitation of the street, which includes new sidewalks, as well as bicycle, transit, and safety improvements.

Given the specific need for those services on the Project, the insufficient local presence of trade contractors capable of meeting those requirements, and the outreach CPE made to determine why no bids were received, I hereby determine for the Project that concrete contractors do not have sufficient local presence. Therefore, for the Project, concrete contractors shall not be Covered Work under the Community Workforce Agreement.


Maraskeshia Smith (Oct 9, 2025 11:28:13 PDT)

Contract

This public works contract ("Contract") is entered into by and between the City of Santa Rosa ("City") and _____ ("Contractor"), for work on the
< _____ > Project ("Project").

The parties agree as follows:

1. **Award of Contract.** In response to the Notice Inviting Bids, Contractor has submitted a Bid Proposal to perform the Work to construct the Project. On _____, 20____, City authorized award of this Contract to Contractor for the amount set forth in Section 4, below. City has elected to include the following Project alternate(s) in the Contract: No alternates
2. **Contract Documents.** The Contract Documents incorporated into this Contract include and are comprised of all of the documents listed below. The definitions provided in Article 1 of the General Conditions apply to all of the Contract Documents, including this Contract.
 - 2.1 Notice Inviting Bids;
 - 2.2 Instructions to Bidders;
 - 2.3 Addenda, if any;
 - 2.4 Bid Proposal and attachments thereto;
 - 2.5 Contract;
 - 2.6 Payment and Performance Bonds;
 - 2.7 General Conditions;
 - 2.8 Special Conditions;
 - 2.9 Project Plans and Specifications;
 - 2.10 Change Orders, if any;
 - 2.11 Notice of Award;
 - 2.12 Notice to Proceed;
 - 2.13 City Standards and City Specifications, as applicable;
 - 2.14 City's CWA, if applicable;
 - 2.15 Caltrans Standard Specifications (excluding Division I) and Caltrans Standard Plans, as applicable; and
 - 2.16 The following: No other documents
3. **Contractor's Obligations.** Contractor will perform all of the Work required for the Project, as specified in the Contract Documents. Contractor must provide, furnish, and supply all things necessary and incidental for the timely performance and completion of the Work, including all necessary labor, materials, supplies, tools, equipment, transportation, onsite facilities, and utilities, unless otherwise specified in the Contract Documents. Contractor must use its best efforts to diligently prosecute and complete the Work in a professional and expeditious manner and to meet or exceed the performance standards required by the Contract Documents.
4. **Payment.** As full and complete compensation for Contractor's timely performance and completion of the Work in strict accordance with the terms and conditions of the Contract Documents, City will pay Contractor \$_____ ("Contract Price") for all of Contractor's direct and indirect costs to perform the Work, including all labor, materials, supplies, equipment, taxes, insurance, bonds and all overhead costs, in accordance with the payment provisions in the General Conditions.
5. **Time for Completion.** Contractor will fully complete the Work for the Project, meeting all requirements for Final Completion, within 60 Working Days from the start date set forth in the Notice to Proceed ("Contract Time"). By signing below, Contractor expressly waives any claim for delayed early completion.
6. **Liquidated Damages.** As further specified in Section 5.4 of the General Conditions, if Contractor fails to complete the Work within the Contract Time, City will assess liquidated damages in the

amount of \$5000 per day for each day of unexcused delay in achieving Final Completion, and such liquidated damages may be deducted from City's payments due or to become due to Contractor under this Contract.

7. Labor Code Compliance.

7.1 General. This Contract is subject to all applicable requirements of Chapter 1 of Part 7 of Division 2 of the Labor Code, including requirements pertaining to wages, working hours and workers' compensation insurance, as further specified in Article 9 of the General Conditions.

7.2 Prevailing Wages. This Project is subject to the prevailing wage requirements applicable to the locality in which the Work is to be performed for each craft, classification or type of worker needed to perform the Work, including employer payments for health and welfare, pension, vacation, apprenticeship and similar purposes. Copies of these prevailing rates are available online at <http://www.dir.ca.gov/DLSR>.

7.3 DIR Registration. City may not enter into the Contract with a bidder without proof that the bidder and its Subcontractors are registered with the California Department of Industrial Relations to perform public work pursuant to Labor Code § 1725.5, subject to limited legal exceptions.

8. Workers' Compensation Certification. Pursuant to Labor Code § 1861, by signing this Contract, Contractor certifies as follows: "I am aware of the provisions of Labor Code § 3700 which require every employer to be insured against liability for workers' compensation or to undertake self-insurance in accordance with the provisions of that code, and I will comply with such provisions before commencing the performance of the Work on this Contract."

9. Conflicts of Interest. Contractor, its employees, Subcontractors, and agents may not have, maintain, or acquire a conflict of interest in relation to this Contract in violation of any City ordinance or requirement, or in violation of any California law, including Government Code § 1090 et seq., or the Political Reform Act, as set forth in Government Code § 81000 et seq. and its accompanying regulations. Any violation of this Section constitutes a material breach of the Contract.

10. Independent Contractor. Contractor is an independent contractor under this Contract and will have control of the Work and the means and methods by which it is performed. Contractor and its Subcontractors are not employees of City and are not entitled to participate in any health, retirement, or any other employee benefits from City.

11. Notice. Any notice, billing, or payment required by or pursuant to the Contract Documents must be made in writing, signed, dated, and sent to the other party by personal delivery, U.S. Mail, a reliable overnight delivery service, or by email as a PDF file. Notice is deemed effective upon delivery, except that service by U.S. Mail is deemed effective on the second working day after deposit for delivery. Notice for each party must be given as follows:

City:

<Department or Title>

<Address>

<City/State/Zip>

<Phone (optional)>

Attn: <Name/Title>

<Email address>

Copy to: <Name/Title>

<Email address>

Contractor:

Name: _____
Address: _____
City/State/Zip: _____
Phone: _____
Attn: _____
Email: _____
Copy to: _____

12. General Provisions.

- 12.1 Assignment and Successors.** Contractor may not assign its rights or obligations under this Contract, in part or in whole, without City's written consent. This Contract is binding on Contractor's and City's lawful heirs, successors and permitted assigns.
- 12.2 Third Party Beneficiaries.** There are no intended third party beneficiaries to this Contract.
- 12.3 Governing Law and Venue.** This Contract will be governed by California law and venue will be in the Sonoma County Superior Court, and no other place. Contractor waives any right it may have pursuant to Code of Civil Procedure § 394, to file a motion to transfer any action arising from or relating to this Contract to a venue outside of Sonoma County, California.
- 12.4 Amendment.** No amendment or modification of this Contract will be binding unless it is in a writing duly authorized and signed by the parties to this Contract.
- 12.5 Integration.** This Contract and the Contract Documents incorporated herein, including authorized amendments or Change Orders thereto, constitute the final, complete, and exclusive terms of the agreement between City and Contractor.
- 12.6 Severability.** If any provision of the Contract Documents is determined to be illegal, invalid, or unenforceable, in whole or in part, the remaining provisions of the Contract Documents will remain in full force and effect.
- 12.7 Iran Contracting Act.** If the Contract Price exceeds \$1,000,000, Contractor certifies, by signing below, that it is not identified on a list created under the Iran Contracting Act, Public Contract Code § 2200 et seq. (the "Act"), as a person engaging in investment activities in Iran, as defined in the Act, or is otherwise expressly exempt under the Act.
- 12.8 Authorization.** Each individual signing below warrants that he or she is authorized to do so by the party that he or she represents, and that this Contract is legally binding on that party. If Contractor is a corporation, signatures from two officers of the corporation are required pursuant to California Corporations Code § 313 or as otherwise authorized by law.
- 12.9 Electronic Signatures.** In accordance with Government Code § 16.5 and Civil Code § 1633.1 et seq., the parties agree that this Contract may be transmitted and executed electronically and that electronic signatures will have the same force and effect as the use of manual signatures.

[Signatures are on the following page.]

The parties agree to this Contract as witnessed by the signatures below:

CITY:

Approved as to form:

s/ _____

s/ _____

Name, Title

Name, Title

Date: _____

Date: _____

Attest:

s/ _____

Name, Title

Date: _____

CONTRACTOR:

Business Name

s/ _____

Seal:

Name, Title

Date: _____

Second Signature (See Section 12.8):

s/ _____

Name, Title

Date: _____

Contractor's California License Number(s) and Expiration Date(s)

END OF CONTRACT

Payment Bond

The City of Santa Rosa ("City") and _____ ("Contractor") have entered into a contract for work on the Sonoma Avenue Pavement Rehabilitation Farmers Lane to Hahman Drive Project ("Project"), City Contract No. C02261. The Contract ("Contract") is incorporated by reference into this Payment Bond ("Bond").

1. **General.** Under this Bond, Contractor as principal and _____, its surety ("Surety"), are bound to City as obligee in an amount not less than \$ _____, under California Civil Code § 9550 et seq., to ensure payment to authorized claimants. This Bond is binding on the respective successors, assigns, owners, heirs, or executors of Surety and Contractor.
2. **Surety's Obligation.** If Contractor or any of its Subcontractors fails to pay a person authorized in California Civil Code § 9100 to assert a claim against a payment bond, any amounts due under the Unemployment Insurance Code with respect to work or labor performed under the Contract, or any amounts required to be deducted, withheld, and paid over to the Employment Development Department from the wages of employees of Contractor and its Subcontractors under California Unemployment Insurance Code § 13020 with respect to the work and labor, then Surety will pay the obligation.
3. **Beneficiaries.** This Bond inures to the benefit of any of the persons named in California Civil Code § 9100, so as to give a right of action to those persons or their assigns in any suit brought upon this Bond. Contractor must promptly provide a copy of this Bond upon request by any person with legal rights under this Bond.
4. **Duration.** If Contractor promptly makes payment of all sums for all labor, materials, and equipment furnished for use in the performance of the Work required by the Contract, in conformance with the time requirements set forth in the Contract and as required by California law, Surety's obligations under this Bond will be null and void. Otherwise, Surety's obligations will remain in full force and effect.
5. **Waivers.** Surety waives any requirement to be notified of alterations to the Contract or extensions of time for performance of the Work under the Contract. Surety waives the provisions of Civil Code §§ 2819 and 2845. City waives the requirement of a new bond for any supplemental contract under Civil Code § 9550. Any notice to Surety may be given in the manner specified in the Contract and sent to Surety as follows:

Attn: _____
Address: _____
City/State/Zip: _____
Phone: _____
Email: _____
6. **Law and Venue.** This Bond will be governed by California law, and venue for any dispute pursuant to this Bond will be in the Sonoma County Superior Court, and no other place. Surety will be responsible for City's attorneys' fees and costs in any action to enforce the provisions of this Bond.

[Signatures are on the following page.]

7. Effective Date; Execution. This Bond is entered into and is effective on _____, 20__.

SURETY:

Business Name

s/ _____

Date

Name, Title

(Attach Acknowledgment with Notary Seal and Power of Attorney)

CONTRACTOR:

Business Name

s/ _____

Date

Name, Title

APPROVED BY CITY:

s/ _____

Date

Name, Title

END OF PAYMENT BOND

Performance Bond

The City of Santa Rosa ("City") and _____ ("Contractor") have entered into a contract for work on the Sonoma Avenue Pavement Rehabilitation Farmers Lane to Hahman Drive Project ("Project"), City Contract No. C02261. The Contract ("Contract") is incorporated by reference into this Performance Bond ("Bond").

1. **General.** Under this Bond, Contractor as principal and _____, its surety ("Surety"), are bound to City as obligee for an amount not less than \$_____ to ensure Contractor's faithful performance of its obligations under the Contract. This Bond is binding on the respective successors, assigns, owners, heirs, or executors of Surety and Contractor.
2. **Surety's Obligations.** Surety's obligations are co-extensive with Contractor's obligations under the Contract. If Contractor fully performs its obligations under the Contract, including its warranty obligations under the Contract, Surety's obligations under this Bond will become null and void. Otherwise, Surety's obligations will remain in full force and effect.
3. **Waiver.** Surety waives any requirement to be notified of and further consents to any alterations to the Contract made under the applicable provisions of the Contract Documents, including changes to the scope of Work or extensions of time for performance of Work under the Contract. Surety waives the provisions of Civil Code §§ 2819 and 2845.
4. **Application of Contract Balance.** Upon making a demand on this Bond for completion of the Work prior to acceptance of the Project, City will make the Contract Balance available to Surety for completion of the Work under the Contract. For purposes of this provision, the Contract Balance is defined as the total amount payable by City to Contractor as the Contract Price minus amounts already paid to Contractor, and minus any liquidated damages, credits, or backcharges to which City is entitled under the terms of the Contract.
5. **Contractor Default.** Upon written notification from City of Contractor's termination for default under Article 13 of the Contract General Conditions, time being of the essence, Surety must act within the time specified in Article 13 to remedy the default through one of the following courses of action:
 - 5.1 Arrange for completion of the Work under the Contract by Contractor, with City's consent, but only if Contractor is in default solely due to its financial inability to complete the Work;
 - 5.2 Arrange for completion of the Work under the Contract by a qualified contractor acceptable to City, and secured by performance and payment bonds issued by an admitted surety as required by the Contract Documents, at Surety's expense; or
 - 5.3 Waive its right to complete the Work under the Contract and reimburse City the amount of City's costs to have the remaining Work completed.
6. **Surety Default.** If Surety defaults on its obligations under the Bond, City will be entitled to recover all costs it incurs due to Surety's default, including legal, design professional, or delay costs.
7. **Notice.** Any notice to Surety may be given in the manner specified in the Contract and sent to Surety as follows:

Attn: _____
Address: _____
City/State/Zip: _____
Phone: _____
Fax: _____
Email: _____

8. **Law and Venue.** This Bond will be governed by California law, and venue for any dispute pursuant to this Bond will be in the Sonoma County Superior Court, and no other place. Surety will be responsible for City's attorneys' fees and costs in any action to enforce the provisions of this Bond.
9. **Effective Date; Execution.** This Bond is entered into and effective on _____, 20____.

SURETY:

Business Name

s/ _____

Date

Name, Title

(Attach Acknowledgment with Notary Seal and Power of Attorney)

CONTRACTOR:

Business Name

s/ _____

Date

Name, Title

APPROVED BY CITY:

s/ _____

Date

Name, Title

END OF PERFORMANCE BOND

General Conditions

Article 1 - Definitions

Definitions. The following definitions apply to all of the Contract Documents unless otherwise indicated, e.g., additional definitions that apply solely to the Specifications or other technical documents. Defined terms and titles of documents are capitalized in the Contract Documents, with the exception of the following (in any tense or form): “day,” “furnish,” “including,” “install,” “work day,” or “working day.”

Allowance means a specific amount that must be included in the Bid Proposal for a specified purpose.

Article, as used in these General Conditions, means a numbered Article of the General Conditions, unless otherwise indicated by the context.

Awarding Authority means the City Council or its authorized delegee(s) unless the Contract is awarded by the Water Department, in which case it means the Board of Public Utilities.

Change Order means a written document duly approved and executed by City, which changes the scope of Work, the Contract Price, or the Contract Time.

City means the City of Santa Rosa, acting through its City Council, officers, employees, City Engineer, and any other authorized representatives.

City Engineer means the City Engineer for City and his or her authorized delegee(s).

City Specifications means the City's Construction Specifications for Public Improvements, which may be accessed on the City's website at <https://www.srcity.org/2321/Design-Construction-Standards>.

City Standards means the City's Design and Construction Standards, which may be accessed on the City's website at <https://www.srcity.org/2321/Design-Construction-Standards>.

Claim means a separate demand by Contractor for a change in the Contract Time or Contract Price, that has previously been submitted to City in accordance with the requirements of the Contract Documents, and which has been rejected by City, in whole or in part; a written demand by Contractor disputing a unilateral Change Order or a portion thereof; or a written demand by Contractor objecting to the amount of Final Payment.

Contract means the signed agreement between City and Contractor for performing the Work required for the Project, and all documents expressly incorporated therein.

Contract Documents means, collectively, all of the documents listed as such in Section 2 of the Contract, including the Notice Inviting Bids; the Instructions to Bidders; addenda, if any; the Bid Proposal and attachments thereto; the Contract; the Notice of Award and Notice to Proceed; the payment and performance bonds; the General Conditions; the Special Conditions; the Project Plans and Specifications; any Change Orders; and any other documents which are clearly and unambiguously made part of the Contract Documents. The Contract Documents do not include documents provided “For Reference Only,” or documents that are intended solely to provide information regarding existing conditions.

Contract Price means the total compensation to be paid to Contractor for performance of the Work, as set forth in the Contract and as may be amended by Change Order or adjusted for an Allowance. The Contract Price is not subject to adjustment due to inflation or due to the increased cost of labor, material, supplies, or equipment following submission of the Bid Proposal.

Contract Time means the time specified for complete performance of the Work, as set forth in the Contract and as may be amended by Change Order.

Contractor (or You) means the individual, partnership, corporation, or joint venture that has signed the Contract with City to perform the Work.

CWA means the Community Workforce Agreement for the City.

Day means a calendar day unless otherwise specified.

Design Professional means the licensed individual(s) or firm(s) retained by City to provide architectural, engineering, or other design professional services for the Project. If no Design Professional has been retained for this Project, any reference to Design Professional is deemed to refer to the Engineer.

DIR means the California Department of Industrial Relations.

Drawings has the same meaning as Plans.

Engineer means the City Engineer for the City of Santa Rosa and his or her authorized delegees.

Excusable Delay is defined in Section 5.3(B), Excusable Delay.

Extra Work means new or unforeseen work added to the Project, as determined by the Engineer in his or her sole discretion, including Work that was not part of or incidental to the scope of the Work when the Contractor's bid was submitted; Work that is substantially different from the Work as described in the Contract Documents at bid time; or Work that results from a substantially differing and unforeseeable condition.

Final Completion means Contractor has fully completed all of the Work required by the Contract Documents to the City's satisfaction, including all punch list items and any required commissioning or training, and has provided the City with all required submittals, including the instructions and manuals, product warranties, and as-built drawings.

Final Payment means payment to Contractor of the unpaid Contract Price, including release of undisputed retention, less amounts withheld or deducted pursuant to the Contract Documents.

Furnish means to purchase and deliver for the Project.

Government Code Claim means a claim submitted pursuant to California Government Code § 900 et seq.

Hazardous Materials means any substance or material identified now or in the future as hazardous under any Laws, or any other substance or material that may be considered hazardous or otherwise subject to Laws governing handling, disposal, or cleanup.

Including, whether or not capitalized, means "including, but not limited to," unless the context clearly requires otherwise.

Inspector means the individual(s) or firm(s) retained or employed by City to inspect the workmanship, materials, and manner of construction of the Project and its components to ensure compliance with the Contract Documents and all Laws.

Install means to fix in place for materials, and to fix in place and connect for equipment.

Laws means all applicable local, state, and federal laws, regulations, rules, codes, ordinances, permits, orders, and the like enacted or imposed by or under the auspices of any governmental entity with jurisdiction over any of the Work or any performance of the Work, including health and safety requirements.

Materials Lab means City's Materials Engineering Laboratory, which may perform quality assurance functions for a Project relating to asphalt and concrete, including inspection and/or testing of workmanship, materials, and the manner of construction.

Non-Excusable Delay is defined in Section 5.3(D), Non-Excusable Delay.

Plans means the City-provided plans, drawings, details, or graphical depictions of the Project requirements, but does not include Shop Drawings.

Project means the public works project referenced in the Contract, as modified by any Project alternates elected by City, if any.

Project Manager means the individual designated by City to oversee and manage the Project on City's behalf and may include his or her authorized delegee(s) when the Project Manager is unavailable. If no Project Manager has been designated for this Project, any reference to Project Manager is deemed to refer to the Engineer.

Recoverable Costs is defined in Section 5.3(F), Recoverable Costs.

Request for Information or **RFI** means Contractor's written request for information about the Contract Documents, the Work or the Project, submitted to City in the manner and format specified by City.

Section, when capitalized in these General Conditions, means a numbered section or subsection of the General Conditions, unless the context clearly indicates otherwise.

Shop Drawings means drawings, plan details or other graphical depictions prepared by or on behalf of Contractor, and subject to City acceptance, which are intended to provide details for fabrication, installation, and the like, of items required by or shown in the Plans or Specifications.

Specialty Work means Work that must be performed by a specialized Subcontractor with the specified license or other special certification, and that the Contractor is not qualified to self-perform.

Specifications means the technical, text specifications describing the Project requirements, which are prepared for and incorporated into the Contract by or on behalf of City, and does not include the Contract, General Conditions or Special Conditions.

Subcontractor means an individual, partnership, corporation, or joint venture retained by Contractor directly or indirectly through a subcontract to perform a specific portion of the Work. The term Subcontractor applies to subcontractors of all tiers, unless otherwise indicated by the context. A third party such as a utility performing related work on the Project is not a Subcontractor, even if Contractor must coordinate its Work with the third party.

Technical Specifications has the same meaning as Specifications.

Water Department means the City of Santa Rosa Water Department.

Work means all of the construction and services necessary for or incidental to completing the Project in conformance with the requirements of the Contract Documents.

Work Day or **Working Day**, whether or not capitalized, means a weekday when the City is open for business, and does not include the following holidays observed by the City:

- (A) New Year's Day, January 1;
- (B) Martin Luther King Jr. Birthday, the third Monday in January;
- (C) President's Day, the third Monday in February;
- (D) Cesar Chavez Day, March 31;
- (E) Memorial Day, the last Monday in May;
- (F) Juneteenth, June 19;
- (G) Independence Day, July 4;
- (H) Labor Day, the first Monday in September;
- (I) Veterans Day, November 11;
- (J) Thanksgiving Day, the fourth Thursday in November;
- (K) The day after Thanksgiving Day; and
- (L) Christmas Day, December 25.

Worksite means the place or places where the Work is performed, which includes, but may extend beyond the Project site, including separate locations for staging, storage, or fabrication.

Article 2 - Roles and Responsibilities

2.1 City.

(A) **City Council.** The City Council has final authority in all matters affecting the Project, except to the extent it has delegated authority to the Engineer.

(B) **Engineer.** The Engineer, acting within the authority conferred by the City Council, is responsible for administration of the Project on behalf of City, including authority to provide directions to the Design Professional and to Contractor to ensure proper and timely completion of the Project. The Engineer's decisions are final and conclusive within the scope of his or her authority, including interpretation of the Contract Documents.

(C) **Project Manager.** The Project Manager assigned to the Project will be the primary point of contact for the Contractor and will serve as City's representative for daily administration of the Project on behalf of City. Unless otherwise specified, all of Contractor's communications to City (in any form) will go to or through the Project Manager. City reserves the right to reassign the Project Manager role at any time or to delegate duties to additional City representatives, without prior notice to or consent of Contractor.

(D) **Design Professional.** The Design Professional is responsible for the overall design of the Project and, to the extent authorized by City, may act on City's behalf to ensure performance of the Work in compliance with the Plans and Specifications, including any design changes authorized by Change Order. The Design Professional's duties may include review of Contractor's submittals, visits to any Worksite, inspecting the Work, evaluating test and inspection results, and participation in Project-related meetings, including any pre-construction conference, weekly meetings, and coordination meetings. The Design Professional's interpretation of the Plans or Specifications is final and conclusive.

2.2 Contractor.

(A) **General.** Contractor must provide all labor, materials, supplies, equipment, services, and incidentals necessary to perform and timely complete the Work in strict accordance with the Contract Documents, and in an economical and efficient manner in the best interests of City, and with minimal inconvenience to the public.

(B) **Responsibility for the Work and Risk of Loss.** Contractor is responsible for supervising and directing all aspects of the Work to facilitate the efficient and timely completion of the Work. Contractor is solely responsible for and required to exercise full control over the Work, including the construction means, methods, techniques, sequences, procedures, safety precautions and programs, and coordination of all portions of the Work with that of all other contractors and Subcontractors, except to the extent that the Contract Documents provide other specific instructions. Contractor's responsibilities extend to any plan, method or sequence suggested but not required by City or specified in the Contract Documents. From the date of commencement of the Work until either the date on which City formally accepts the Project or the effective date of termination of the Contract, whichever is later, Contractor bears all risks of injury or damage to the Work and the materials and equipment delivered to any Worksite, by any cause including fire, earthquake, wind, weather, vandalism, or theft, subject to the limitations of Laws, including Public Contract Code § 7105.

(C) **Project Administration.** Contractor must provide sufficient and competent administration, staff, and skilled workforce necessary to perform and timely complete the Work in accordance with the Contract Documents. Before starting the Work, Contractor must designate in writing and provide complete contact information, including telephone numbers and email address, for the officer or employee in Contractor's organization who is to serve as Contractor's

primary representative for the Project, and who has authority to act on Contractor's behalf. A Subcontractor may not serve as Contractor's primary representative.

(D) **On-Site Superintendent.** Contractor must, at all times during performance of the Work, provide a qualified and competent full-time superintendent acceptable to City, and assistants as necessary, who must be physically present at the Project site while any aspect of the Work is being performed. The superintendent must have full authority to act and communicate on behalf of Contractor, and Contractor will be bound by the superintendent's communications to City. City's approval of the superintendent is required before the Work commences. If City is not satisfied with the superintendent's performance, City may request a qualified replacement of the superintendent. Failure to comply may result in temporary suspension of the Work, at Contractor's sole expense and with no extension of Contract Time, until an approved superintendent is physically present to supervise the Work. Contractor must provide written notice to City, as soon as practicable, before replacing the superintendent.

(E) **Standards.** Contractor must, at all times, ensure that the Work is performed in an efficient, skillful manner following best practices and in full compliance with the Contract Documents, Laws, and applicable manufacturer's recommendations. Contractor has a material and ongoing obligation to provide true and complete information, to the best of its knowledge, with respect to all records, documents, or communications pertaining to the Project, including oral or written reports, statements, certifications, Change Order requests, or Claims.

(F) **Meetings.** Contractor, its project manager, superintendent and any primary Subcontractors requested by City, must attend and participate in a pre-construction conference, weekly Project progress meetings, and coordination meetings, as set forth herein.

(1) **Pre-Construction Conference.** City will designate a date and time for a pre-construction conference with Contractor following Contract execution. Project administration procedures and coordination between City and Contractor will be discussed. City will provide Contractor with meeting minutes covering the topics discussed after the Pre-Construction Conference. Contractor must present City with the following information or documents at the conference, unless otherwise specified by City, for City's review and acceptance before the Work commences:

- a. Name, 24-hour contact information, and qualifications of the proposed on-site superintendent;
- b. List of all key Project personnel and their complete contact information, including email addresses and telephone numbers during regular hours and after hours;
- c. Staging plans that identify the sequence of the Work, including any phases and alternative sequences or phases, with the goal of minimizing the impacts on residents, businesses and other operations in the Project vicinity;
- d. If required, traffic control plans associated with the staging plans that are signed and stamped by a licensed traffic engineer;
- e. Draft baseline schedule for the Work as required under Section 5.2, to be finalized within ten days after City issues the Notice to Proceed or as otherwise specified by City;
- f. Breakdown of lump sum bid items, to be used for determining the value of Work completed for future progress payments to Contractor;
- g. Schedule with list of Project submittals that require City review, and list of the proposed material suppliers;
- h. Plan for coordination with affected utility owner(s) and compliance with any related permit requirements;

i. Videotape and photographs recording the conditions throughout the pre-construction Project site, showing the existing improvements and current condition of the curbs, gutters, sidewalks, signs, landscaping, streetlights, structures near the Project such as building faces, canopies, shades and fences, and any other features within the Project area limits;

j. If requested by City, Contractor's cash flow projections; and

k. Any other documents specified by City.

(2) **Progress Meetings.** Contractor, its project manager, superintendent and any primary Subcontractors requested by City, must participate in weekly Project progress meetings scheduled with City.

(3) **Coordination Meetings.** If applicable, Contractor may also be required to participate in coordination meetings with other parties relating to other work being performed on or near the Project site or in relation to the Project, including work or activities performed by City, other contractors, or other utility owners.

(G) **Construction Records.** Contractor will maintain up-to-date, thorough, legible, and dated daily job reports, which document all significant activity on the Project for each day that Work is performed on the Project. The daily report for each day must include the number of workers at the Project site; primary Work activities; major deliveries; problems encountered, including injuries, if any; weather and site conditions; and delays, if any. Contractor will take date and time-stamped photographs to document general progress of the Project, including site conditions prior to construction activities, before and after photographs at offset trench laterals, existing improvements and utilities, damage and restoration. Contractor will maintain copies of all subcontracts, Project-related correspondence with Subcontractors, and records of meetings with Subcontractors. Upon request by the City, Contractor will permit review of and/or provide copies of any of these construction records.

(H) **Responsible Party.** Contractor is solely responsible to City for the acts or omissions of any Subcontractors, or any other party or parties performing portions of the Work or providing equipment, materials or services for or on behalf of Contractor or the Subcontractors. Upon City's written request, Contractor must promptly and permanently remove from the Project, at no cost to City, any employee or Subcontractor or employee of a Subcontractor who the Engineer has determined to be incompetent, intemperate or disorderly, or who has failed or refused to perform the Work as required under the Contract Documents.

(I) **Correction of Defects.** Contractor must promptly correct, at Contractor's sole expense, any Work that is determined by City to be deficient or defective in any way, including workmanship, materials, parts, or equipment. Workmanship, materials, parts, or equipment that do not conform to the requirements under the Contract Documents, as determined by City, will be considered defective and subject to rejection. Contractor must also promptly correct, at Contractor's sole expense, any Work performed beyond the lines and grades shown on the Plans or established by City, and any Extra Work performed without City's prior written approval. If requested by City in City's notice to correct, Contractor must submit a Work plan for correcting defective Work in advance of Contractor taking corrective action. If Contractor fails to correct or to take reasonable steps toward correcting defective Work within five days following notice from City, or within the time specified in City's notice to correct, City may elect to have the defective Work corrected by its own forces or by a third party, in which case the cost of correction will be deducted from the Contract Price. If City elects to correct defective Work due to Contractor's failure or refusal to do so, City or its agents will have the right to take possession of and use any equipment, supplies, or materials available at the Project site or any Worksite on City property, in order to effectuate the correction, at no extra cost to City. Contractor's warranty obligations under Section 11.2, Warranty, will not be waived nor limited by City's actions to correct defective Work under these circumstances. Alternatively, City may elect to retain defective Work, and deduct the difference in value, as determined by the Engineer, from payments otherwise due to Contractor.

This paragraph applies to any defective Work performed by Contractor during the one-year warranty period under Section 11.2.

(J) **Contractor's Records.** Contractor must maintain all of its records relating to the Project in any form, including paper documents, photos, videos, electronic records, approved samples, and the construction records required pursuant to paragraph (G), above. Project records subject to this provision include complete Project cost records, copies of the insurance policies and endorsements required by the Contract Documents, and records relating to preparation of Contractor's bid, including estimates, take-offs, and price quotes or bids.

(1) Contractor's cost records must include all supporting documentation, including original receipts, invoices, and payroll records, evidencing its direct costs to perform the Work, including, but not limited to, costs for labor, materials, and equipment. Each cost record should include, at a minimum, a description of the expenditure with references to the applicable requirements of the Contract Documents, the amount actually paid, the date of payment, and whether the expenditure is part of the original Contract Price, related to an executed Change Order, or otherwise categorized by Contractor as Extra Work. Contractor's failure to comply with this provision as to any claimed cost operates as a waiver of any rights to recover the claimed cost.

(2) Contractor must continue to maintain its Project-related records in an organized manner for a period of five years after City's acceptance of the Project or following Contract termination, whichever occurs first. Subject to prior notice to Contractor, City is entitled to inspect or audit any of Contractor's records relating to the Project during Contractor's normal business hours. Contractor's records may also be subject to examination and audit by the California State Auditor, pursuant to Government Code § 8546.7. The record-keeping requirements set forth in this subsection 2.2(J) will survive expiration or termination of the Contract.

(K) **Copies of Project Documents.** Contractor and its Subcontractors must keep copies, at the Project site, of all Work-related documents, including the Contract, permit(s), Plans, Specifications, addenda, Contract amendments, Change Orders, RFIs and RFI responses, Shop Drawings, as-built drawings, schedules, daily records, testing and inspection reports or results, and any related written interpretations. These documents must be available to City for reference at all times during construction of the Project.

(L) **Quality Control.** Contractor is responsible for developing, implementing, and maintaining a quality control plan that includes sampling, testing, and inspecting the Work to control material quality and to ensure that the Work satisfies the quality characteristics in the Contract Documents. Contractor must submit copies of the quality control plan to City, within two Working Days after the pre-construction conference, and make one copy available at each Worksite.

(1) **Records.** Contractor must prepare and maintain quality control records, including the names and qualifications of samplers, testers, and inspectors; testing laboratories' identification and certifications; testing equipment calibrations and certifications; inspection reports; sampling and testing records organized by date and type of material; test results with comparison of quality characteristic requirements; test results in relation to action and any suspension limits; and records of corrective actions and suspensions. Contractor will submit any quality control test data and test results to the Engineer within two Working Days following test completion. Contractor must immediately notify the Engineer of any noncompliant Work.

(2) **Quality Control Manager.** Unless otherwise specified in the Special Conditions or Specifications, before starting Work, Contractor will designate in writing, and provide complete contact information for, the quality control manager for the Project who will be responsible for receiving, reviewing, and approving all correspondence and submittals prior to submission to the City; signing and implementing Contractor's quality control

plan; and maintaining quality control records. The quality control manager must either be an employee of Contractor, or a Subcontractor retained solely to provide quality control services for the Project. The quality control manager must not be employed or compensated by a Subcontractor who will provide other Work for the Project.

(3) **Test Modifications.** The following specific tests are modified as follows: For California Test 216 (Relative Compaction), a mechanical compactor (Ploog Engineering Co. Model M 100 or equal) with a 10-pound hammer and split compaction molds must be used in lieu of the specified manual compaction equipment. For California Test 231 (Nuclear Gage Determination of In-Place Density), in-place density and relative compaction may be determined on the basis of individual test sites in lieu of the area concept at the discretion of the Engineer.

2.3 Subcontractors.

(A) **General.** All Work which is not performed by Contractor with its own forces must be performed by Subcontractors. City reserves the right to approve or reject any and all Subcontractors proposed to perform the Work, for reasons including the Subcontractor's poor reputation, lack of relevant experience, financial instability, and lack of technical ability or adequate trained workforce. Each Subcontractor must obtain a City business tax certificate before performing any Work.

(B) **Contractual Obligations.** Contractor must require each Subcontractor to comply with the provisions of the Contract Documents as they apply to the Subcontractor's portion(s) of the Work, including the generally applicable terms of the Contract Documents, and to likewise bind their subcontractors. Contractor will provide that the rights that each Subcontractor may have against any manufacturer or supplier for breach of warranty or guarantee relating to items provided by the Subcontractor for the Project, will be assigned to City. Nothing in these Contract Documents creates a contractual relationship between a Subcontractor and City, but City is deemed to be a third-party beneficiary of the contract between Contractor and each Subcontractor.

(C) **Termination.** If the Contract is terminated, each Subcontractor's agreement must be assigned by Contractor to City, subject to the prior rights of any surety, but only if and to the extent that City accepts, in writing, the assignment by written notification, and assumes all rights and obligations of Contractor pursuant to each such subcontract agreement.

(D) **Substitution of Subcontractor.** If Contractor requests substitution of a listed Subcontractor under Public Contract Code § 4107, Contractor is solely responsible for all costs City incurs in responding to the request, including legal fees and costs to conduct a hearing, and any increased subcontract cost to perform the Work that was to be performed by the listed Subcontractor. If City determines that a Subcontractor is unacceptable to City based on the Subcontractor's failure to satisfactorily perform its Work, or for any of the grounds for substitution listed in Public Contract Code § 4107(a), City may request removal of the Subcontractor from the Project. Upon receipt of a written request from City to remove a Subcontractor pursuant to this paragraph, Contractor will immediately remove the Subcontractor from the Project and, at no further cost to City, will either (1) self-perform the remaining Work to the extent that Contractor is duly licensed and qualified to do so, or (2) substitute a Subcontractor that is acceptable to City, in compliance with Public Contract Code § 4107, as applicable.

2.4 Coordination of Work.

(A) **Concurrent Work.** City reserves the right to perform, have performed, or permit performance of other work on or adjacent to the Project site while the Work is being performed for the Project. Contractor is responsible for coordinating its Work with other work being performed on or adjacent to the Project site, including by any City work forces or utility companies or agencies, and must avoid hindering, delaying, or interfering with the work of other contractors, individuals, or entities, and must ensure safe and reasonable site access and use as required or authorized by City. To the full extent permitted by law, Contractor must hold harmless and

indemnify City against any and all claims arising from or related to Contractor's avoidable, negligent, or willful hindrance of, delay to, or interference with the work of any City work forces, utility company or agency, or another contractor or subcontractor.

(B) **Coordination.** If Contractor's Work will connect or interface with work performed by others, Contractor is responsible for independently measuring and visually inspecting such work to ensure a correct connection and interface. Contractor is responsible for any failure by Contractor or its Subcontractors to confirm measurements before proceeding with connecting Work. Before proceeding with any portion of the Work affected by the construction or operations of others, Contractor must give the Project Manager prompt written notification of any defects Contractor discovers which will prevent the proper execution of the Work. Failure to give notice of any known or reasonably discoverable defects will be deemed acknowledgement by Contractor that the work of others is not defective and will not prevent the proper execution of the Work. Contractor must also promptly notify City if work performed by others, including work or activities performed by City's own forces, is operating to hinder, delay, or interfere with Contractor's timely performance of the Work. City reserves the right to backcharge Contractor for any additional costs incurred due to Contractor's failure to comply with the requirements in this Section 2.4.

2.5 Submittals. Unless otherwise specified, Contractor must submit to the Engineer for review and acceptance, all schedules, Shop Drawings, samples, product data, and similar submittals required by the Contract Documents, or upon request by the Engineer. Unless otherwise specified, all submittals, including Requests for Information, are subject to the general provisions of this Section, as well as specific submittal requirements that may be included elsewhere in the Contract Documents, including the Special Conditions or Specifications. The Engineer may require submission of a submittal schedule at or before a pre-construction conference, as may be specified in the Notice to Proceed.

(A) **General.** Contractor is responsible for ensuring that its submittals are accurate and conform to the Contract Documents.

(B) **Time and Manner of Submission.** Contractor must ensure that its submittals are prepared and delivered in a manner consistent with the current City-accepted schedule for the Work and within the applicable time specified in the Contract Documents, or if no time is specified, in such time and sequence so as not to delay the performance of the Work or completion of the Project. Contractor must provide submittals in electronic format, unless otherwise specified by the Engineer.

(C) **Required Contents.** Each submittal must be uniquely numbered and include the Project name and contract number, Contractor's name and address, the name and address of any Subcontractor or supplier involved with the submittal, the date, and references to applicable Specification section(s) and/or drawing and detail number(s). Submittal resubmissions must include a revision designation.

(D) **Required Corrections.** If corrections are required, Contractor must promptly make and submit any required corrections as specified in full conformance with the requirements of this Section, or other requirements that apply to that submittal. Except as required for corrections, Contractor will not make changes to a submittal upon resubmission. City reserves the right to reject a partial resubmission of a submittal.

(E) **Effect of Review and Acceptance.** Review and acceptance of a submittal by City will not relieve Contractor from complying with the requirements of the Contract Documents. Contractor is responsible for any errors in any submittal, and review or acceptance of a submittal by City is not an assumption of risk or liability by City.

(F) **Enforcement.** Any Work performed or any material furnished, installed, fabricated or used without City's prior acceptance of a required submittal is performed or provided at Contractor's risk, and Contractor may be required to bear the costs incident thereto, including the cost of removing and replacing such Work, repairs to other affected portions of the Work or

material, and the cost of additional time or services required of City, including costs for the Design Professional, Project Manager, Inspector, and Materials Lab.

(G) **Excessive RFIs.** A RFI will be considered excessive or unnecessary if City determines that the explanation or response to the RFI is clearly and unambiguously discernable from the Contract Documents. City's costs to review and respond to excessive or unnecessary RFIs may be deducted from payments otherwise due to Contractor.

- 2.6 Shop Drawings.** When Shop Drawings are required by the Specifications or requested by the Engineer, they must be prepared according to best practices at Contractor's expense. The Shop Drawings must be of a size and scale to clearly show all necessary details. Unless otherwise specified by City, Shop Drawings must be provided to the Engineer for review and acceptance at least 30 days before the Work will be performed. If City requires changes, the corrected Shop Drawings must be resubmitted to the Engineer for review within the time specified by the Engineer. For all Project components requiring Shop Drawings, Contractor will not furnish materials or perform any Work until the Shop Drawings for those components are accepted by City. Contractor is responsible for any errors or omissions in the Shop Drawings, shop fits and field corrections; any deviations from the Contract Documents; and for the results obtained by the use of Shop Drawings. Acceptance of Shop Drawings by City does not relieve Contractor of Contractor's responsibility.
- 2.7 Material List.** Unless otherwise specified by City, Contractor must submit to the Engineer, at or before the pre-construction conference, a list of all materials proposed for use in the Work and any supporting documentation and samples required by the Contract Documents and source of supply. For a material listed on the "Engineer's List of Approved Items," located in the Sewer and Water sections of the City Standards, Contractor must provide the name of the manufacturer and model and part number for each material proposed for the Work, unless the item has been replaced for the Project, as specifically set forth in the Contract Documents. For all other materials, Contractor must provide the name of the manufacturer, model and part number, and supporting documentation and samples that will enable the Engineer to evaluate the material.
- 2.8 Access to Work.** Contractor must afford prompt and safe access to any Worksite by City and its employees, agents, or consultants authorized by City; and upon request by City, Contractor must promptly arrange for City representatives to visit or inspect manufacturing sites or fabrication facilities for items to be incorporated into the Work.
- 2.9 Personnel.** Contractor and its Subcontractors must employ only competent and skillful personnel to perform the Work. Contractor and its Subcontractor's supervisors, security or safety personnel, and employees who have unescorted access to the Project site must possess proficiency in English sufficient to read, understand, receive, and implement oral or written communications or instructions relating to their respective job functions, including safety and security requirements. Upon written notification from the Engineer, Contractor and its Subcontractors must immediately discharge any personnel who are incompetent, disorderly, disruptive, threatening, abusive, or profane, or otherwise refuse or fail to comply with the requirements of the Contract Documents or Laws, including Laws pertaining to health and safety. Any such discharged personnel may not be re-employed or permitted on the Project in any capacity without City's prior written consent.

Article 3 - Contract Documents

3.1 Interpretation of Contract Documents.

(A) **Plans and Specifications.** The Plans and Specifications included in the Contract Documents are complementary. If Work is shown on one but not on the other, Contractor must perform the Work as though fully described on both, consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the indicated results. The Plans and Specifications are deemed to include and require everything necessary and reasonably incidental to completion of the Work, whether or not particularly mentioned or shown. Contractor must perform all Work and services and supply all things reasonably related to and inferable from the Contract Documents. In the event of a conflict between the Plans and Specifications, the

Specifications will control, unless the drawing(s) at issue are dated later than the Specification(s) at issue. Detailed drawings take precedence over general drawings, and large-scale drawings take precedence over smaller scale drawings. Any arrangement or division of the Plans and Specifications into sections is for convenience and is not intended to limit the Work required by separate trades. A conclusion presented in the Plans or Specifications is only a recommendation. Actual locations and depths must be determined by Contractor's field investigation. Contractor may request access to underlying or background information in City's possession that is necessary for Contractor to form its own conclusions.

(B) ***Duty to Notify and Seek Direction.*** If Contractor becomes aware of a changed condition in the Project, or of any ambiguity, conflict, inconsistency, discrepancy, omission, or error in the Contract Documents, including the Plans or Specifications, Contractor must promptly submit a Request for Information to the Engineer and wait for a response from City before proceeding further with the related Work. The RFI must notify City of the issue and request clarification, interpretation or direction. The Engineer's clarification, interpretation or direction will be final and binding on the Contractor. If Contractor proceeds with the related Work before obtaining the City's response, Contractor will be responsible for any resulting costs, including the cost of correcting any incorrect or defective Work that results. Timely submission of a clear and complete RFI is essential to avoiding delay. Delay resulting from Contractor's failure to submit a timely and complete RFI to the Engineer is Non-Excusable Delay. If Contractor believes that City's response to an RFI justifies a change to the Contract Price or Contract Time, Contractor must perform the Work as directed but may submit a timely Change Order request in accordance with the Contract Documents. (See Articles 5 and 6.)

(C) ***Figures and Dimensions.*** Figures control over scaled dimensions.

(D) ***Technical or Trade Terms.*** Any terms that have well-known technical or trade meanings will be interpreted in accordance with those meanings, unless otherwise specifically defined in the Contract Documents.

(E) ***Measurements.*** Contractor must verify all relevant measurements in the Contract Documents and at the Project site before ordering any material or performing any Work, and will be responsible for the correctness of those measurements or for costs that could have been avoided by independently verifying measurements.

(F) ***Compliance with Laws.*** The Contract Documents are intended to comply with Laws and will be interpreted to comply with Laws.

3.2 Order of Precedence. Information included in one Contract Document but not in another will not be considered a conflict or inconsistency. Unless otherwise specified in the Special Conditions, in case of any conflict or inconsistency among the Contract Documents, the following order of precedence will apply, beginning from highest to lowest, with the most recent version taking precedent over an earlier version:

- (A) Change Orders;
- (B) Addenda;
- (C) Contract;
- (D) Notice to Proceed;
- (E) Attachment B – Federal Contract Requirements (only if used);
- (F) Special Conditions;
- (G) General Conditions;
- (H) Payment and Performance Bonds;
- (I) Specifications;
- (J) Plans;
- (K) Notice of Award;
- (L) Notice Inviting Bids;
- (M) Attachment A – Federal Bidding Requirements (only if used);
- (N) Instructions to Bidders;
- (O) Community Workforce Agreement, if applicable;

- (P) Contractor's Bid Proposal and attachments;
- (Q) City Standards and City Specifications, as applicable; and
- (R) Any generic documents prepared by and on behalf of a third party, that were not prepared specifically for this Project, such as the Caltrans Standard Specifications, Caltrans Special Provisions, or Caltrans Standard Plans.

3.3 Caltrans Standard Specifications and Standard Plans. Any reference to or incorporation of the Standard Specifications of the State of California, Department of Transportation ("Caltrans"), including "Standard Specifications," "Caltrans Specifications," "State Specifications," or "CSS," means the most current edition of Caltrans' Standard Specifications, unless otherwise specified ("Caltrans Standard Specifications"), including the most current amendments and revisions as of the date that Contractor's bid was submitted for this Project. Any reference to or incorporation of Caltrans' Standard Plans means the most current edition of Caltrans' Standard Plans, unless otherwise specified ("Caltrans Standard Plans"), including the most current amendments or revisions as of the date that Contractor's bid was submitted for this Project. The following provisions apply to use of or reference to the Caltrans Standard Specifications, Special Provisions, or Caltrans Standard Plans:

(A) **Limitations.** The "Division I General Provisions" of the Caltrans Standard Specifications, i.e., sections 1 through 9, do not apply to these Contract Documents with the exception of any specific provisions, if any, which are expressly stated to apply to these Contract Documents. Unless otherwise specified in the Specifications, the remaining Divisions of the Caltrans Standard Specifications, i.e., Division II through Division XII, are applicable to the extent relevant to the Work and are subject to any modifications set forth in the Specifications. A specific reference in the Specifications to a section from the Caltrans Standard Specifications will not be construed as excluding other applicable sections from the Caltrans Standard Specifications.

(B) **Conflicts or Inconsistencies.** If there is a conflict or inconsistency between any provision in the Caltrans Standard Specifications or Special Provisions and a provision of these Contract Documents, as determined by City, the provision in the Contract Documents will govern.

(C) **Meanings.** Terms used in the Caltrans Standard Specifications or Special Provisions are to be interpreted as follows:

(1) Any reference to the "Engineer" or "Director" is deemed to mean the City Engineer.

(2) Any reference to the "Special Provisions" is deemed to mean the Special Conditions, unless the Caltrans Special Provisions are expressly included in the Contract Documents listed in Section 2 of the Contract.

(3) Any reference to the "Department" or "State" is deemed to mean City.

(4) Any reference to "Laboratory" is deemed to mean the Materials Lab, or such other laboratory as may be authorized by the City.

3.4 For Reference Only. Contractor is responsible for the careful review of any document, study, or report provided by City or appended to the Contract Documents solely for informational purposes and identified as "For Reference Only." Nothing in any document, study, or report so appended and identified is intended to supplement, alter, or void any provision of the Contract Documents. Contractor is advised that the City or its representatives may be guided by information or recommendations included in such reference documents, particularly when making determinations as to the acceptability of proposed materials, methods, or changes in the Work. Any record drawings or similar final or accepted drawings or maps that are not part of the Contract Documents are deemed to be For Reference Only. The provisions of the Contract Documents are not modified by any perceived or actual conflict with provisions in any document that is provided For Reference Only.

- 3.5 Current Versions.** Unless otherwise specified by the City, any reference to standard specifications, technical specifications, or any City or state codes or regulations means the latest specification, code, or regulation in effect on the date that bids were due.
- 3.6 Conformed Copies.** If City prepares a conformed set of the Contract Documents following award of the Contract, it will provide Contractor with two hard copy (paper) sets and one copy of the electronic file in PDF format. It is Contractor's responsibility to ensure that all Subcontractors, including fabricators, are provided with the conformed set of the Contract Documents at Contractor's sole expense.
- 3.7 Ownership.** No portion of the Contract Documents may be used for any purpose other than construction of the Project, without prior written consent from City. Contractor is deemed to have conveyed the copyright in any designs, drawings, specifications, Shop Drawings, or other documents (in paper or electronic form) developed by Contractor for the Project, and City will retain all rights to such works, including the right to possession.

Article 4 - Bonds, Indemnity, and Insurance

- 4.1 Payment and Performance Bonds.** Within ten days following issuance of the Notice of Award, Contractor is required to provide a payment bond and a performance bond, each in the penal sum of not less than 100% of the Contract Price, and each executed by Contractor and its surety using the bond forms included with the Contract Documents.
- (A) **Surety.** Each bond must be issued and executed by a surety admitted in California. If an issuing surety cancels the bond or becomes insolvent, within seven days following written notice from City, Contractor must substitute a surety acceptable to City. If Contractor fails to substitute an acceptable surety within the specified time, City may, at its sole discretion, withhold payment from Contractor until the surety is replaced to City's satisfaction, or terminate the Contract for default.
- (B) **Supplemental Bonds for Increase in Contract Price.** If the Contract Price increases during construction by five percent or more over the original Contract Price, Contractor must provide supplemental or replacement bonds within ten days of written notice from City pursuant to this Section, covering 100% of the increased Contract Price and using the bond forms included with the Contract Documents.
- 4.2 Indemnity.** To the fullest extent permitted by law, Contractor must indemnify, defend, and hold harmless City, its Council, officers, officials, employees, agents, volunteers, and consultants (individually, an "Indemnitee," and collectively the "Indemnitees") from and against any and all liability, loss, damage, claims, causes of action, demands, charges, fines, costs, and expenses (including, without limitation, attorney fees, expert witness fees, paralegal fees, fees and costs of litigation or arbitration, and fees and expenses incurred in enforcing this Section) (collectively, "Liability") of every nature arising out of or in connection with the acts or omissions of Contractor, its employees, Subcontractors, representatives, or agents, in bidding or performing the Work or in failing to comply with any obligation of Contractor under the Contract, except such Liability caused by the active negligence, sole negligence, or willful misconduct of an Indemnitee. This indemnity requirement applies to any Liability arising from alleged defects in the content or manner of submission of Contractor's bid for the Contract. Contractor's failure or refusal to timely accept a tender of defense pursuant to this Contract will be deemed a material breach of the Contract. City will timely notify Contractor upon receipt of any third-party claim relating to the Contract, as required by Public Contract Code § 9201. Contractor waives any right to express or implied indemnity against any Indemnitee. Contractor's indemnity obligations under this Contract will survive the expiration or any early termination of the Contract.
- 4.3 Insurance.** No later than ten days following issuance of the Notice of Award, Contractor must procure and provide proof of the insurance coverage required by this Section in the form of certificates and endorsements acceptable to City. The required insurance must cover the activities of Contractor and its Subcontractors relating to or arising from the performance of the Work. The required insurance must remain in full force and effect at all times during the period

covered by the Contract through the date of City's acceptance of the Project, except as specified for commercial general liability insurance in subsection (A)(1), below, which requires a longer duration. All required insurance must be issued by a company licensed to do business in the State of California, and each such insurer must have an A.M. Best's financial strength rating of "A-" or better and a financial size rating of "VII" or better. If Contractor fails to provide any of the required coverage in full compliance with the requirements of the Contract Documents, City may, at its sole discretion, purchase such coverage at Contractor's expense and deduct the cost from payments due to Contractor, or terminate the Contract for default. The procurement of the required insurance, or Contractor's failure to procure and maintain the required insurance, will not be construed to limit Contractor's liability under this Contract. The procurement of the required insurance will not be construed to fulfill Contractor's indemnification obligations under this Contract.

(A) ***Policies and Limits.*** The following insurance policies and limits are required for this Contract, unless otherwise specified in the Special Conditions:

(1) ***Commercial General Liability ("CGL") Insurance:*** The CGL insurance policy must be issued on an occurrence basis, written on a comprehensive general liability form with coverage at least as broad as ISO CG 00 01, and must include coverage for liability arising from Contractor's or its Subcontractor's acts or omissions in the performance of the Work, including contractor's protective coverage, contractual liability, products liability, completed operations, and broad form property damage, with limits of at least \$5,000,000 per occurrence and at least \$5,000,000 general aggregate. If insurance applies separately to a project/location, aggregate may be equal to per occurrence amount. The CGL insurance coverage may be arranged under a single policy for the full limits required or by a combination of underlying policies with the balance provided by excess or umbrella policies, provided each such policy complies with the requirements set forth in this Section, including required endorsements. The products liability and completed operations coverage must continue for a period of three years following City's acceptance of the Project.

(2) ***Automobile Liability Insurance:*** The automobile liability insurance policy must provide coverage of at least \$3,000,000 combined single-limit per accident for bodily injury, death, or property damage, including hired, owned, and non-owned auto liability. Coverage must be at least as broad as ISO Form Number CA 00 01 covering any auto (Code 1).

(3) ***Workers' Compensation Insurance and Employer's Liability:*** The workers' compensation and employer's liability insurance policy must comply with the requirements of the California Labor Code, providing coverage of at least \$1,000,000 or as otherwise required by statute, per accident for bodily injury or disease. If Contractor is self-insured, Contractor must provide its Certificate of Permission to Self-Insure, duly authorized by the DIR.

(4) ***Pollution Liability Insurance:*** The pollution liability insurance policy must provide coverage of at least \$1,000,000 per occurrence and \$2,000,000 aggregate for all loss arising out of claims for bodily injury, death, property damage, or environmental damage caused by pollution conditions resulting from the Work. If the Work involves lead-based paint or asbestos identification and/or remediation, the pollution liability insurance policy must not contain lead-based paint or asbestos exclusions. If the Work involves mold identification, the pollution liability policy must not contain a mold exclusion and the definition of "pollution" in the policy must include microbial matter, including mold.

(5) ***Builder's Risk Insurance:*** The builder's risk insurance policy must be issued on an occurrence basis, for all-risk or "all perils" coverage on a 100% completed value basis on the insurable portion of the Project for the benefit of City, without co-insurance provisions. Contractor must name City as loss payee.

(B) **Notice.** Each certificate of insurance must state that the coverage afforded by the policy or policies will not be reduced, cancelled or allowed to expire without at least 30 days prior written notice to City, unless due to non-payment of premiums, in which case ten days prior written notice must be made to City.

(C) **Waiver of Subrogation.** Each required policy must include an endorsement providing that the carrier will waive any right of subrogation it may have against City.

(D) **Required Endorsements.** The CGL policy, automobile liability policy, pollution liability policy, and builder's risk policy must include the following specific endorsements:

(1) The City of Santa Rosa, including its Council, officials, officers, employees, agents, volunteers and consultants (collectively, "Additional Insured") must be named as an additional insured for all liability arising out of the operations by or on behalf of the named insured, and the policy must protect the Additional Insured against any and all liability for personal injury, death or property damage or destruction arising directly or indirectly in the performance of the Contract. Coverage for an Additional Insured will not be limited to the Additional Insured's vicarious liability. The additional insured endorsement must be provided using ISO forms at least as broad as CG 20 10 04 13 or 20 38 04 13 (ongoing operations) and CG 20 37 04 13 (completed operations), or equivalent form(s) approved by the City.

(2) The inclusion of more than one insured will not operate to impair the rights of one insured against another, and the coverages afforded will apply as though separate policies have been issued to each insured.

(3) The insurance provided by Contractor is primary and no insurance held or owned by any Additional Insured may be called upon to contribute to a loss. This endorsement must be provided using ISO form CG 20 01 04 13 or an equivalent form approved by the City.

(4) This policy does not exclude explosion, collapse, underground excavation hazard, or removal of lateral support.

(E) **Contractor's Responsibilities.** This Section 4.3 establishes the minimum requirements for Contractor's insurance coverage in relation to this Project but is not intended to limit Contractor's ability to procure additional or greater coverage. Contractor is responsible for its own risk assessment and needs and is encouraged to consult its insurance provider to determine what coverage it may wish to carry beyond the minimum requirements of this Section. Contractor is solely responsible for the cost of its insurance coverage, including premium payments, deductibles, or self-insured retentions, and no Additional Insured will be responsible or liable for any of the cost of Contractor's insurance coverage. Contractor's insurance coverage applies to the full extent of the policies, and nothing contained herein will be construed to limit the application of such coverage.

(F) **Deductibles and Self-Insured Retentions.** Any deductibles or self-insured retentions that apply to the required insurance (collectively, "deductibles") in excess of \$10,000 are subject to approval by the City's Risk Manager, acting in his or her sole discretion, and must be declared by Contractor when it submits its certificates of insurance and endorsements pursuant to this Section 4.3. If the City's Risk Manager determines that the deductibles are unacceptably high, at City's option, Contractor must either reduce or eliminate the deductibles as they apply to City and all required Additional Insured; or must provide a financial guarantee, to City's satisfaction, guaranteeing payment of losses and related investigation, claim administration, and legal expenses.

(G) **Subcontractors.** Contractor must ensure that each Subcontractor is required to maintain the same insurance coverage required under this Section 4.3, with respect to its performance of Work on the Project, including those requirements related to the Additional

Insureds and waiver of subrogation, but excluding pollution liability or builder's risk insurance unless otherwise specified in the Special Conditions. A Subcontractor may be eligible for reduced insurance coverage or limits, but only to the extent approved in writing in advance by the City's Risk Manager. Contractor must confirm that each Subcontractor has complied with these insurance requirements before the Subcontractor is permitted to begin Work on the Project. Upon request by the City, Contractor must provide certificates and endorsements submitted by each Subcontractor to prove compliance with this requirement. The insurance requirements for Subcontractors do not replace or limit the Contractor's insurance obligations.

Article 5 - Contract Time

5.1 Time is of the Essence. Time is of the essence in Contractor's performance and completion of the Work, and Contractor must diligently prosecute the Work and complete it within the Contract Time.

(A) **General.** Contractor must commence the Work on the date indicated in the Notice to Proceed and must fully complete the Work in strict compliance with all requirements of the Contract Documents and within the Contract Time. Contractor may not begin performing the Work before the date specified in the Notice to Proceed.

(B) **Authorization.** Contractor is not entitled to compensation or credit for any Work performed before the date specified in the Notice to Proceed, with the exception of any schedules, submittals, or other requirements, if any, that must be provided or performed before issuance of the Notice to Proceed.

(C) **Rate of Progress.** Contractor and its Subcontractors must, at all times, provide workers, materials, and equipment sufficient to maintain the rate of progress necessary to ensure full completion of the Work within the Contract Time. Contractor will diligently prosecute the Work to minimize the public's exposure to construction activities. If City determines that Contractor is failing to prosecute the Work at a sufficient rate of progress, City may, in its sole discretion, direct Contractor to provide additional workers, materials, or equipment, or to work additional hours or days without additional cost to City, in order to achieve a rate of progress satisfactory to City. If Contractor fails to comply with City's directive in this regard, City may, at Contractor's expense, separately contract for additional workers, materials, or equipment or use City's own forces to achieve the necessary rate of progress. Alternatively, City may terminate the Contract based on Contractor's default.

5.2 Schedule Requirements. Contractor must prepare all schedules using standard, commercial scheduling software acceptable to the Engineer, and must provide the schedules in electronic and paper form as requested by the Engineer. Contractor must provide the Engineer with a license for use of Contractor's scheduling software, unless otherwise specified by the Engineer. In addition to the general scheduling requirements set forth below, Contractor must also comply with any scheduling requirements included in the Special Conditions or in the Technical Specifications.

(A) **Baseline (As-Planned) Schedule.** Within ten calendar days following City's issuance of the Notice to Proceed (or as otherwise specified in the Notice to Proceed), Contractor must submit to City for review and acceptance a baseline (as-planned) schedule using critical path methodology showing in detail how Contractor plans to perform and fully complete the Work within the Contract Time, including labor, equipment, materials, and fabricated items. The baseline schedule must show the order of the major items of Work and the dates of start and completion of each item, including when the materials and equipment will be procured. The schedule must also include the work of all trades, reflecting anticipated labor or crew hours and equipment loading for the construction activities, and must be sufficiently comprehensive and detailed to enable progress to be monitored on a day-by-day basis. For each activity, the baseline schedule must be dated, provided in the format specified in the Contract Documents or as required by City, and must include, at a minimum, a description of the activity, the start and completion dates of the activity, and the duration of the activity.

(1) **Specialized Materials Ordering.** Within five calendar days following issuance of the Notice to Proceed, Contractor must order any specialized material or equipment for the Work that is not readily available from material suppliers. Contractor must also retain documentation of the purchase order date(s).

(2) **High Dollar or Long Duration Projects.** In addition to the requirements set forth above, if the Contract Price is \$5,000,000 or more or if the Contract Time is 100 Working Days or more, Contractor's baseline (as-planned) schedule must include the following: the start and completion dates for submittal development, submittal review, milestones and constraints, equipment and plant setup, interfaces with outside entities, erection and removal of falsework and shoring, test periods, major traffic stage change, and final cleanup; logical links between time-scaled Work activities; controlling activities; at least 50 but no more than 500 activities, unless otherwise specified or authorized by the Engineer; alphanumeric activity identification and activity description system for labeling Work activities; identification code for each activity for responsibility, stage, Work shifts, location, and bid items; activity durations of at least one Working Day and no more than 20 Working Days for each activity, unless otherwise authorized by the Engineer; and float as the predecessor activity to Final Completion. Each activity description must indicate its associated scope or location of Work.

(B) **City's Review of Schedules.** City will review and may note exceptions to the baseline schedule, and to the progress schedules submitted as required below, to assure completion of the Work within the Contract Time. Contractor is solely responsible for resolving any exceptions noted in a schedule and, within seven days, must correct the schedule to address the exceptions. City's review or acceptance of Contractor's schedules will not operate to waive or limit Contractor's duty to complete the Project within the Contract Time, nor to waive or limit City's right to assess liquidated damages for Contractor's unexcused failure to do so.

(C) **Progress Schedules.** After City accepts the final baseline schedule with no exceptions, Contractor must submit an updated progress schedule and three-week look-ahead schedule, in the format specified by City, for review and acceptance with each application for a progress payment, or when otherwise specified by City, until completion of the Work. The updated progress schedule must: show how the actual progress of the Work as constructed to date compares to the baseline schedule; reflect any proposed changes in the construction schedule or method of operations, including to achieve Project milestones within the Contract Time; and identify any actual or potential impacts to the critical path. Contractor must also submit periodic reports to City of any changes in the projected material or equipment delivery dates for the Project.

(1) **Float.** The progress schedule must show early and late completion dates for each task. The number of days between those dates will be designated as the "float." Any float belongs to the Project and may be allocated by the Engineer to best serve timely completion of the Project.

(2) **Failure to Submit Schedule.** Reliable, up-to-date schedules are essential to efficient and cost-effective administration of the Project and timely completion. If Contractor fails to submit a schedule within the time periods specified in this Section or submits a schedule to which City has noted exceptions that are not corrected, City may withhold up to five percent from payment(s) otherwise due to Contractor until the exceptions are resolved, the schedule is corrected and resubmitted, and City has accepted the schedule. In addition, Contractor's failure to comply with the schedule requirements in this Section 5.2 will be deemed a material default and a waiver of any claims for Excusable Delay or loss of productivity arising during any period when Contractor is out of compliance, subject only to the limits of Public Contract Code § 7102.

(D) **Recovery Schedule.** If City determines that the Work is more than one week behind schedule, within seven days following written notice of such determination, Contractor must submit a recovery schedule, showing how Contractor intends to perform and complete the Work within the Contract Time, based on actual progress to date.

(E) **Effect of Acceptance.** Contractor and its Subcontractors must perform the Work in accordance with the most current City-accepted schedule unless otherwise directed or approved by City. If Contractor wants to perform non-critical Work activities that are out of sequence with the current City-accepted schedule, Contractor must notify and request approval from the Engineer in advance of performance of any such activities. Performance of any such Work must not impact the critical path Work activities. City's acceptance of a schedule does not operate to extend the time for completion of the Work or any component of the Work and will not affect City's right to assess liquidated damages for Contractor's unexcused delay in completing the Work within the Contract Time.

(F) **Posting.** Contractor must at all times prominently post a copy of the most current City-accepted progress or recovery schedule in its on-site office.

(G) **Reservation of Rights.** City reserves the right to direct the sequence in which the Work must be performed or to make changes in the sequence of the Work in order to facilitate the performance of work by City or others, to facilitate City's use of its property, or to minimize the public's exposure to construction activities. The Contract Time or Contract Price may be adjusted to the extent such changes in sequence actually increase or decrease Contractor's time or cost to perform the Work.

(H) **Authorized Working Days and Times.** Contractor is limited to working Monday through Friday, excluding holidays observed by City, during City's normal business hours, except as provided in the Special Conditions or as authorized in writing by City. City reserves the right to charge Contractor for additional costs incurred by City due to Work performed on days or during hours not expressly authorized in the Contract Documents, including reimbursement of costs incurred for inspection, testing, and construction management services.

5.3 Delay and Extensions of Contract Time.

(A) **Notice of Delay.** If Contractor becomes aware of any actual or potential delay affecting the critical path, Contractor must promptly notify the Engineer in writing, regardless of the nature or cause of the delay, so that City has a reasonable opportunity to mitigate or avoid the delay.

(B) **Excusable Delay.** The Contract Time may be extended if Contractor encounters "Excusable Delay," which is an unavoidable delay in completing the Work within the Contract Time due to causes completely beyond Contractor's control, and which Contractor could not have avoided or mitigated through reasonable care, planning, foresight, or diligence, provided that Contractor is otherwise fully performing its obligations under the Contract Documents. Grounds for Excusable Delay may include fire, natural disasters including earthquake or unusually severe weather, acts of terror or vandalism, epidemic, unforeseeable adverse government actions, unforeseeable actions of third parties, encountering unforeseeable hazardous materials, unforeseeable site conditions, or suspension for convenience under Article 13. The Contract Time will not be extended based on circumstances which will not unavoidably delay completing the Work within the Contract Time based on critical path analysis.

(C) **Weather Delays.** A "Weather Delay Day" is a Working Day during which Contractor and its forces, including Subcontractors, are unable to perform more than 40% of the critical path Work scheduled for that day due to adverse weather conditions which impair the ability to safely or effectively perform the scheduled critical path Work that day. Adverse weather conditions may include rain, saturated soil, and Project site clean-up required due to adverse weather. Determination of what constitutes critical path Work scheduled for that day will be based on the most current, City-approved schedule. Contractor will be entitled to a non-compensable extension of the Contract Time for each Weather Delay Day in excess of the normal Weather Delay Days

within a given month as determined by reliable records, including monthly rainfall averages, for the preceding ten years (or as otherwise specified in the Special Conditions or Specifications).

(1) Contractor must fully comply with the applicable procedures in Articles 5 and 6 of the General Conditions regarding requests to modify the Contract Time.

(2) Contractor will not be entitled to an extension of time for a Weather Delay Day to the extent Contractor is responsible for concurrent delay on that day.

(3) Contractor must take reasonable steps to mitigate the consequences of Weather Delay Days, including prudent workforce management and protecting the Work, Project Site, materials, and equipment.

(D) **Non-Excusable Delay.** Delay which Contractor could have avoided or mitigated through reasonable care, planning, foresight, or diligence is "Non-Excusable Delay." Contractor is not entitled to an extension of Contract Time or any compensation for Non-Excusable Delay, or for Excusable Delay that is concurrent with Non-Excusable Delay. Non-Excusable Delay includes delay caused by:

(1) weather conditions which are normal for the location of the Project, as determined by reliable records, including monthly rainfall averages, for the preceding ten years;

(2) Contractor's failure to order equipment and materials sufficiently in advance of the time needed for completion of the Work within the Contract Time;

(3) Contractor's failure to provide adequate notification to utility companies or agencies for connections or services necessary for completion of the Work within the Contract Time;

(4) foreseeable conditions which Contractor could have ascertained from reasonably diligent inspection of the Project site or review of the Contract Documents or other information provided or available to Contractor;

(5) Contractor's failure, refusal, or financial inability to perform the Work within the Contract Time, including insufficient funds to pay its Subcontractors or suppliers;

(6) performance or non-performance by Contractor's Subcontractors or suppliers;

(7) the time required to respond to excessive RFIs (see Section 2.5(G));

(8) delayed submission of required submittals, or the time required for correction and resubmission of defective submittals;

(9) time required for repair of, re-testing, or re-inspection of defective Work;

(10) enforcement of Laws by City, or outside agencies with jurisdiction over the Work; or

(11) City's exercise or enforcement of any of its rights or Contractor's duties pursuant to the Contract Documents, including correction of defective Work, extra inspections or testing due to non-compliance with Contract requirements, safety compliance, environmental compliance, or rejection and return of defective or deficient submittals.

(E) **Compensable Delay.** Pursuant to Public Contract Code § 7102, in addition to entitlement to an extension of Contract Time, Contractor is entitled to compensation for costs incurred due to delay caused solely by City, when that delay is unreasonable under the circumstances involved and not within the contemplation of the parties ("Compensable Delay"). Contractor is not entitled to an extension of Contract Time or recovery of costs for Compensable Delay that is concurrent with Non-Excusable Delay. Delay due to Weather Delay Days in excess

of normal for a given month, as set forth in Section 5.3(C), is not Compensable Delay, and will only entitle Contractor to an extension of time commensurate with the time lost due to such delay.

(F) **Recoverable Costs.** Contractor is not entitled to compensation for Excusable Delay unless it is Compensable Delay, as defined above. Contractor is entitled to recover only the actual, direct, reasonable, and substantiated costs ("Recoverable Costs") for each working day that the Compensable Delay prevents Contractor from proceeding with more than 50% of the critical path Work scheduled for that day, based on the most recent progress schedule accepted by City. Recoverable Costs will not include home office overhead or lost profit.

(G) **Request for Extension of Contract Time or Recoverable Costs.** A request for an extension of Contract Time or any associated Recoverable Costs must be submitted in writing to City within 14 calendar days of the date the delay is first encountered, even if the duration of the delay is not yet known at that time, or any entitlement to the Contract Time extension or to the Recoverable Costs will be deemed waived. In addition to complying with the requirements of this Article 5, the request must be submitted in compliance with the Change Order request procedures in Article 6 below. Strict compliance with these requirements is necessary to ensure that any delay or consequences of delay may be mitigated as soon as possible, and to facilitate cost-efficient administration of the Project and timely performance of the Work. Any request for an extension of Contract Time or Recoverable Costs that does not strictly comply with all of the requirements of Article 5 and Article 6 will be deemed waived.

(1) **Required Contents.** The request must include a detailed description of the cause(s) of the delay and must also describe the measures that Contractor has taken to mitigate the delay and/or its effects, including efforts to mitigate the cost impact of the delay, such as by workforce management or by a change in sequencing. If the delay is still ongoing at the time the request is submitted, the request should also include Contractor's plan for continued mitigation of the delay or its effects.

(2) **Delay Days and Costs.** The request must specify the number of days of Excusable Delay claimed or provide a realistic estimate if the duration of the delay is not yet known. If Contractor believes it is entitled to Recoverable Costs for Compensable Delay, the request must specify the amount and basis for the Recoverable Costs that are claimed or provide a realistic estimate if the amount is not yet known. Any estimate of delay duration or cost must be updated in writing and submitted with all required supporting documentation as soon as the actual time and cost is known. The maximum extension of Contract Time will be the number of days, if any, by which an Excusable Delay or a Compensable Delay exceeds any concurrent Non-Excusable Delay. Contractor is entitled to an extension of Contract Time, or compensation for Recoverable Costs, only if, and only to the extent that, such delay will unavoidably delay Final Completion.

(3) **Supporting Documentation.** The request must also include any and all supporting documentation necessary to evidence the delay and its actual impacts, including scheduling and cost impacts with a time impact analysis using critical path methodology and demonstrating the unavoidable delay to Final Completion. The time impact analysis must be submitted in a form or format acceptable to City.

(4) **Burden of Proof.** Contractor has the burden of proving that: the delay was an Excusable Delay or Compensable Delay, as defined above; Contractor has fully complied with its scheduling obligations in Section 5.2, Schedule Requirements; Contractor has made reasonable efforts to mitigate the delay and its schedule and cost impacts; the delay will unavoidably result in delaying Final Completion; and any Recoverable Costs claimed by Contractor were actually incurred and were reasonable under the circumstances.

(5) **Legal Compliance.** Nothing in this Section 5.3 is intended to require the waiver, alteration, or limitation of the applicability of Public Contract Code § 7102.

(6) *No Waiver.* Any grant of an extension of Contract Time, or compensation for Recoverable Costs due to Compensable Delay, will not operate as a waiver of City's right to assess liquidated damages for Non-Excusable Delay.

(7) *Dispute Resolution.* In the event of a dispute over entitlement to an extension of Contract Time or compensation for Recoverable Costs, Contractor may not stop Work pending resolution of the dispute, but must continue to comply with its duty to diligently prosecute the performance and timely completion of the Work. Contractor's sole recourse for an unresolved dispute based on City's rejection of a Change Order request for an extension of Contract Time or compensation for Recoverable Costs is to comply with the dispute resolution provisions set forth in Article 12 below.

5.4 Liquidated Damages. It is expressly understood that if Final Completion is not achieved within the Contract Time, City will suffer damages from the delay that are difficult to determine and accurately specify. Pursuant to Public Contract Code § 7203, if Contractor fails to achieve Final Completion within the Contract Time due to Contractor's Non-Excusable Delay, City will charge Contractor in the amount specified in the Contract for each calendar day that Final Completion is delayed beyond the Contract Time, as liquidated damages and not as a penalty. Any waiver of accrued liquidated damages, in whole or in part, is subject to approval of the City Council or its authorized delegate.

(A) **Liquidated Damages.** Liquidated damages will not be assessed for any Excusable Delay or Compensable Delay, as set forth above.

(B) **Milestones.** Liquidated damages may also be separately assessed for failure to meet milestones specified elsewhere in the Contract Documents.

(C) **Setoff.** City is entitled to deduct the amount of liquidated damages assessed against any payments otherwise due to Contractor, including progress payments, Final Payment, or unreleased retention. If there are insufficient Contract funds remaining to cover the full amount of liquidated damages assessed, City is entitled to recover the balance from Contractor or its performance bond surety.

(D) **Occupancy or Use.** Occupancy or use of the Project in whole or in part prior to Final Completion does not constitute City's acceptance of the Project and will not operate as a waiver of City's right to assess liquidated damages for Contractor's Non-Excusable Delay in achieving Final Completion.

(E) **Other Remedies.** City's right to liquidated damages under this Section applies only to damages arising from Contractor's Non-Excusable Delay or failure to complete the Work within the Contract Time. City retains its right to pursue all other remedies under the Contract for other types of damage, including damage to property or persons, costs or diminution in value from defective materials or workmanship, costs to repair or complete the Work, or other liability caused by Contractor.

Article 6 - Contract Modification

6.1 Contract Modification. Subject to the limited exception set forth in subsection (D) below, any change in the Work or the Contract Documents, including the Contract Price or Contract Time, will not be a valid and binding change to the Contract unless it is formalized in a Change Order, including a "no-cost" Change Order or a unilateral Change Order. Changes in the Work pursuant to this Article 6 will not operate to release, limit, or abridge Contractor's warranty obligations pursuant to Article 11 or any obligations of Contractor's bond sureties.

(A) **City-Directed Changes.** City may direct changes in the scope or sequence of Work or the requirements of the Contract Documents, without invalidating the Contract. Such changes may include Extra Work as set forth in subsection (C) below, or deletion or modification of portions of the Work. Contractor must promptly comply with City-directed changes in the Work in

accordance with the original Contract Documents, even if Contractor and City have not yet reached agreement as to adjustments to the Contract Price or Contract Time for the change in the Work or for the Extra Work. Contractor is not entitled to extra compensation for cost savings resulting from "value engineering" pursuant to Public Contract Code § 7101, except to the extent authorized in advance by City in writing, and subject to any applicable procedural requirements for submitting a proposal for value engineering cost savings.

(B) **Disputes.** In the event of a dispute over entitlement to or the amount of a change in Contract Time or a change in Contract Price related to a City-directed change in the Work, Contractor must perform the Work as directed and may not delay its Work or cease Work pending resolution of the dispute, but must continue to comply with its duty to diligently prosecute the performance and timely completion of the Work, including the Work in dispute. Likewise, in the event that City and Contractor dispute whether a portion or portions of the Work are already required by the Contract Documents or constitute Extra Work, or otherwise dispute the interpretation of any portion(s) of the Contract Documents, Contractor must perform the Work as directed and may not delay its Work or cease Work pending resolution of the dispute, but must continue to comply with its duty to diligently prosecute the performance and timely completion of the Work, including the Work in dispute, as directed by City. If Contractor refuses to perform the Work in dispute, City may, acting in its sole discretion, elect to delete the Work from the Contract and reduce the Contract Price accordingly, and self-perform the Work or direct that the Work be performed by others. Alternatively, City may elect to terminate the Contract for convenience or for cause. Contractor's sole recourse for an unresolved dispute related to changes in the Work or performance of any Extra Work is to comply with the dispute resolution provisions set forth in Article 12, below.

(C) **Extra Work.** City may direct Contractor to perform Extra Work related to the Project. Contractor must promptly perform any Extra Work as directed or authorized by City in accordance with the original Contract Documents, even if Contractor and City have not yet reached agreement on adjustments to the Contract Price or Contract Time for such Extra Work. If Contractor believes it is necessary to perform Extra Work due to changed conditions, Contractor must notify the Engineer in writing, within one Working Day following the date the Contractor first encounters the circumstances giving rise to Contractor's contention that Extra Work is necessary. Contractor's written notice must specifically identify the Extra Work and the reason(s) the Contractor believes it is Extra Work. This notification requirement does not constitute a Change Order request pursuant to Section 6.2, below. Contractor must maintain detailed daily records that itemize the cost of each element of Extra Work, and sufficiently distinguish the direct cost of the Extra Work from the cost of other Work performed. For each day that Contractor performs Extra Work, or Work that Contractor contends is Extra Work, Contractor must submit, by no later than close of business on that same Working Day, a daily report of the Extra Work performed that day, signed by the City and Contractor, identifying the labor, materials, and equipment used in the Extra Work ("Extra Work Report"). The Engineer may make any adjustments to Contractor's Extra Work Report(s) based on the Engineer's records of the Work. The Extra Work Report enables the parties to document and track the Extra Work, or Work that the Contractor contends is Extra Work. City's signature on the Extra Work Report is intended solely to document City's receipt of the Extra Work Report; it does not constitute any acknowledgement, acceptance, or approval of the Extra Work by City. To request compensation for Extra Work, Contractor must comply with the requirements in Section 6.2, below, including submission of the Extra Work Reports and a breakdown of the costs related to the Extra Work, together with copies of certified payroll, invoices, and other documentation substantiating the costs. Failure to submit the Extra Work Report by close of business on the same Working Day as the Extra Work is deemed a full and complete waiver for any change in the Contract Price or Contract Time for any Extra Work performed that day.

(D) **Minor Changes and RFIs.** Minor field changes, including RFI replies from City, that do not affect the Contract Price or Contract Time and that are approved by the Engineer acting within his or her scope of authority, do not require a Change Order. By executing an RFI reply from City, Contractor agrees that it will perform the Work as clarified therein, with no change to the Contract Price or Contract Time.

(E) **Remedy for Non-Compliance.** Contractor's failure to promptly comply with a City-directed change is deemed a material breach of the Contract, and in addition to all other remedies available to it, City may, at its sole discretion, hire another contractor or use its own forces to complete the disputed Work at Contractor's sole expense, and may deduct the cost from the Contract Price.

6.2 Contractor Change Order Requests. Contractor must submit a request or proposal for a change in the Work, compensation for Extra Work, or a change in the Contract Price or Contract Time as a written Change Order request or proposal.

(A) **Time for Submission.** Any request for a change in the Contract Price or the Contract Time must be submitted in writing to the Engineer within 14 calendar days of the date that Contractor first encounters the circumstances, information or conditions giving rise to the Change Order request, even if the total amount of the requested change in the Contract Price or impact on the Contract Time is not yet known at that time. If City requests that Contractor propose the terms of a Change Order, unless otherwise specified in City's request, Contractor must provide the Engineer with a written proposal for the change in the Contract Price or Contract Time within five working days of receiving City's request, in a form satisfactory to the Engineer.

(B) **Required Contents.** Any Change Order request or proposal submitted by Contractor must include a complete breakdown of actual or estimated costs and credits, and must itemize labor, materials, equipment, taxes, insurance, subcontract amounts, and, if applicable, Extra Work Reports. Any estimated cost must be updated in writing as soon as the actual amount is known.

(C) **Required Documentation.** All claimed costs must be fully documented, and any related request for an extension of time or delay-related costs must be included at that time and in compliance with the requirements of Article 5 of the General Conditions. Upon request, Contractor must permit City to inspect its original and unaltered bidding records, subcontract agreements, subcontract change orders, purchase orders, invoices, or receipts associated with the claimed costs.

(D) **Required Form.** Contractor must use City's form(s) for submitting all Change Order requests or proposals, unless otherwise specified by City.

(E) **Certification.** All Change Order requests must be signed by Contractor and must include the following certification:

"The undersigned Contractor certifies under penalty of perjury that its statements and representations in this Change Order request are true and correct. Contractor warrants that this Change Order request is comprehensive and complete as to the Work or changes referenced herein, and agrees that any known or foreseeable costs, expenses, or time extension requests not included herein, are deemed waived."

6.3 Adjustments to Contract Price. The amount of any increase or decrease in the Contract Price will be determined based on one of the following methods listed below, in the order listed with unit pricing taking precedence over the other methods. Markup applies only to City-authorized time and material Work and does not apply to any other payments to Contractor. For Work items or components that are deleted in their entirety, Contractor will only be entitled to compensation for those direct, actual, and documented costs (including restocking fees), reasonably incurred before Contractor was notified of the City's intent to delete the Work, with no markup for overhead, profit, or other indirect costs.

(A) **Unit Pricing.** Amounts previously provided by Contractor in the form of unit prices, either in a bid schedule or in a post-award schedule of values pursuant to Section 8.1, Schedule of Values, will apply to determine the price for the affected Work, to the extent applicable unit prices have been provided for that type of Work. No additional markup for overhead, profit, or other indirect costs will be added to the calculation.

(B) **Lump Sum.** A mutually agreed upon, all-inclusive lump sum price for the affected Work with no additional markup for overhead, profit, or other indirect costs.

(C) **Time and Materials.** On a time and materials basis, if and only to the extent compensation on a time and materials basis is expressly authorized by City in advance of Contractor's performance of the Work and subject to any not-to-exceed limit. Time and materials compensation for increased costs or Extra Work (but not decreased costs or deleted Work) will include allowed markup for overhead, profit, and other indirect costs, calculated as the total of the following sums, the cumulative total of which may not exceed the maximum markup rate of 15%:

(1) All direct labor costs provided by the Contractor, excluding superintendence, project management, or administrative costs, plus 15% markup;

(2) All direct material costs provided by the Contractor, including sales tax, plus 15% markup;

(3) All direct plant and equipment rental costs provided by the Contractor, plus 15% markup;

(4) All direct additional subcontract costs plus 10% markup for Work performed by Subcontractors; and

(5) Increased bond and insurance premium costs computed at 1.5% of the total of the previous four sums.

6.4 Unilateral Change Order. If the parties dispute the terms of a proposed Change Order, including disputes over the amount of compensation or extension of time that Contractor has requested, the value of deleted or changed Work, what constitutes Extra Work, or quantities used, City may elect to issue a unilateral Change Order, directing performance of the Work, and authorizing a change in the Contract Price or Contract Time for the adjustment to compensation or time that the City believes is merited. Contractor's sole recourse to dispute the terms of a unilateral Change Order is to submit a timely Claim pursuant to Article 12, below.

6.5 Non-Compliance Deemed Waiver. Contractor waives its entitlement to any increase in the Contract Price or Contract Time if Contractor fails to fully comply with the provisions of this Article. Contractor will not be paid for unauthorized Extra Work.

Article 7 - General Construction Provisions

7.1 Permits, Fees, Licenses, Certificates, and Taxes.

(A) **Fees, Licenses, Certificates, and Permits.** Contractor must obtain and pay for all fees, licenses, and certificates required to perform the Work, including a City business tax certificate. Contractor must obtain all permits required to perform the Work including a Caltrans Encroachment Permit necessary to implement traffic control measures shown in the Plans. Contractor is not responsible for the fees associated with obtaining permits unless otherwise specified in the Special Conditions or Specifications. Contractor must cooperate with and provide notifications to all government agencies with jurisdiction over the Project, as may be required. Contractor must provide City with copies of all records of permits and permit applications, payment of required fees, and any licenses and certificates required for the Work.

(B) **Taxes.** Contractor must pay for all taxes on labor, material, and equipment, except Federal Excise Tax to the extent that City is exempt from Federal Excise Tax.

7.2 Temporary Facilities. Contractor must provide, at Contractor's sole expense, any and all temporary facilities for the Project, including an onsite staging area for materials and equipment, a field office, sanitary facilities, utilities, storage, scaffolds, barricades, walkways, and any other temporary structure required to safely perform the Work along with any incidental utility services. The location of all temporary facilities must be approved by the City prior to installation.

Temporary facilities must be safe and adequate for the intended use and installed and maintained in accordance with Laws and the Contract Documents. Contractor must fence and screen the Project site and, if applicable, any separate Worksites, including the staging area, and its operation must minimize inconvenience to neighboring properties. Additional provisions pertaining to temporary facilities are set forth in this Article 7 and may also be included in the Specifications or Special Conditions.

(A) **Utilities.** Contractor must install and maintain the power, water, sewer, and all other utilities required for the Project site and performance of the Work, including the piping, wiring, internet and Wi-Fi connections, and any related equipment necessary to maintain the temporary facilities. Contractor may obtain water from the City's water system or from a source other than City's water system, if approved in advance by the Engineer. Before obtaining water from the City's water system, Contractor must obtain a Water Use Permit from the Water Department and rent a hydrant or bridge meter. Contractor is responsible for the cost of all water and all related deposits, permits, and fees. Contractor is prohibited from operating gate valves or fire hydrants on the City's water system. The acquisition of water from the City's water system through unmetered hydrants or other facilities is a violation of Laws. Citations and fines may be levied for violation of these and other utility regulations and may be deducted from payment otherwise due Contractor.

(B) **Removal and Repair.** Contractor must promptly remove all such temporary facilities when they are no longer needed or upon completion of the Work, whichever comes first. Contractor must promptly repair any damage to City's property or to other property caused by the installation, use, or removal of the temporary facilities, and must promptly restore the property to its original or intended condition.

7.3 Noninterference and Site Management. Contractor must avoid interfering with City's use of its property at or adjacent to the Project site, including use of roadways, entrances, parking areas, walkways, and structures. Contractor must also minimize disruption of access to private property in the Project vicinity. Contractor must coordinate with affected property owners, tenants, and businesses, and maintain some vehicle and pedestrian access to their residences or properties at all times. Temporary access ramps, fencing or other measures must be provided as needed. Before blocking access to a private driveway or parking lot, Contractor must provide effective notice to the affected parties at least 48 hours in advance of the pending closure and allow them to remove vehicles. Private driveways, residences and parking lots must have access to a roadway during non-Work hours. Property owners, tenants, and businesses must have full access to their driveways during non-Work hours. The Engineer may, at any time, direct or approve of opening completed sections of surfacing, pavement, or structure roadway surface for public use.

(A) **Offsite Acquisition.** Unless otherwise provided by City, Contractor must acquire, use, and dispose of, at its sole expense, any Worksites, licenses, easements, and temporary facilities necessary to access and perform the Work.

(B) **Offsite Staging Area and Field Office.** If additional space beyond the Project site is needed, such as for the staging area or the field office, Contractor may need to make arrangements with the nearby property owner(s) to secure the space and obtain a temporary use permit, in accordance with City Code § 20-52.040. Before using or occupying any property owned by a third party, Contractor must provide City with a copy of the necessary license agreement, easement, or other written authorization from the property owner, together with a written release from the property owner holding City harmless from any related liability, in a form acceptable to the City Attorney.

(C) **Traffic Management.** Contractor must provide traffic management and traffic controls as specified in the Contract Documents, as required by Laws, and as otherwise required to ensure public and worker safety, and to avoid interference with public or private operations or the normal flow of vehicular, bicycle, and pedestrian traffic.

(D) **Railroad Property.** Sonoma-Marín Area Rail Transit (“SMART”) maintains railroad property within the City. Contractor will not interfere with railroad operations or perform Work on or adjacent to railroad property unless Contractor has obtained an encroachment permit from SMART. Contractor is responsible for obtaining an encroachment permit from SMART if necessary for the Work or for Contractor’s traffic control. Contractor will not be entitled to an extension of time or additional compensation to obtain the SMART permit. For any excavation on or affecting railroad property, Contractor must submit Work plans to the City and SMART, if requested by SMART, showing the system to be used to protect the railroad facilities. Contractor will prevent material, equipment, and debris from falling onto railroad property.

(E) **Third Party Material Sourcing and Disposal.** If Contractor intends to procure materials from or dispose of materials on any property owned by a third party, before procuring material or disposing of material, Contractor must provide City with a copy of the agreement between Contractor and the third party authorizing the use of the property and absolving the City from responsibility in connection with the property. Contractor must obtain authorization from the third party to start sourcing or disposing of material on the property. As a condition precedent to Final Completion, Contractor must submit a document to the City, signed by the third party property owner, stating that the Contractor complied with its agreement with the third party.

7.4 Signs. No signs may be displayed on or about City’s property, except signage which is required by Laws or by the Contract Documents, without City’s prior written approval as to size, design, and location.

7.5 Project Site and Nearby Property Protections.

(A) **General.** Contractor is responsible at all times, on a 24-hour basis and at its sole cost, for protecting the Work, the Project site, and the materials and equipment to be incorporated into the Work, until the City has accepted the Project, excluding any exceptions to acceptance, if any. Except as specifically authorized by City, Contractor must confine its operations to the area of the Project site indicated in the Plans and Specifications. Contractor is liable for any damage caused by Contractor or its Subcontractors to the Work, City’s property, the property of adjacent or nearby property owners and the work or personal property of other contractors working for City, including damage related to Contractor’s failure to adequately secure the Work or any Worksite.

(1) Subject to City’s approval, Contractor will provide and install safeguards to protect the Work; any Worksite, including the Project site; City’s real or personal property and the real or personal property of adjacent or nearby property owners, including plant and tree protections.

(2) City wastewater systems may not be interrupted. If the Work disrupts existing sewer facilities, Contractor must immediately notify City and establish a plan, subject to City’s approval, to convey the sewage in closed conduits back into the sanitary sewer system. Sewage must not be permitted to flow in trenches or be covered by backfill.

(3) Contractor must remove with due care, and store at City’s request, any objects or material from the Project site that City will salvage or reuse at another location.

(4) If directed by Engineer, Contractor must promptly repair or replace any property damage, as specified by the Engineer. However, acting in its sole discretion, City may elect to have the property damage remedied otherwise, and may deduct the cost to repair or replace the damaged property from payment otherwise due to Contractor.

(5) Contractor will not permit any structure or infrastructure to be loaded in a manner that will damage or endanger the integrity of the structure or infrastructure.

(6) All valves, hydrants, and other appurtenances of the City’s water system that are the property of City and removed by Contractor in the performance of the Work must be delivered to City’s Municipal Services Center (55 Stony Point Road) as a condition

precedent to Final Completion, unless Contractor has obtained specific written approval from the Water Department to dispose of the items.

(B) **Securing Project Site.** After completion of Work each day, Contractor must secure the Project site and, to the extent feasible, make the area reasonably accessible to the public unless City approves otherwise. All excess materials and equipment not protected by approved traffic control devices must be relocated to the staging area or demobilized. Trench spoils must be hauled off the Project site daily and open excavations must be protected with steel plates. Contractor and Subcontractor personnel may not occupy or use the Project site for any purpose during non-Work hours, except as may be provided in the Contract Documents or pursuant to prior written authorization from City.

(C) **Unforeseen Conditions.** If Contractor encounters facilities, utilities, or other unknown conditions not shown on or reasonably inferable from the Plans or apparent from inspection of the Project site, Contractor must immediately notify the City and promptly submit a Request for Information to obtain further directions from the Engineer. Contractor must avoid taking any action which could cause damage to the facilities or utilities pending further direction from the Engineer. The Engineer's written response will be final and binding on Contractor. If the Engineer's subsequent direction to Contractor affects Contractor's cost or time to perform the Work, Contractor may submit a Change Order request as set forth in Article 6 above.

(D) **Support; Adjacent Properties.** Contractor must provide, install, and maintain all shoring, bracing, and underpinning necessary to provide support to City's property and adjacent properties and improvements thereon. Contractor must provide notifications to adjacent property owners as may be required by Laws. See also, Section 7.15, Trenching of Five Feet or More.

(E) **Notification of Property Damage.** Contractor must immediately notify the City of damage to any real or personal property resulting from Work on the Project, including damage to City's water system. Contractor must immediately provide a written report to City of any such property damage in excess of \$500 (based on estimated cost to repair or replace) within 24 hours of the occurrence. The written report must include: (1) the location and nature of the damage, and the owner of the property, if known; (2) the name and address of each employee of Contractor or any Subcontractor involved in the damage; (3) a detailed description of the incident, including precise location, time, and names and contact information for known witnesses; and (4) a police or first responder report, if applicable. If Contractor is required to file an accident report with another government agency, Contractor will provide a copy of the report to City.

(F) **Damage to City's Water System.** Contractor must promptly repair and remediate, at its sole expense, any damage caused by Contractor to the City's water system, in a manner satisfactory to the Water Department. This includes damage to property and facilities resulting from Contractor's failure to make a written request for a markout or starting Work without providing the Water Department a reasonable opportunity to mark facilities; Contractor's destruction of markouts; Contractor's failure to perform hand digging or probing for utilities near markouts; and Contractor's failure to use reasonable caution, regardless of whether markouts are present or clear. Reasonable caution includes any efforts to avoid damaging existing facilities, such as when excavating in the vicinity of water mains. All repairs must be witnessed, inspected, and approved by the Water Department prior to backfilling the excavation. If backfilling occurs prior to inspection and approval, City may require re-excavation by Contractor, at Contractor's sole expense. Acting in its sole discretion, City may elect to have the damage remedied otherwise, including by its own forces, and may deduct the cost thereof from payment otherwise due to Contractor. If City elects to remedy damage to the water system with its own forces, the cost thereof will be in accordance with the emergency repair rate schedule of the Water Department.

7.6 Materials and Equipment.

(A) **General.** Unless otherwise specified, all materials and equipment required for the Work must be new, free from defects, and of the best grade for the intended purpose, and furnished in

sufficient quantities to ensure the proper and expeditious performance of the Work. All materials, equipment, and tools furnished or installed by Contractor must meet or exceed applicable Occupational Safety and Health Administration ("OSHA") standards. Contractor must employ measures to preserve the specified quality and fitness of the materials and equipment. Unless otherwise specified, all materials and equipment required for the Work are deemed to include all components required for complete installation and intended operation and must be installed in accordance with the manufacturer's recommendations or instructions. Contractor is responsible for all shipping, handling, and storage costs associated with the materials and equipment required for the Work. Contractor is responsible for providing security and protecting the Work and all of the required materials, supplies, tools and equipment at Contractor's sole cost until City has formally accepted the Project as set forth in Section 11.1, Final Completion. Contractor will not assign, sell, mortgage, or hypothecate any materials or equipment for the Project, or remove any materials or equipment that have been installed or delivered.

(B) **City-Provided.** If the Work includes installation of materials or equipment to be provided by City, Contractor is solely responsible for the proper examination, handling, storage, and installation in accordance with the Contract Documents. Contractor must notify City of any defects discovered in City-provided materials or equipment, sufficiently in advance of scheduled use or installation to afford adequate time to procure replacement materials or equipment as needed. Contractor is solely responsible for any loss of or damage to such items which occurs while the items are in Contractor's custody and control, the cost of which may be offset from the Contract Price and deducted from any payment(s) due to Contractor.

(C) **Intellectual Property Rights.** Contractor must, at its sole expense, obtain any authorization or license required for use of patented or copyright-protected materials, equipment, devices, or processes that are incorporated into the Work. Upon request, Contractor must provide proof of any such authorization or license to City. Contractor's indemnity obligations in Article 4 apply to any claimed violation of intellectual property rights.

(D) **Equipment Labeling and Information.** Contractor must label each piece of equipment, except hand tools, with the following information, at a clearly visible location on each piece of equipment using a stencil or stamp: an identifying number; and for compacting equipment, its make, model number, and empty gross weight that is either the manufacturer's rated weight or the scale weight, or for meters and on the load-receiving element and indicators of each scale, the make, model, serial number, and manufacturer's rated capacity. Upon request, Contractor must submit the manufacturer's information that designates portable vehicle scale capacities.

(E) **Measuring Devices.** For proportioning materials, Contractor must use measuring devices, material plant controllers, and undersupports that comply with 4 CCR § 4000 et seq. and Business and Professions Code § 12001 et seq. Measuring devices must be tested and approved under California Test 109 in the Engineer's presence by any of the following: County Sealer of Weights and Measures; Scale Service Agency; or Official of the Division of Measurement Standards. The indicator over-travel must be at least one-third of the loading travel. The indicators must be enclosed against moisture and dust. Contractor must group the measuring system dials such that the smallest increment for each indicator can be read from the location at which proportioning is controlled.

7.7 Substitutions.

(A) **"Or Equal."** Any Specification designating a material, product, or thing (collectively, "item") or service by specific brand or trade name, followed by the words "or equal," is intended only to indicate the quality and type of item or service desired, and Contractor may request use of any equal item or service. Unless otherwise stated in the Specifications, any reference to a specific brand or trade name for an item or service that is used solely for the purpose of describing the type of item or service desired, will be deemed to be followed by the words "or equal." A substitution will only be approved if it is a true "equal" item or service in every aspect of design, function, and quality, as determined by City, including dimensions, weight, maintenance requirements, durability, fit with other elements, and schedule impacts.

(B) **Request for Substitution.** A post-award request for substitution of an item or service must be submitted in writing to the Engineer for approval at least four weeks in advance of Contractor's proposed order date and sufficiently in advance of the time needed to avoid delay of the Work. A request for substitution must contain a description of any proposed changes to the Work required to accommodate the substitution and drawings and details showing all such changes.

(C) **Substantiation.** Any available data substantiating the proposed substitute as an equal item or service must be submitted with the written request for substitution. Contractor's failure to timely provide all necessary substantiation, including any required test results as soon as they are available, is grounds for rejection of the proposed substitution, without further review.

(D) **Burden of Proving Equality.** Contractor has the burden of proving the equality of the proposed substitution at Contractor's sole cost. City has sole discretion to determine whether a proposed substitution is equal, and City's determination is final.

(E) **Approval or Rejection.** If the proposed substitution is approved, Contractor is solely responsible for any additional costs or time associated with the substituted item or service. If the proposed substitution is rejected, Contractor must, without delay, install the item or use the service as specified by City.

(F) **Contractor's Obligations.** City's approval of a proposed substitution will not relieve Contractor from any of its obligations under the Contract Documents. In the event Contractor makes an unauthorized substitution, Contractor will be solely responsible for all resulting cost impacts, including the cost of removal and replacement and the impact to other design elements.

7.8 Testing and Inspection.

(A) **General.** All materials, equipment, and workmanship used in the Work are subject to inspection and testing by City at all times and at all locations during construction and/or fabrication, including at any Worksite, shops, and yards. All manufacturers' application or installation instructions must be provided to the Engineer at least ten days prior to the first such application or installation. Contractor must, at all times, make the Work available for testing or inspection. City may record, including by photograph or video, all materials, equipment, and workmanship used in the Work. Neither City's inspection or testing of Work, nor its failure to do so, operate to waive or limit Contractor's duty to complete the Work in accordance with the Contract Documents.

(B) **Scheduling and Notification.** Contractor must cooperate with City in coordinating the inspections and testing. Contractor must submit samples of materials, at Contractor's expense, and schedule all tests required by the Contract Documents in time to avoid any delay to the progress of the Work. Contractor will coordinate directly with the Engineer when scheduling inspections or tests, unless otherwise specified in the Special Conditions or Specifications. Contractor must notify the Engineer no later than noon of the Working Day before any inspection or testing and must provide timely notice to the other necessary parties as specified in the Contract Documents. If Contractor schedules an inspection or test beyond regular Work hours, or on a Saturday, Sunday, or recognized City holiday, Contractor must notify the Engineer at least two Working Days in advance for approval. If approved, Contractor must reimburse City for the cost of the overtime inspection or testing. Such costs, including the City's hourly costs for required personnel, may be deducted from payments otherwise due to Contractor. Contractor will not coordinate directly with, or provide direction to, the Materials Lab.

(C) **Responsibility for Costs.** City will bear the initial cost of inspection and testing to be performed by independent consultants retained by City, subject to the following exceptions:

- (1) Contractor will be responsible for the costs of any subsequent inspections or tests which are required to substantiate compliance with the Contract Documents, and any associated remediation costs.

(2) Contractor will be responsible for inspection costs, at City's hourly rates, for inspection time lost because the Work is not ready, or Contractor fails to appear for a scheduled inspection.

(3) If any portion of the Work that is subject to inspection or testing is covered or concealed by Contractor prior to the inspection or testing, Contractor will bear the cost of making that portion of the Work available for the inspection or testing required by the Contract Documents, and any associated repair or remediation costs.

(4) Contractor is responsible for properly shoring all compaction test sites deeper than five feet below grade, as required under Section 7.15 below.

(5) Any Work or material that is defective or fails to comply with the requirements of the Contract Documents must be promptly repaired, removed, replaced, or corrected by Contractor, at Contractor's sole expense, even if that Work or material was previously inspected or included in a progress payment.

(D) **Contractor's Obligations.** Contractor is solely responsible for any delay occasioned by remediation of defective or noncompliant Work or material. Inspection or testing of the Work does not in any way relieve Contractor of its obligations to perform the Work as specified. Contractor has an independent duty to test and inspect its Work and perform quality control activities to ensure that the Work and the materials, products, and equipment incorporated into the Work comply with the Contract Documents. City is not responsible for any testing performed by Contractor or a third-party retained by Contractor. Contractor will submit its testing methodology to City for review and acceptance. Any Work done without the inspection(s) or testing required by the Contract Documents will be subject to rejection by City.

(E) **Distant Locations.** If required off-site testing or inspection must be conducted at a location more than 100 miles from the Project site, Contractor is solely responsible for the additional travel costs required for testing and/or inspection at such locations.

(F) **Final Inspection.** The provisions of this Section 7.8 also apply to final inspection under Article 11, Completion and Warranty Provisions.

7.9 Project Site Conditions and Maintenance. Contractor must at all times, on a 24-hour basis and at its sole cost, maintain the Project site and staging and storage areas in clean, neat, and sanitary condition and in compliance with all Laws pertaining to safety, air quality, and dust control. Adequate toilets must be provided and properly maintained and serviced for all workers on the Project site, located in a suitably secluded area, subject to City's prior approval. Contractor must also, on a daily basis and at its sole cost, remove and properly dispose of the debris and waste materials from the Project site.

(A) **Air Emissions Control.** Contractor must not discharge smoke or other air contaminants into the atmosphere in violation of any Laws. Contractor must comply with all Laws, including the California Air Resources Board's In-Use Off-Road Diesel-Fueled Fleets Regulation (13 CCR § 2449 et seq.).

(B) **Dust and Debris.** Contractor must minimize and confine dust and debris resulting from the Work. Contractor must abate dust nuisance by cleaning, sweeping, and immediately sprinkling with water excavated areas of dirt or other materials prone to cause dust, and within one hour after the Engineer notifies Contractor that an airborne nuisance exists. The Engineer may direct that Contractor provide an approved water-spraying truck for this purpose. If water is used for dust control, Contractor will only use the minimum necessary. Contractor must take all necessary steps to keep wastewater out of streets, gutters, or storm drains. See Section 7.19, Environmental Control. If City determines that the dust control is not adequate, City may have the work done by others and deduct the cost from the Contract Price. Contractor will immediately remove any excess excavated material from the Project site and any dirt deposited on public

streets.

(C) **Clean up.** Before discontinuing Work in an area, Contractor must clean the area and remove all debris and waste along with the construction equipment, tools, machinery, and surplus materials.

(1) Except as otherwise specified, all excess Project materials, and the materials removed from existing improvements on the Project site with no salvage value or intended reuse by City, will be Contractor's property.

(2) Hauling trucks and other vehicles leaving the Project site must be cleaned of exterior mud or dirt before traveling on City streets. Materials and loose debris must be delivered and loaded to prevent dropping materials or debris. Contractor must immediately remove spillage from hauling on any publicly traveled way. Streets affected by Work on the Project must be kept clean by street sweeping.

(D) **Disposal.** Contractor must dispose of all Project debris and waste materials in a safe and legal manner. Contractor may not burn or bury waste materials on the Project site. Contractor will not allow any dirt, refuse, excavated material, surplus concrete or mortar, or any associated washings, to be disposed of onto streets, into manholes or into the storm drain system.

(E) **Completion.** At the completion of the Work, Contractor must remove from the Project site all of its equipment, tools, surplus materials, waste materials and debris, presenting a clean and neat appearance. Before demobilizing from the Project site, Contractor must ensure that all surfaces are cleaned, sealed, waxed, or finished as applicable, and that all marks, stains, paint splatters, and the like have been properly removed from the completed Work and the surrounding areas. Contractor must ensure that all parts of the construction are properly joined with the previously existing and adjacent improvements and conditions. Contractor must provide all cutting, fitting and patching needed to accomplish that requirement. Contractor must also repair or replace, in accordance with City Standards, all existing improvements that are damaged or removed during the Work, both on and off the Project site, including curbs, sidewalks, driveways, fences, gates, signs, landscaping, drainage ditches, irrigation systems, utilities, street surfaces and structures. Repairs and replacements must be at least equal to the previously existing improvements, and the condition, finish and dimensions must match the previously existing improvements. Concrete surface treatment and score marks must match adjacent existing concrete improvements. Contractor must restore to original condition all property or items that are not designated for alteration under the Contract Documents and leave each Worksite clean and ready for occupancy or use by City.

(F) **Non-Compliance.** If Contractor fails to comply with its maintenance and cleanup obligations or any City clean up order, City may, acting in its sole discretion, elect to suspend the Work until the condition(s) is corrected with no increase in the Contract Time or Contract Price, or undertake appropriate cleanup measures without further notice and deduct the cost from any amounts due or to become due to Contractor.

7.10 Instructions and Manuals. Contractor must provide to City three copies each of all instructions and manuals required by the Contract Documents, unless otherwise specified. These must be complete as to drawings, details, parts lists, performance data, and other information that may be required for City to easily maintain and service the materials and equipment installed for this Project.

(A) **Submittal Requirements.** The instructions and manuals, along with any required guarantees, must be delivered to City for review prior to requesting final inspection pursuant to Section 11.1(A), unless otherwise specified.

(B) **Training.** Contractor or its Subcontractors must train City's personnel in the operation and maintenance of any complex equipment or systems as a condition precedent to Final Completion, if required in the Contract Documents.

7.11 As-built Drawings. Contractor and its Subcontractors must prepare and maintain at the Project site a detailed, complete and accurate as-built set of the Plans which will be used solely for the purpose of recording changes made in any portion of the original Plans in order to create accurate record drawings at the end of the Project.

(A) **Duty to Update.** The as-built drawings must be updated as changes occur, on a daily basis if necessary. City may withhold the estimated cost for City to have the as-built drawings prepared from payments otherwise due to Contractor, until the as-built drawings are brought up to date to the satisfaction of City. Actual locations to scale must be identified on the as-built drawings for all runs of mechanical and electrical work, including all site utilities installed underground, in walls, floors, or otherwise concealed. Deviations from the original Plans must be shown in detail. The exact location of all main runs, whether piping, conduit, ductwork or drain lines, must be shown by dimension and elevation. The location of all buried pipelines, appurtenances, or other improvements must be represented by coordinates and by the horizontal distance from visible above-ground improvements.

(B) **Final Completion.** Contractor must verify that all changes in the Work are depicted in the as-built drawings and must deliver the complete set of as-built drawings to the Engineer for review and acceptance as a condition precedent to Final Completion and Final Payment.

7.12 Existing Utilities.

(A) **General.** The Work may be performed in developed, urban areas with existing utilities, both above and below ground, including utilities identified in the Contract Documents or in other informational documents or records. Contractor must take due care to locate identified or reasonably identifiable utilities before proceeding with trenching, excavation, or any other activity that could damage or disrupt existing utilities. This may include excavation with small equipment, potholing, or hand excavation, and, if practical, using white paint or other suitable markings to delineate the area to be excavated. Except as otherwise provided herein, Contractor will be responsible for costs resulting from damage to identified or reasonably identifiable utilities due to Contractor's negligence or failure to comply with the Contract Documents, including the requirements in this Article 7.

(B) **Unidentified Utilities.** Pursuant to Government Code § 4215, if, during the performance of the Work, Contractor discovers utility facilities not identified by City in the Contract Documents, Contractor must immediately provide written notice to City and the utility. City assumes responsibility for the timely removal, relocation, or protection of existing main or trunkline utility facilities located on the Project site if those utilities are not identified in the Contract Documents. Contractor will be compensated in accordance with the provisions of the Contract Documents for the costs of locating, repairing damage not due to Contractor's failure to exercise reasonable care, and removing or relocating utility facilities not indicated in the Plans or Specifications with reasonable accuracy, and for equipment on the Project necessarily idled during such work. Contractor will not be assessed liquidated damages for delay in completion of the Work, to the extent the delay was caused by City's failure to provide for removal or relocation of the utility facilities.

(C) **Alteration or Relocation of Utilities.** If Contractor wishes to alter or relocate utilities for Contractor's convenience, and not due to a conflict that requires alteration or relocation, Contractor will be solely responsible for the time and cost required for such alteration or relocation, which may not proceed except as specified by the prior written authorization of the utility owner. Any damage to utilities or improvements caused by Contractor must be repaired by Contractor at its sole expense and to the full satisfaction of the utility owner and Engineer. Contractor will not be entitled to an extension of the Contract Time in connection with any such Work.

7.13 Notice of Excavation. Contractor must comply with all applicable requirements in Government Code § 4216 et seq., which are incorporated by reference herein, including, but not limited to, the requirement to notify Underground Service Alert ("USA") of a proposed excavation and provide

USA all relevant data relating to the excavation, at least two Working Days before starting any excavation Work.

7.14 Trenching and Excavations of Four Feet or More. As required by Public Contract Code § 7104, if the Work includes digging trenches or other excavations that extend deeper than four feet below the surface, the provisions in this Section apply to the Work and the Project.

(A) **Duty to Notify.** Contractor must promptly, and before the following conditions are disturbed, provide written notice to City if Contractor finds any of the following conditions:

(1) Material that Contractor believes may be a hazardous waste, as defined in § 25117 of the Health and Safety Code, that is required to be removed to a Class I, Class II, or Class III disposal site in accordance with the provisions of existing Laws;

(2) Subsurface or latent physical conditions at the Project site differing from those indicated by information about the Project site made available to bidders prior to the deadline for submitting bids; or

(3) Unknown physical conditions at the Project site of any unusual nature, materially different from those ordinarily encountered and generally recognized as inherent in work of the character required by the Contract Documents.

(B) **City Investigation.** City will promptly investigate the conditions and if City finds that the conditions materially differ from those indicated, apparent, or reasonably inferred from information about the Project site made available to bidders, or involve hazardous waste, and cause a decrease or increase in Contractor's cost of, or the time required for, performance of any part of the Work, City will issue a Change Order.

(C) **Disputes.** In the event that a dispute arises between City and Contractor regarding any of the conditions specified in subsection (B) above, or the terms of a Change Order issued by City, Contractor will not be excused from completing the Work within the Contract Time but must proceed with all Work to be performed under the Contract. Contractor will retain any and all rights provided either by the Contract or by Laws which pertain to the resolution of disputes between Contractor and City.

7.15 Trenching of Five Feet or More. As required by Labor Code § 6705, if the Contract Price exceeds \$25,000 and the Work includes the excavation of any trench or trenches of five feet or more in depth, a detailed plan must be submitted to City for acceptance in advance of the excavation. The detailed plan must show the design of shoring, bracing, sloping, or other provisions to be made for worker protection from the hazard of caving ground during the excavation. If the plan varies from the shoring system standards or if the trench is expected to exceed 20 feet, the plan must be prepared by a California registered civil or structural engineer. Use of a shoring, sloping, or protective system less effective than that required by the Construction Safety Orders is prohibited.

7.16 New Utility Connections. Except as otherwise specified, City will pay connection charges and meter costs for new permanent utilities required by the Contract Documents, if any. Contractor must notify City sufficiently in advance of the time needed to request service from each utility provider so that connections and services are initiated in accordance with the Project schedule.

7.17 Lines and Grades. Contractor is required to use any benchmark provided by the Engineer. Unless otherwise specified in the Contract Documents, Contractor must provide all lines and grades required to execute the Work. Contractor must also provide, preserve, and replace if necessary, all construction stakes required for the Project unless otherwise specified in the Special Conditions. All stakes or marks must be set by a California licensed land surveyor or a California registered civil engineer. All survey monuments that may be disturbed or destroyed during performance of the Work must be tied-out by Contractor prior to the start of Work.

Contractor must also file a Pre-Construction Corner Record, prepared by a California licensed land surveyor, with the County of Sonoma Surveyor's Office, prior to the start of Work. Contractor must notify the Engineer of any discrepancies found between Contractor's staking and grading and information provided by the Contract Documents. Contractor must replace any survey monuments that are disturbed, damaged, or destroyed during the Work and must file a Post-Construction Corner Record, prepared by a licensed land surveyor as required by law, with the County of Sonoma Surveyor's Office. Upon completion, all Work must conform to the lines, elevations, and grades shown in the Plans, including any changes directed by a Change Order.

7.18 Historic or Archeological Items.

(A) **Contractor's Obligations.** Contractor must ensure that all persons performing Work at the Project site are required to immediately notify the Project Manager, upon discovery of any potential historic or archeological items, including historic or prehistoric ruins, a burial ground, archaeological or vertebrate paleontological site, including fossilized footprints or other archeological, paleontological or historical feature on the Project site (collectively, "Historic or Archeological Items").

(B) **Discovery; Cessation of Work.** Upon discovery of any potential Historic or Archeological Items, Work must be stopped within an 85-foot radius of the find and may not resume until authorized in writing by City. If required by City, Contractor must assist in protecting or recovering the Historic or Archeological Items, with any such assistance to be compensated as Extra Work on a time and materials basis under Article 6, Contract Modification. At City's discretion, a suspension of Work required due to discovery of Historic or Archeological Items may be treated as Excusable Delay pursuant to Article 5, or as a suspension for convenience under Article 13.

7.19 Environmental Control. Contractor must not pollute any drainage course or its tributary inlets with fuels, oils, bitumens, acids, insecticides, herbicides or other harmful materials. Contractor must prevent the release of any hazardous material or hazardous waste into the soil or groundwater and prevent the unlawful discharge of pollutants into City's storm drain system and watercourses as required below. Contractor and its Subcontractors must at all times in the performance of the Work comply with all Laws concerning pollution of waterways.

(A) **Stormwater Permit.** Contractor must comply with all applicable conditions of the State Water Resources Control Board National Pollutant Discharge Elimination System General Permit for Waste Discharge Requirements for Discharges of Stormwater Runoff Associated with Construction Activity ("Stormwater Permit").

(B) **Contractor's Obligations.** If required for the Work, a copy of the Stormwater Permit is on file in City's principal administrative offices, and Contractor must comply with it without adjustment of the Contract Price or the Contract Time. Contractor must timely and completely submit required reports and monitoring information required by the conditions of the Stormwater Permit. Contractor also must comply with all other Laws governing discharge of stormwater, including applicable municipal stormwater management programs.

(C) **Pest Management.** Contractor must comply with the City-Wide Integrated Pest Management ("IPM") Policy, Policy Number 000-74, which is available at <https://www.srcity.org/DocumentCenter/View/41774/Integrated-Pest-Management-Policy-030524>. Contractor will not use pesticides or herbicides in the Work without City's prior written approval. Contractor may submit a written request for use of pesticides or herbicides to the Engineer. Contractor's written request must include the location proposed for use, the proposed date and time of application, product specifications, and all other information required by the IPM policy. City reserves the right, in its sole discretion, to approve or reject the use of pesticides or herbicides, for any reason.

- 7.20 Noise Control.** Contractor must comply with all applicable noise control Laws. Noise control requirements apply to all equipment used for the Work or related to the Work, including trucks, transit mixers or transient equipment that may or may not be owned by Contractor.
- 7.21 Mined Materials.** Pursuant to Public Contract Code § 20676, Contractor will not purchase any sand, gravel, or other minerals for the Work from an operation subject to the Surface Mining and Reclamation Act of 1975 (Public Resources Code § 2710 et seq.) unless Contractor certifies, under penalty of perjury, that the minerals are from a mining operation included on the AB 3098 List, which may be accessed online at: <https://www.conservation.ca.gov/smgb/Pages/AB-3098-List.aspx>.
- 7.22 Water Department Notification.** If Contractor requires the services of the Water Department in connection with the Work, Contractor must request such services at least two Working Days in advance of the time the services are needed. If the requested services require Water Department forces for more than eight hours or an extensive number of City-provided parts, Contractor must request services at least seven calendar days in advance of the time the services are needed.
- (A) **Service Shut Down.** Contractor must minimize disruption of utility service to the greatest extent practicable. Contractor must coordinate any shut down or disruption of utility service with the Engineer, Water Department, and affected utility customers. If it is necessary to shut down or disrupt utility service to any customer of the Water Department, Contractor must request the services of the Water Department an additional three Working Days in advance of the time such services are needed, for a total of five Working Days advance notification for a standard service request, to allow affected customers a minimum of three days' advance notice. If Contractor fails to keep field appointments, Contractor will be billed for scheduled Water Department crew standby time and for costs incurred by the Water Department for re-notification of customers.
- (B) **Water Department Scheduling.** Water Department crews work a 9/80 schedule. This schedule may prohibit shutdowns for tie-ins on alternating Fridays. After-hours work or weekend work may be performed if authorized in advance by the Engineer. Requests by Contractor for after-hours or weekend work are to be avoided when possible. Contractor will be responsible for any overtime costs incurred by City for such work and the cost thereof may be deducted from payment otherwise due Contractor.
- 7.23 Public Safety and Traffic Control.** Contractor must undertake all required and appropriate measures to ensure public safety during construction of the Project, in accordance with Laws, including, but not limited to, the Americans with Disabilities Act of 1990 (42 U.S.C. § 12101 et seq.). Contractor will ensure the safe passage of pedestrians around the Project site at all times. If Work is within a City-owned right-of-way, Contractor will ensure the safe passage of public traffic through the Project site at all times, consistent with the requirements of City Code Chapter 13-04. Contractor is solely responsible for the costs of all public safety and traffic control measures.
- (A) **Warning Devices.** Contractor must furnish, install, and maintain, at its sole expense, all fences, barricades, signs, lights, and other devices necessary to prevent accidents, injuries, death, and property damage. All such devices must conform to the requirements of the current edition of the California Manual on Uniform Traffic Control Devices ("CA MUTCD") and the directions of the Engineer. Contractor's warning and safety devices will not obscure the visibility of or conflict with existing signs and traffic control devices. Contractor may be required to cover certain signs which regulate or direct public traffic to roadways that are not open to traffic, as directed by the Engineer.
- (B) **Flaggers.** Contractor must also furnish, at Contractor's sole expense, trained flaggers as necessary to provide adequate warning to the public of construction conditions that may impact pedestrian or vehicular traffic.

(C) **Project Signage.** Unless otherwise specified in the Special Conditions, Contractor must install and maintain Project identification signs at each boundary of the Project site or as directed by the Engineer. Contractor must install the signs two weeks prior to the start of Work at the Project site, using sign panels furnished by City. To mount sign panels, Contractor must furnish and install 4" X 4" posts or mount by other appropriate methods as approved by the Engineer. Upon completion of the Project, Contractor will remove Project identification signs, in a timely manner, and return the City-furnished sign panels to the City Corporation Yard at 55 Stony Point Road.

(D) **Road Closure Signage.** If the Work requires road closures, Contractor must furnish and install advance notice signs for road closures at each boundary of the Project site. Panel construction and lettering are subject to advance approval of the Engineer. Contractor must install the signs two weeks prior to the start of Work at the Project site. The signs must remain in place for the duration of the road closure and must be removed by Contractor when no longer necessary for the Work.

(E) **Emergency Response Agencies.** Contractor is responsible for notifying emergency response agencies operating in the jurisdiction of the Worksite(s) of obstructions to roads resulting from Contractor's Work.

(F) **Additional Devices.** City reserves the right to require additional warning or safety devices for the Project at the Contractor's sole expense, but no actions by City to add to or improve signage or any other public safety requirements will waive or limit Contractor's duties under the Contract Documents.

(G) **Compliance.** If Contractor fails or refuses to comply with the requirements of this Section, the Engineer may take immediate action to protect the public, including, but not limited to, furnishing the required safety measures at Contractor's expense or suspending the Work, in addition to all other remedies available to City. Any such remedial costs incurred by City may be deducted from payment otherwise due to Contractor as specified in Section 8.3, Adjustment of Payment Application. If there are insufficient Contract funds remaining to cover the remedial costs, City is entitled to recover the balance from Contractor or its performance bond surety.

Article 8 - Payment

8.1 Schedule of Values. Prior to submitting its first application for payment, Contractor must prepare and submit to the Project Manager a schedule of values apportioned to the various divisions and phases of the Work, including mobilization and demobilization. If a Bid Schedule was submitted with Contractor's bid, the amounts in the schedule of values must be consistent with the Bid Schedule. Each line item contained in the schedule of values must be assigned a value such that the total of all items equals the Contract Price. The items must be sufficiently detailed to enable accurate evaluation of the percentage of completion claimed in each application for payment, and the assigned value consistent with any itemized or unit pricing submitted with Contractor's bid.

(A) **Measurements for Unit Price Work.** Materials and items of Work to be paid for on the basis of unit pricing will be measured according to the methods specified in the Contract Documents.

(B) **Deleted or Reduced Work.** Contractor will not be compensated for Work that City has deleted or reduced in scope, except for any labor, material, or equipment costs for such Work that Contractor reasonably incurred before Contractor learned that the Work could be deleted or reduced. Contractor will only be compensated for those actual, direct and documented costs incurred, and will not be entitled to any mark up for overhead or lost profits.

8.2 Progress Payments. Following the last day of each month, or as otherwise required by the Special Conditions or Specifications, Contractor will submit to the Project Manager a monthly

application for payment for Work performed during the preceding month based on the estimated value of the Work performed during that preceding month.

(A) **Application for Payment.** Each application for payment must be itemized to include labor, materials, and equipment incorporated into the Work, and materials and equipment delivered to the Project site, as well as authorized and approved Change Orders. Each payment application must be supported by the unit prices submitted with Contractor's Bid Schedule and/or schedule of values and any other substantiating data required by the Contract Documents.

(B) **Payment of Undisputed Amounts.** City will pay the undisputed amount due within 30 days after Contractor has submitted a complete and accurate payment application, subject to Public Contract Code § 20104.50. City will deduct a percentage from each progress payment as retention, as set forth in Section 8.5, below, and may deduct or withhold additional amounts as set forth in Section 8.3, below.

8.3 Adjustment of Payment Application. City may adjust or reject the amount requested in a payment application, including application for Final Payment, in whole or in part, if the amount requested is disputed or unsubstantiated. Contractor will be notified in writing of the basis for the modification to the amount requested. City may also deduct or withhold from payment otherwise due based upon any of the circumstances and amounts listed below. Sums withheld from payment otherwise due will be released when the basis for that withholding has been remedied and no longer exists.

(A) For Contractor's unexcused failure to perform the Work as required by the Contract Documents, including correction or completion of punch list items, City may withhold or deduct an amount based on the City's estimated cost to correct or complete the Work.

(B) For loss or damage caused by Contractor or its Subcontractors arising out of or relating to performance of the Work or any failure to protect the Project site, City may deduct an amount based on the estimated cost to repair or replace.

(C) For Contractor's failure to pay its Subcontractors and suppliers when payment is due, City may withhold an amount equal to the total of past due payments and may opt to pay that amount separately via joint check pursuant to Section 8.6(B), Joint Checks.

(D) For Contractor's failure to timely correct rejected, nonconforming, or defective Work, City may withhold or deduct an amount based on the City's estimated cost to correct or complete the Work.

(E) For any unreleased stop notice, City may withhold 125% of the amount claimed.

(F) For Contractor's failure to submit any required schedule or schedule update in the manner specified or within the time specified in the Contract Documents, City may withhold an amount equal to five percent of the total amount requested until Contractor complies with its schedule submittal obligations.

(G) For Contractor's failure to maintain or submit as-built documents in the manner specified or within the time specified in the Contract Documents, City may withhold or deduct an amount based on the City's cost to prepare the as-builts.

(H) For Work performed without Shop Drawings that have been accepted by City, when accepted Shop Drawings are required before proceeding with the Work, City may deduct an amount based on the estimated cost to correct unsatisfactory Work or diminution in value.

(I) For fines, payments, or penalties assessed under the Labor Code, City may deduct from payments due to Contractor as required by Laws and as directed by the Division of Labor Standards Enforcement.

(J) For any other fines, payments, or penalties assessed against the City relating to Contractor's acts or omissions, including violations of Laws, City may withhold or deduct such amounts from payment otherwise due to Contractor.

(K) For any other costs or charges that may be withheld or deducted from payments to Contractor, as provided in the Contract Documents, including liquidated damages, City may withhold or deduct such amounts from payment otherwise due to Contractor.

8.4 Early Occupancy. Neither City's payment of progress payments nor its partial or full use or occupancy of the Project constitutes acceptance of any part of the Work.

8.5 Retention. City will retain five percent of the full amount due on each progress payment (i.e., the amount due before any withholding or deductions pursuant to Section 8.3, Adjustment of Payment Application), or the percentage stated in the Notice Inviting Bids, whichever is greater, as retention to ensure full and satisfactory performance of the Work. Contractor is not entitled to any reduction in the rate of withholding at any time, nor to release of any retention before 35 days following City's recordation of the Notice of Completion, subject to the terms of Public Contract Code § 7107.

(A) **Substitution of Securities.** As provided by Public Contract Code § 22300, Contractor may request in writing that it be allowed, at its sole expense, to substitute securities for the retention withheld by City. Any escrow agreement entered into pursuant to this provision must fully comply with Public Contract Code § 22300 and will be subject to approval as to form by City's legal counsel. If City exercises its right to draw upon such securities in the event of default pursuant to section (7) of the statutory Escrow Agreement for Security Deposits in Lieu of Retention, pursuant to subdivision (g) of Public Contract Code § 22300 ("Escrow Agreement"), and if Contractor disputes that it is in default, its sole remedy is to comply with the dispute resolution procedures in Article 12 and the provisions therein. It is agreed that for purposes of this paragraph, an event of default includes City's rights pursuant to these Contract Documents to withhold or deduct sums from retention, including withholding or deduction for liquidated damages, incomplete or defective Work, stop payment notices, or back charges. It is further agreed that if any individual authorized to give or receive written notice on behalf of a party pursuant to section (10) of the Escrow Agreement are unavailable to give or receive notice on behalf of that party due to separation from employment, retirement, death, or other circumstances, the successor or delegee of the named individual is deemed to be the individual authorized to give or receive notice pursuant to section (10) of the Escrow Agreement.

(B) **Release of Undisputed Retention.** All undisputed retention, less any amounts that may be assessed as liquidated damages, retained for stop notices, or otherwise withheld pursuant to Section 8.3, Adjustment of Payment Application, will be released as Final Payment to Contractor no sooner than 35 days following recordation of the notice of completion, and no later than 60 days following acceptance of the Project by City's governing body or authorized designee pursuant to Section 11.1(C), Acceptance, or, if the Project has not been accepted, no later than 60 days after the Project is otherwise considered complete pursuant to Public Contract Code § 7107(c).

8.6 Payment to Subcontractors and Suppliers. Each month, Contractor must promptly pay each Subcontractor and supplier the value of the portion of labor, materials, and equipment incorporated into the Work or delivered to the Project site by the Subcontractor or supplier during the preceding month. Such payments must be made in accordance with the requirements of Laws pertaining to such payments, and those of the Contract Documents and applicable subcontract or supplier contract.

(A) **Withholding for Stop Notice.** Pursuant to Civil Code § 9358, City will withhold 125% of the amount claimed by an unreleased stop notice, a portion of which may be retained by City for the costs incurred in handling the stop notice claim, including attorneys' fees and costs, as authorized by law.

(B) **Joint Checks.** City reserves the right, acting in its sole discretion, to issue joint checks made payable to Contractor and a Subcontractor or supplier, if City determines this is necessary to ensure fair and timely payment for a Subcontractor or supplier who has provided services or goods for the Project. As a condition to release of payment by a joint check, the joint check payees may be required to execute a joint check agreement in a form provided or approved by the City Attorney's Office. The joint check payees will be jointly and severally responsible for the allocation and disbursement of funds paid by joint check. Payment by joint check will not be construed to create a contractual relationship between City and a Subcontractor or supplier of any tier beyond the scope of the joint check agreement.

- 8.7 Final Payment.** Contractor's application for Final Payment must comply with the requirements for submitting an application for a progress payment as stated in Section 8.2, above. Corrections to previous progress payments, including adjustments to estimated quantities for unit priced items, may be included in the Final Payment. If Contractor fails to submit a timely application for Final Payment, City reserves the right to unilaterally process and issue Final Payment without an application from Contractor in order to close out the Project. For the purposes of determining the deadline for Claim submission pursuant to Article 12, the date of Final Payment is deemed to be the date that City acts to release undisputed retention as final payment to Contractor, or otherwise provides written notice to Contractor of Final Payment or that no undisputed funds remain available for Final Payment due to offsetting withholdings or deductions pursuant to Section 8.3, Adjustment of Payment Application. If the amount due from Contractor to City exceeds the amount of Final Payment, City retains the right to recover the balance from Contractor or its sureties.
- 8.8 Release of Claims.** City may, at any time, require that payment of the undisputed portion of any progress payment or Final Payment be contingent upon Contractor furnishing City with a written waiver and release of all claims against City arising from or related to the portion of Work covered by those undisputed amounts subject to the limitations of Public Contract Code § 7100. Any disputed amounts may be specifically excluded from the release.
- 8.9 Warranty of Title.** Contractor warrants that title to all work, materials, or equipment incorporated into the Work and included in a request for payment will pass over to City free of any claims, liens, or encumbrances upon payment to Contractor.

Article 9 - Labor Provisions

- 9.1 Discrimination Prohibited.** Discrimination against any prospective or present employee engaged in the Work on grounds of race, color, ancestry, national origin, ethnicity, religion, sex, sexual orientation, age, disability, or marital status is strictly prohibited. Contractor and its Subcontractors are required to comply with all applicable Laws prohibiting discrimination, including the California Fair Employment and Housing Act (Govt. Code § 12900 et seq.), Government Code § 11135, and Labor Code §§ 1735, 1777.5, 1777.6, and 3077.5.
- 9.2 Labor Code Requirements.**
- (A) **Eight Hour Day.** Pursuant to Labor Code § 1810, eight hours of labor constitute a legal day's work under this Contract.
- (B) **Penalty.** Pursuant to Labor Code § 1813, Contractor will forfeit to City as a penalty, the sum of \$25.00 for each day during which a worker employed by Contractor or any Subcontractor is required or permitted to work more than eight hours in any one calendar day or more than 40 hours per calendar week, except if such workers are paid overtime under Labor Code § 1815.
- (C) **Apprentices.** Contractor is responsible for compliance with the requirements governing employment and payment of apprentices, as set forth in Labor Code § 1777.5, which is fully incorporated by reference.
- (D) **Notices.** Pursuant to Labor Code § 1771.4, Contractor is required to post all job site notices prescribed by Laws.

9.3 Prevailing Wages. Each worker performing Work under this Contract that is covered under Labor Code §§ 1720, 1720.3, or 1720.9, including cleanup at the Project site, must be paid at a rate not less than the prevailing wage as defined in §§ 1771 and 1774 of the Labor Code. The prevailing wage rates are on file with the City and available online at <http://www.dir.ca.gov/dlsr>. Contractor must post a copy of the applicable prevailing rates at the Project site.

(A) **Penalties.** Pursuant to Labor Code § 1775, Contractor and any Subcontractor will forfeit to City as a penalty up to \$200.00 for each calendar day, or portion thereof, for each worker paid less than the applicable prevailing wage rate. Contractor must also pay each worker the difference between the applicable prevailing wage rate and the amount actually paid to that worker.

(B) **Federal Requirements.** If this Project is subject to federal prevailing wage requirements in addition to California prevailing wage requirements, Contractor and its Subcontractors are required to pay the higher of the currently applicable state or federal prevailing wage rates.

9.4 Payroll Records. Contractor must comply with the provisions of Labor Code §§ 1771.4, 1776, and 1812 and all implementing regulations, which are fully incorporated by this reference, including requirements for monthly electronic submission of payroll records to the DIR.

(A) **Contractor and Subcontractor Obligations.** Contractor and each Subcontractor must keep accurate payroll records, showing the name, address, social security number, work classification, straight time and overtime hours worked each day and week, and the actual per diem wages paid to each journeyman, apprentice, worker, or other employee employed in connection with the Work. Each payroll record must contain or be verified by a written declaration that it is made under penalty of perjury, stating both of the following:

(1) The information contained in the payroll record is true and correct; and

(2) Contractor or the Subcontractor has complied with the requirements of Labor Code §§ 1771, 1811, and 1815 for any Work performed by its employees on the Project.

(B) **Certified Record.** A certified copy of an employee's payroll record must be made available for inspection or furnished to the employee or his or her authorized representative on request, to City, to the Division of Labor Standards Enforcement, to the Division of Apprenticeship Standards of the DIR, and as further required by the Labor Code.

(C) **Enforcement.** Upon notice of noncompliance with Labor Code § 1776, Contractor or Subcontractor has ten days in which to comply with the requirements of this section. If Contractor or Subcontractor fails to do so within the ten-day period, Contractor or Subcontractor will forfeit a penalty of \$100.00 per day, or portion thereof, for each worker for whom compliance is required, until strict compliance is achieved. Upon request by the Division of Apprenticeship Standards, or the Division of Labor Standards Enforcement, these penalties will be withheld from payments then due to Contractor.

9.5 Labor Compliance. Pursuant to Labor Code § 1771.4, the Contract for this Project is subject to compliance monitoring and enforcement by the DIR.

Article 10 - Safety Provisions

10.1 Safety Precautions and Programs. Contractor and its Subcontractors are fully responsible for safety precautions and programs, and for the safety of persons and property in the performance of the Work. Contractor and its Subcontractors must at all times comply with all applicable health and safety Laws and seek to avoid injury, loss, or damage to persons or property by taking reasonable steps to protect its employees and other persons at any Worksite, materials and equipment stored on or off site, and property at or adjacent to any Worksite.

(A) **Reporting Requirements.** Contractor must immediately notify the City of any death, serious injury or illness resulting from Work on the Project. Contractor must immediately provide a written report to City of each recordable accident or injury occurring at any Worksite within 24 hours of the occurrence. The written report must include: (1) the name and address of the injured or deceased person; (2) the name and address of each employee of Contractor or of any Subcontractor involved in the incident; (3) a detailed description of the incident, including precise location, time, and names and contact information for known witnesses; and (4) a police or first responder report, if applicable. If Contractor is required to file an accident report with a government agency, Contractor will provide a copy of the report to City.

(B) **Legal Compliance.** Contractor's safety program must comply with the applicable legal and regulatory requirements. Contractor must provide City with copies of all notices required by Laws.

(C) **Contractor's Obligations.** Any damage or loss caused by Contractor arising from the Work which is not insured under property insurance must be promptly remedied by Contractor.

(D) **Remedies.** If City determines, in its sole discretion, that any part of the Work or Project site is unsafe, City may, without assuming responsibility for Contractor's safety program, require Contractor or its Subcontractor to cease performance of the Work or to take corrective measures to City's satisfaction. If Contractor fails to promptly take the required corrective measures, City may perform them and deduct the cost from the Contract Price. Contractor agrees it is not entitled to submit a Claim for damages, for an increase in Contract Price, or for a change in Contract Time based on Contractor's compliance with City's request for corrective measures pursuant to this provision.

10.2 Hazardous Materials. Unless otherwise specified in the Contract Documents, this Contract does not include the removal, handling, or disturbance of any asbestos or other Hazardous Materials. If Contractor encounters materials on the Project site that Contractor reasonably believes to be asbestos or other Hazardous Materials, and the asbestos or other Hazardous Materials have not been rendered harmless, Contractor may continue Work in unaffected areas reasonably believed to be safe but must immediately cease work on the area affected and report the condition to City. No asbestos, asbestos-containing products or other Hazardous Materials may be used in performance of the Work.

10.3 Material Safety. Contractor is solely responsible for complying with § 5194 of Title 8 of the California Code of Regulations, including by providing information to Contractor's employees about any hazardous chemicals to which they may be exposed in the course of the Work. A hazard communication program and other forms of warning and training about such exposure must be used. Contractor must also maintain Safety Data Sheets ("SDS") at the Project site, as required by Laws, for materials or substances used or consumed in the performance of the Work. The SDS will be accessible and available to Contractor's employees, Subcontractors, and City.

(A) **Contractor Obligations.** Contractor is solely responsible for the proper delivery, handling, use, storage, removal, and disposal of all materials brought to the Project site and/or used in the performance of the Work. Contractor must notify the Engineer if a specified product or material cannot be used safely.

(B) **Labeling.** Contractor must ensure proper labeling on any material brought onto the Project site so that any persons working with or in the vicinity of the material may be informed as to the identity of the material, any potential hazards, and requirements for proper handling, protections, and disposal.

10.4 Hazardous Condition. Contractor is solely responsible for determining whether a hazardous condition exists or is created during the course of the Work, involving a risk of bodily harm to any person or risk of damage to any property. If a hazardous condition exists or is created, Contractor must take all precautions necessary to address the condition and ensure that the Work progresses safely under the circumstances. Hazardous conditions may result from, but are not

limited to, use of specified materials or equipment, the Work location, the Project site condition, the method of construction, or the way any Work must be performed.

- 10.5 Emergencies.** In an emergency affecting the safety or protection of persons, Work, or property at or adjacent to any Worksite, Contractor must take reasonable and prompt actions to prevent damage, injury, or loss, without prior authorization from the City if, under the circumstances, there is inadequate time to seek prior authorization from the City.
- 10.6 Confined Space Operations.** If the Work requires a confined space entry, including, but not limited to, manhole or water storage tank entry, Contractor must obtain a confined space entry permit pursuant to Cal/OSHA regulations, as set forth in 8 CCR § 5156 et seq. For any confined space entry for construction operations regulated by 8 CCR § 1502, Contractor must comply with 8 CCR § 5158. For any other confined space operations, Contractor must comply with 8 CCR § 5157. With respect to entry to any City-maintained confined space, Contractor is responsible for obtaining any available information regarding hazards and operations for any City-maintained confined spaces, pursuant to 8 CCR § 5157. The City-maintained Confined Space Entry Manual is available for viewing at the Water Department or Transportation and Public Works Department office. Contractor must immediately notify the Engineer of any previously unidentified hazards confronted or created during confined space entry.

Article 11 - Completion and Warranty Provisions

11.1 Final Completion.

- (A) **Final Inspection and Punch List.** When the Work required by this Contract is fully performed, Contractor must provide written notification to City requesting final inspection. The Engineer will schedule the date and time for final inspection, which must include Contractor's primary representative for this Project and its superintendent. Based on that inspection, City will prepare a punch list of any items that are incomplete, missing, defective, incorrectly installed, or otherwise not compliant with the Contract Documents. The punch list to Contractor will specify the time by which all of the punch list items must be completed or corrected. The punch list may include City's estimated cost to complete each punch list item if Contractor fails to do so within the specified time. The omission of any non-compliant item from a punch list will not relieve Contractor from fulfilling all requirements of the Contract Documents. Contractor's failure to complete any punch list item within the time specified in the punch list will not waive or abridge its warranty obligations for any such items that must be completed by the City or by a third party retained by the City due to Contractor's failure to timely complete any such outstanding item.
- (B) **Requirements for Final Completion.** Final Completion will be achieved upon completion or correction of all punch list items, as verified by City's further inspection, and upon satisfaction of all other Contract requirements, including any commissioning required under the Contract Documents and submission of all final submittals, including instructions and manuals as required under Section 7.10, and complete, final as-built drawings as required under Section 7.11, all to City's satisfaction.
- (C) **Acceptance.** The Project will be considered accepted upon the date of the Engineer's issuance of a written notice of acceptance. In order to avoid delay of Project close out, the City may elect, acting in its sole discretion, to accept the Project as complete subject to exceptions for punch list items that are not completed within the time specified in the punch list.
- (D) **Final Payment and Release of Retention.** Final Payment and release of retention, less any sums withheld pursuant to the provisions of the Contract Documents, will not be made sooner than 35 days after recordation of the notice of completion. If Contractor fails to complete all of the punch list items within the specified time, City may withhold up to 150% of City's estimated cost to complete each of the remaining items from Final Payment and may use the withheld retention to pay for the costs to self-perform the outstanding items or to retain a third party to complete any such outstanding punch list item.

11.2 Warranty.

(A) **General.** Contractor warrants that all materials and equipment will be new unless otherwise specified, of good quality, in conformance with the Contract Documents, and free from defective workmanship and materials. Contractor further warrants that the Work will be free from material defects not intrinsic in the design or materials required in the Contract Documents. Contractor warrants that materials or items incorporated into the Work comply with the requirements and standards in the Contract Documents, including compliance with Laws, and that any Hazardous Materials encountered or used were handled as required by Laws. At City's request, Contractor must furnish satisfactory evidence of the quality and type of materials and equipment furnished. Contractor's warranty does not extend to damage caused by normal wear and tear, or improper use or maintenance.

(B) **Warranty Period.** Contractor's warranty must guarantee its Work for a period of one year from the date of Project acceptance pursuant to Section 11.1(C) (the "Warranty Period"), except when a longer guarantee is provided by a supplier or manufacturer or is required by the Specifications or Special Conditions. If the City accepts the Project as complete subject to exceptions for incomplete punch list item(s) and the Contractor thereafter completes the punch list item(s), the completed punch list item(s) will be subject to the warranty provisions in this Section 11.2 for a one-year period that begins upon City's acceptance of the completed punch list item(s). Contractor must obtain from its Subcontractors, suppliers and manufacturers any special or extended warranties required by the Contract Documents.

(C) **Warranty Documents.** As a condition precedent to Final Completion, Contractor must supply City with all warranty and guarantee documents relevant to equipment and materials incorporated into the Work and guaranteed by their suppliers or manufacturers.

(D) **Subcontractors.** The warranty obligations in the Contract Documents apply to Work performed by Contractor and its Subcontractors, and Contractor agrees to be co-guarantor of such Work.

(E) **Contractor's Obligations.** Upon written notice from City to Contractor of any defect in the Work discovered during the Warranty Period, Contractor or its responsible Subcontractor must promptly correct the defective Work at its own cost. Contractor's obligation to correct defects discovered during the Warranty Period will continue past the expiration of the Warranty Period as to any defects in Work for which Contractor was notified prior to expiration of the Warranty Period. Work performed during the Warranty Period ("Warranty Work") will be subject to the warranty provisions in this Section 11.2 for a one-year period that begins upon completion of such Warranty Work to City's satisfaction.

(F) **City's Remedies.** If Contractor or its responsible Subcontractor fails to correct defective Work within ten days following notice by City, or sooner if required by the circumstances, City may correct the defects to conform with the Contract Documents at Contractor's sole expense. Contractor must reimburse City for its costs in accordance with subsection (H), below.

(G) **Emergency Repairs.** In cases of emergency where any delay in correcting defective Work could cause harm, loss or damage, City may immediately correct the defects to conform with the Contract Documents at Contractor's sole expense. Contractor or its surety must reimburse City for its costs in accordance with subsection (H), below.

(H) **Reimbursement.** Contractor must reimburse City for its costs to repair under subsections (F) or (G), above, within 30 days following City's submission of a demand for payment pursuant to this provision. If City is required to initiate legal action to compel Contractor's compliance with this provision, and City is the prevailing party in such action, Contractor and its surety are solely responsible for all of City's attorney's fees and legal costs expended to enforce Contractor's warranty obligations herein, in addition to any and all costs City incurs to correct the defective Work.

11.3 Use Prior to Final Completion. City reserves the right to occupy or make use of the Project, or any portions of the Project, prior to Final Completion if City has determined that the Project or portion of it is in a condition suitable for the proposed occupation or use, and that it is in its best interest to occupy or make use of the Project, or any portions of it, prior to Final Completion.

(A) **Non-Waiver.** Occupation or use of the Project, in whole or in part, prior to Final Completion will not operate as acceptance of the Work or any portion of it, nor will it operate as a waiver of any of City's rights or Contractor's duties pursuant to these Contract Documents, and will not affect nor bear on the determination of the time of substantial completion with respect to any statute of repose pertaining to the time for filing an action for construction defect.

(B) **City's Responsibility.** City will be responsible for the cost of maintenance and repairs due to normal wear and tear with respect to those portions of the Project that are being occupied or used before Final Completion. The Contract Price or the Contract Time may be adjusted pursuant to the applicable provisions of these Contract Documents if, and only to the extent that, any occupation or use under this Section actually adds to Contractor's cost or time to complete the Work within the Contract Time.

11.4 Substantial Completion. For purposes of determining "substantial completion" with respect to any statute of repose pertaining to the time for filing an action for construction defect, "substantial completion" is deemed to mean the last date that Contractor or any Subcontractor performs Work on the Project prior to City acceptance of the Project, except for warranty work performed under this Article.

Article 12 - Dispute Resolution

12.1 Claims. This Article applies to and provides the exclusive procedures for any Claim arising from or related to the Contract or performance of the Work.

(A) **Limitations.** A Claim may only include the portion of a previously rejected demand that remains in dispute between Contractor and City. With the exception of any dispute regarding the amount of money actually paid to Contractor as Final Payment, Contractor is not entitled to submit a Claim demanding a change in the Contract Time or the Contract Price, which has not previously been submitted to City in full compliance with Article 5 and Article 6, and subsequently rejected in whole or in part by City.

(B) **Scope of Article.** This Article is intended to provide the exclusive procedures for submission and resolution of Claims of any amount and applies in addition to the provisions of Public Contract Code § 9204 and § 20104 et seq., which are incorporated by reference herein.

(C) **No Work Delay.** Notwithstanding the submission of a Claim or any other dispute between the parties related to the Project or the Contract Documents, Contractor must perform the Work and may not delay or cease Work pending resolution of a Claim or other dispute but must continue to diligently prosecute the performance and timely completion of the Work, including the Work pertaining to the Claim or other dispute.

(D) **Informal Resolution.** Contractor will make a good faith effort to informally resolve a dispute before initiating a Claim, preferably by face-to-face meeting between authorized representatives of Contractor and City.

12.2 Claims Submission. The following requirements apply to any Claim subject to this Article:

(A) **Substantiation.** The Claim must be submitted to City in writing by registered or certified mail with return receipt requested and clearly identified as a "Claim" submitted pursuant to this Article 12. The Claim must include all of the documents necessary to substantiate the Claim including the Change Order request that was rejected in whole or in part, and a copy of City's written rejection that is in dispute. The Claim must clearly identify and describe the dispute, including relevant references to applicable portions of the Contract Documents, and a chronology of relevant events. Any Claim for additional payment must include a complete, itemized

breakdown of all known or estimated labor, materials, taxes, insurance, and subcontract, or other costs. Substantiating documentation such as payroll records, receipts, invoices, or the like, must be submitted in support of each component of claimed cost. Any Claim for an extension of time or delay costs must be substantiated with a schedule analysis and narrative depicting and explaining claimed time impacts.

(B) ***Claim Format and Content.*** A Claim must be submitted in the following format:

(1) Provide a cover letter, specifically identifying the submission as a “Claim” submitted under this Article 12 and specifying the requested remedy (e.g., amount of proposed change to Contract Price and/or change to Contract Time).

(2) Provide a summary of each Claim, including underlying facts and the basis for entitlement, and identify each specific demand at issue, including the specific Change Order request (by number and submittal date), and the date of City’s rejection of that demand, in whole or in part.

(3) Provide a detailed explanation of each issue in dispute. For multiple issues included within a single Claim or for multiple Claims submitted concurrently, separately number and identify each individual issue or Claim, and include the following for each separate issue or Claim:

- a. A succinct statement of the matter in dispute, including Contractor’s position and the basis for that position;
- b. Identify and attach all documents that substantiate the Claim, including relevant provisions of the Contract Documents, RFIs, calculations, and schedule analysis (see subsection (A), Substantiation, above);
- c. A chronology of relevant events; and
- d. Analysis and basis for claimed changes to Contract Price, Contract Time, or any other remedy requested.

(4) Provide a summary of issues and corresponding claimed damages. If, by the time of the Claim submission deadline (below), the precise amount of the requested change in the Contract Price or Contract Time is not yet known, Contractor must provide a good faith estimate, including the basis for that estimate, and must identify the date by which it is anticipated that the Claim will be updated to provide final amounts.

(5) Include the following certification, executed by Contractor’s authorized representative:

“The undersigned Contractor certifies under penalty of perjury that its statements and representations in this Claim submittal are true and correct. Contractor warrants that this Claim submittal is comprehensive and complete as to the matters in dispute, and agrees that any costs, expenses, or delay not included herein are deemed waived.”

(C) **Submission Deadlines.**

(1) A Claim disputing rejection of a request for a change in the Contract Time or Contract Price must be submitted within 21 days following the date that City notified Contractor in writing that a request for a change in the Contract Time or Contract Price, duly submitted in compliance with Article 5 and Article 6, has been rejected in whole or in part. A Claim disputing the terms of a unilateral Change Order must be submitted within 21 days following the date of issuance of the unilateral Change Order. These Claim deadlines apply even if Contractor cannot yet quantify the total amount of any requested change in the Contract Time or Contract Price. If the Contractor cannot quantify those amounts, it must submit an estimate of the amounts claimed pending final determination of the requested remedy by Contractor.

(2) With the exception of any dispute regarding the amount of Final Payment, any Claim must be filed on or before the date of Final Payment or will be deemed waived.

(3) A Claim disputing the amount of Final Payment must be submitted within 21 days of the effective date of Final Payment, under Section 8.7, Final Payment.

(4) Strict compliance with these Claim submission deadlines is necessary to ensure that any dispute may be mitigated as soon as possible, and to facilitate cost-efficient administration of the Project. **Any Claim that is not submitted within the specified deadlines will be deemed waived by Contractor.**

12.3 City's Response. City will respond within 45 days of receipt of the Claim with a written statement identifying which portion(s) of the Claim are disputed, unless the 45-day period is extended by mutual agreement of City and Contractor or as otherwise allowed under Public Contract Code § 9204. However, if City determines that the Claim is not adequately substantiated pursuant to Section 12.2(A), Substantiation, City may first request in writing, within 30 days of receipt of the Claim, any additional documentation supporting the Claim or relating to defenses to the Claim that City may have against the Claim.

(A) **Additional Information.** If additional information is thereafter required, it may be requested and provided upon mutual agreement of City and Contractor. If Contractor's Claim is based on estimated amounts, Contractor has a continuing duty to update its Claim as soon as possible with information on actual amounts in order to facilitate prompt and fair resolution of the Claim.

(B) **Non-Waiver.** Any failure by City to respond within the times specified above will not be construed as acceptance of the Claim, in whole or in part, or as a waiver of any provision of these Contract Documents.

12.4 Meet and Confer. If Contractor disputes City's written response, or City fails to respond within the specified time, within 15 days of receipt of City's response or within 15 days of City's failure to respond within the applicable 45-day time period under Section 12.3, respectively, Contractor may notify City of the dispute in writing sent by registered or certified mail, return receipt requested, and demand an informal conference to meet and confer for settlement of the issues in dispute. If Contractor fails to notify City of the dispute and demand for an informal conference to meet and confer in writing within the specified time, Contractor's Claim will be deemed waived.

(A) **Schedule Meet and Confer.** Upon receipt of the demand to meet and confer, City will schedule the meet and confer conference to be held within 30 days, or later if needed to ensure the mutual availability of each of the individuals that each party requires to represent its interests at the meet and confer conference.

(B) **Location for Meet and Confer.** The meet and confer conference will be scheduled at a location at or near City's principal office.

(C) **Written Statement After Meet and Confer.** Within ten working days after the meet and confer has concluded, City will issue a written statement identifying which portion(s) of the Claim remain in dispute, if any.

(D) **Submission to Mediation.** If the Claim or any portion remains in dispute following the meet and confer conference, within ten working days after the City issues the written statement identifying any portion(s) of the Claim remaining in dispute, the Contractor may identify in writing disputed portion(s) of the Claim, which will be submitted for mediation, as set forth below.

12.5 Mediation and Government Code Claims.

(A) **Mediation.** Within ten working days after the City issues the written statement identifying any portion(s) of the Claim remaining in dispute following the meet and confer, City and Contractor will mutually agree to a mediator, as provided under Public Contract Code § 9204. Mediation will be scheduled to ensure the mutual availability of the selected mediator and all of the individuals that each party requires to represent its interests. If there are multiple Claims in dispute, the parties may agree to schedule the mediation to address all outstanding Claims at the same time. The parties will share the costs of the mediator and mediation fees equally, but each party is otherwise solely and separately responsible for its own costs to prepare for and participate in the mediation, including costs for its legal counsel or any other consultants.

(B) **Government Code Claims.**

(1) Timely presentation of a Government Code Claim is a condition precedent to filing any legal action based on or arising from the Contract. Compliance with the Claim submission requirements in this Article 12 is a condition precedent to filing a Government Code Claim.

(2) The time for filing a Government Code Claim will be tolled from the time Contractor submits its written Claim pursuant to Section 12.2, above, until the time that Claim is denied in whole or in part at the conclusion of the meet and confer process, including any period of time used by the meet and confer process. However, if the Claim is submitted to mediation, the time for filing a Government Code Claim will be tolled until conclusion of the mediation, including any continuations, if the Claim is not fully resolved by mutual agreement of the parties during the mediation or any continuation of the mediation.

12.6 Tort Claims. This Article does not apply to tort claims and nothing in this Article is intended nor will be construed to change the time periods for filing tort-based Government Code Claims.

12.7 Arbitration. City does not consent to arbitration unless required by Laws. It is expressly agreed, under Code of Civil Procedure § 1296, that in any arbitration to resolve a dispute relating to this Contract, the arbitrator's award must be supported by law and substantial evidence.

12.8 Burden of Proof and Limitations. Contractor bears the burden of proving entitlement to and the amount of any claimed damages. Contractor is not entitled to damages calculated on a total cost basis but must prove actual damages. Contractor is not entitled to speculative, special, or consequential damages, including home office overhead or any form of overhead not directly incurred at the Project site or any other Worksite; lost profits; loss of productivity; lost opportunity to work on other projects; diminished bonding capacity; increased cost of financing for the Project; extended capital costs; non-availability of labor, material or equipment due to delays; or any other indirect loss arising from the Contract. The Eichleay Formula or similar formula will not be used for any recovery under the Contract. The City will not be directly liable to any Subcontractor or supplier.

12.9 Legal Proceedings. In any legal proceeding that involves enforcement of any requirements of the Contract Documents, the finder of fact will receive detailed instructions on the meaning and operation of the Contract Documents, including conditions, limitations of liability, remedies, claim procedures, and other provisions bearing on the defenses and theories of liability. Detailed

findings of fact will be requested to verify enforcement of the Contract Documents. All of the City's remedies under the Contract Documents will be construed as cumulative, and not exclusive, and the City reserves all rights to all remedies available under law or equity as to any dispute arising from or relating to the Contract Documents or performance of the Work.

- 12.10 Other Disputes.** The procedures in this Article 12 will apply to any and all disputes or legal actions, in addition to Claims, arising from or related to this Contract, including disputes regarding suspension or early termination of the Contract, unless and only to the extent that compliance with a procedural requirement is expressly and specifically waived by City. Nothing in this Article is intended to delay suspension or termination under Article 13.

Article 13 - Suspension and Termination

- 13.1 Suspension for Cause.** In addition to all other remedies available to City, if Contractor fails to perform or correct Work in accordance with the Contract Documents, including non-compliance with applicable environmental or health and safety Laws, City may immediately order the Work, or any portion of it, suspended until the circumstances giving rise to the suspension have been eliminated to City's satisfaction.

(A) **Notice of Suspension.** Upon receipt of City's written notice to suspend the Work, in whole or in part, except as otherwise specified in the notice of suspension, Contractor and its Subcontractors must promptly stop Work as specified in the notice of suspension; comply with directions for cleaning and securing the Worksite; and protect the completed and in-progress Work and materials. Contractor is solely responsible for any damages or loss resulting from its failure to adequately secure and protect the Project.

(B) **Resumption of Work.** Upon receipt of the City's written notice to resume the suspended Work, in whole or in part, except as otherwise specified in the notice to resume, Contractor and its Subcontractors must promptly re-mobilize and resume the Work as specified; and within ten days from the date of the notice to resume, Contractor must submit a recovery schedule, prepared in accordance with the Contract Documents, showing how Contractor will complete the Work within the Contract Time.

(C) **Failure to Comply.** Contractor will not be entitled to an increase in the Contract Time or Contract Price for a suspension occasioned by Contractor's failure to comply with the Contract Documents.

(D) **No Duty to Suspend.** City's right to suspend the Work will not give rise to a duty to suspend the Work, and City's failure to suspend the Work will not constitute a defense to Contractor's failure to comply with the requirements of the Contract Documents.

- 13.2 Suspension for Convenience.** City reserves the right to suspend, delay, or interrupt the performance of the Work in whole or in part, for a period of time determined to be appropriate for City's convenience. Upon notice by City pursuant to this provision, Contractor must immediately suspend, delay, or interrupt the Work and secure the Project site as directed by City except for taking measures to protect completed or in-progress Work as directed in the suspension notice, and subject to the provisions of Section 13.1(A) and (B), above. If Contractor submits a timely request for a Change Order in compliance with Articles 5 and 6, the Contract Price and the Contract Time will be equitably adjusted by Change Order pursuant to the terms of Articles 5 and 6 to reflect the cost and delay impact occasioned by such suspension for convenience, except to the extent that any such impacts were caused by Contractor's failure to comply with the Contract Documents or the terms of the suspension notice or notice to resume. However, the Contract Time will only be extended if the suspension causes or will cause unavoidable delay in Final Completion. If Contractor disputes the terms of a Change Order issued for such equitable adjustment due to suspension for convenience, its sole recourse is to comply with the Claim procedures in Article 12.

13.3 Termination for Default. City may declare that Contractor is in default of the Contract for a material breach of or inability to fully, promptly, or satisfactorily perform its obligations under the Contract.

(A) **Default.** Events giving rise to a declaration of default include Contractor's refusal or failure to supply sufficient skilled workers, proper materials, or equipment to perform the Work within the Contract Time; Contractor's refusal or failure to make prompt payment to its employees, Subcontractors, or suppliers or to correct defective Work or damage; Contractor's failure to comply with Laws, or orders of any public agency with jurisdiction over the Project; evidence of Contractor's bankruptcy, insolvency, or lack of financial capacity to complete the Work as required within the Contract Time; suspension, revocation, or expiration and nonrenewal of Contractor's license or DIR registration; Contractor's failure to procure, maintain, or renew insurance coverage or provide notice of any modifications or reductions in insurance coverage; dissolution, liquidation, reorganization, or other major change in Contractor's organization, ownership, structure, or existence as a business entity; unauthorized assignment of Contractor's rights or duties under the Contract; or any material breach of the Contract requirements.

(B) **Notice of Default and Opportunity to Cure.** Upon City's declaration that Contractor is in default due to a material breach of the Contract Documents, if City determines that the default is curable, City will afford Contractor the opportunity to cure the default within ten days of City's notice of default, or within a period of time reasonably necessary for such cure, including a shorter period of time if applicable.

(C) **Termination.** If Contractor fails to cure the default or fails to expediently take steps reasonably calculated to cure the default within the time period specified in the notice of default, City may issue written notice to Contractor and its performance bond surety of City's termination of the Contract for default.

(D) **Waiver.** Time being of the essence in the performance of the Work, if Contractor's surety fails to arrange for completion of the Work in accordance with the Performance Bond within seven calendar days from the date of the notice of termination pursuant to paragraph (C), City may immediately make arrangements for the completion of the Work through use of its own forces, by hiring a replacement contractor, or by any other means that City determines advisable under the circumstances. Contractor and its surety will be jointly and severally liable for any additional cost incurred by City to complete the Work following termination, where "additional cost" means all cost in excess of the cost City would have incurred if Contractor had timely completed Work without the default and termination. In addition, City will have the right to immediate possession and use of any materials, supplies, and equipment procured for the Project and located at the Project site or any Worksite on City property for the purposes of completing the remaining Work.

(E) **Compensation.** Within 30 days of receipt of updated as-builts, all warranties, manuals, instructions, or other required documents for Work installed to date, and delivery to City of all equipment and materials for the Project for which Contractor has already been compensated, Contractor will be compensated for the Work satisfactorily performed in compliance with the Contract Documents up to the effective date of the termination pursuant to the terms of Article 8, Payment, subject to City's rights to withhold or deduct sums from payment otherwise due pursuant to Section 8.3, and excluding any costs Contractor incurs as a result of the termination, including any cancellation or restocking charges or fees due to third parties. If Contractor disputes the amount of compensation determined by City, its sole recourse is to comply with the Claim Procedures in Article 12, by submitting a Claim no later than 30 days following notice from City of the total compensation to be paid by City.

(F) **Wrongful Termination.** If Contractor disputes the termination, its sole recourse is to comply with the Claim procedures in Article 12. If a court of competent jurisdiction or an arbitrator later determines that the termination for default was wrongful, the termination will be deemed to be a termination for convenience, and Contractor's damages will be strictly limited to the compensation provided for termination for convenience under Section 13.4, below. Contractor waives any claim for any other damages for wrongful termination including special or

consequential damages, lost opportunity costs, or lost profits, and any award of damages is subject to Section 12.8, Burden of Proof and Limitations.

13.4 Termination for Convenience. City reserves the right, acting in its sole discretion, to terminate all or part of the Contract for convenience upon written notice to Contractor.

(A) **Compensation to Contractor.** In the event of City's termination for convenience, Contractor waives any claim for damages, including for loss of anticipated profits from the Project. The following will constitute full and fair compensation to Contractor, and Contractor will not be entitled to any additional claim or compensation:

(1) **Completed Work.** The value of its Work satisfactorily performed as of the date notice of termination is received, based on Contractor's schedule of values and unpaid costs for items delivered to the Project site that were fabricated for incorporation in the Work;

(2) **Demobilization.** Demobilization costs specified in the schedule of values, or if demobilization costs were not provided in a schedule of values pursuant to Section 8.1, then based on actual, reasonable, and fully documented demobilization costs; and

(3) **Termination Markup.** Five percent of the total value of the Work performed as of the date of notice of termination, including reasonable, actual, and documented costs to comply with the direction in the notice of termination for convenience, and demobilization costs, which is deemed to cover all overhead and profit to date.

(B) **Disputes.** If Contractor disputes the amount of compensation determined by City pursuant to paragraph (A), above, its sole recourse is to comply with the Claim procedures in Article 12, by submitting a Claim no later than 30 days following notice from City of total compensation to be paid by City.

13.5 Actions Upon Termination for Default or Convenience. The following provisions apply to any termination under this Article, whether for default or convenience, and whether in whole or in part.

(A) **General.** Upon termination, City may immediately enter upon and take possession of the Project and the Work and all tools, equipment, appliances, materials, and supplies procured or fabricated for the Project. Contractor will transfer title to and deliver all completed Work and all Work in progress to City.

(B) **Submittals.** Unless otherwise specified in the notice of termination, Contractor must immediately submit to City all designs, drawings, as-built drawings, Project records, contracts with vendors and Subcontractors, manufacturer warranties, manuals, and other such submittals or Work-related documents required under the terms of the Contract Documents, including incomplete documents or drafts.

(C) **Close Out Requirements.** Except as otherwise specified in the notice of termination, Contractor must comply with all of the following:

(1) Immediately stop the Work, except for any Work that must be completed pursuant to the notice of termination and comply with City's instructions for cessation of labor and securing the Project and any other Worksite(s).

(2) Comply with City's instructions to protect the completed Work and materials, using best efforts to minimize further costs.

(3) Contractor must not place further orders or enter into new subcontracts for materials, equipment, services or facilities, except as may be necessary to complete any portion of the Work that is not terminated.

(4) As directed in the notice, Contractor must assign to City or cancel existing subcontracts that relate to performance of the terminated Work, subject to any prior

rights, if any, of the surety for Contractor's performance bond, and settle all outstanding liabilities and claims, subject to City's approval.

(5) As directed in the notice, Contractor must use its best efforts to sell any materials, supplies, or equipment intended solely for the terminated Work in a manner and at market rate prices acceptable to City.

(D) **Payment Upon Termination.** Upon completion of all termination obligations, as specified herein and in the notice of termination, Contractor will submit its request for Final Payment, including any amounts due following termination pursuant to this Article 13. Payment will be made in accordance with the provisions of Article 8, based on the portion of the Work satisfactorily completed, including the close out requirements, and consistent with the previously submitted schedule of values and unit pricing, including demobilization costs. Adjustments to Final Payment may include deductions for the cost of materials, supplies, or equipment retained by Contractor; payments received for sale of any such materials, supplies, or equipment, less re-stocking fees charged; and as otherwise specified in Section 8.3, Adjustment of Payment Application.

(E) **Continuing Obligations.** Regardless of any Contract termination, Contractor's obligations for portions of the Work already performed will continue and the provisions of the Contract Documents will remain in effect as to any claim, indemnity obligation, warranties, guarantees, submittals of as-built drawings, instructions, or manuals, record maintenance, or other such rights and obligations arising prior to the termination date.

Article 14 - Miscellaneous Provisions

- 14.1 Assignment of Unfair Business Practice Claims.** Under Public Contract Code § 7103.5, Contractor and its Subcontractors agree to assign to City all rights, title, and interest in and to all causes of action it may have under section 4 of the Clayton Act (15 U.S.C. § 15) or under the Cartwright Act (Chapter 2 (commencing with § 16700) of Part 2 of Division 7 of the Business and Professions Code), arising from purchases of goods, services, or materials pursuant to the Contract or any subcontract. This assignment will be effective at the time City tenders Final Payment to Contractor, without further acknowledgement by the parties.
- 14.2 Provisions Deemed Inserted.** Every provision of law required to be inserted in the Contract Documents is deemed to be inserted, and the Contract Documents will be construed and enforced as though such provision has been included. If it is discovered that through mistake or otherwise that any required provision was not inserted, or not correctly inserted, the Contract Documents will be deemed amended accordingly.
- 14.3 Waiver.** City's waiver of a breach, failure of any condition, or any right or remedy contained in or granted by the provisions of the Contract Documents will not be effective unless it is in writing and signed by City. City's waiver of any breach, failure, right, or remedy will not be deemed a waiver of any other breach, failure, right, or remedy, whether or not similar, nor will any waiver constitute a continuing waiver unless specified in writing by City.
- 14.4 Titles, Headings, and Groupings.** The titles and headings used and the groupings of provisions in the Contract Documents are for convenience only and may not be used in the construction or interpretation of the Contract Documents or relied upon for any other purpose.
- 14.5 Statutory and Regulatory References.** With respect to any amendments to any statutes or regulations referenced in these Contract Documents, the reference is deemed to be the version in effect on the date that bids were due.
- 14.6 Survival.** The provisions that survive termination or expiration of this Contract include Contract Section 11, Notice, and subsections 12.1, 12.2, 12.3, 12.4, 12.5, and 12.6 of Section 12, General Provisions; and the following provisions in these General Conditions: Section 2.2(J), Contractor's Records, Section 2.3(C), Termination, Section 3.7, Ownership, Section 4.2, Indemnity, Article 12, Dispute Resolution, and Section 11.2, Warranty.

END OF GENERAL CONDITIONS

Special Conditions

1. Authorized Work Days and Hours.

- 1.1 Authorized Work Days.** Except as expressly authorized in writing by City, Contractor is limited to performing Work on the Project on the following days of the week, excluding holidays observed by City:
Monday to Friday
- 1.2 Authorized Work Hours.** Except as expressly authorized in writing by City, Contractor is limited to performing Work on the Project during the following hours: **7:00 a.m. to 7:00 p.m.**

2. Advance Order Requirement.

- 2.1 Materials and Equipment.** Within five days following receipt of the fully executed Contract from City, Contractor must promptly order the following materials and/or equipment and submit documentation to City evidencing the order, including, but not limited to, the purchase order, documentation showing that the order has been accepted by supplier(s), and the anticipated shipment and delivery date for the materials and/or equipment:
- (A) MODULAR BUS PLATFORM SYSTEM BY ZICLA (2 EA)
(B) BUS STOP SHELTERS (2 EA)
(C) BUS STOP BENCHES (4 EA)
- 2.2 Delivery Notification.** Within two days following delivery of the specified materials and/or equipment to Contractor, Contractor must provide written notice of the delivery to the Engineer. Except as set forth in this Section, Contractor will not perform any Work until the start date set forth in the Notice to Proceed. City anticipates issuing the Notice to Proceed following delivery of the materials and/or equipment set forth in this Section to Contractor.
- 2.3 Application for Payment.** Contractor may request payment for the materials and/or equipment specified in this Section, which are delivered to a Worksite but not yet incorporated into the Work, subject to the following conditions: the materials and/or equipment must be delivered and suitably stored at a local Worksite agreed to, in writing, by City; full title vests in City at the time of delivery to the agreed upon Worksite; Contractor obtains and submits to City a negotiable warehouse receipt, endorsed over to City for materials and/or equipment stored in an off-site warehouse; the materials and/or equipment are segregated and labeled or tagged to identify the Project; the materials and/or equipment are protected from damage, weather, and contamination; if any defects or damage are discovered after delivery, Contractor agrees to replace the materials and/or equipment at Contractor's expense; and Contractor's application for payment is accompanied by a bill of sale, invoice, or other documentation warranting that City has received the materials and equipment free and clear of all liens and evidence that the materials and equipment are covered by appropriate property insurance and other arrangements to protect City's interest therein, all of which must be satisfactory to City. If these conditions are satisfied, Contractor's application for payment may include up to 100% of the cost of the materials and/or equipment delivered, but not yet incorporated into the Work.

- 3. Construction Manager Role and Authority.** The City Plans to contract with a Construction Manager for this Project. The Construction Manager will assist City in the management of the construction of the Project. The Construction Manager may perform services in the areas of supervision and coordination of the work of Contractor and/or other contractors, scheduling the

Work, monitoring the progress of the Work, providing City with evaluations and recommendations concerning the quality of the Work, recommending the approval of progress payments to Contractor, or other services for the Project in accordance with the Construction Manager's contract with City.

- 3.1 Communications.** Contractor must submit all notices and communications relating to the Work directly to the Construction Manager in writing, as follows:

Construction Manager:

Contact information to be provided in the Meeting Minutes following the Pre-Construction Conference.

With a copy to the Engineer:

Greg Dwyer

69 Stony Circle, Santa Rosa CA 95401

gdwyer@srcity.org

- 3.2 On-Site Management and Communication Procedures.** The Construction Manager will provide and maintain a management team on the Project site to provide contract administration as an agent of City and will establish and implement coordination and communication procedures among City, the Design Professional, Contractor, and others.
- 3.3 Contract Administration Procedures.** The Construction Manager will establish and implement procedures for reviewing and processing requests for clarifications and interpretations of the Contract Documents, Shop Drawings, samples, other submittals, schedule adjustments, Change Order proposals, written proposals for substitutions, payment applications, and maintenance of logs.
- 3.4 Pre-Construction Conference.** Contractor will attend the pre-construction conference, during which the Construction Manager will review the Contract administration procedures and Project requirements.
- 3.5 Contractor's Construction Schedule.** The Construction Manager will review Contractor's construction schedules and will verify that each schedule is prepared in accordance with the requirements of the Contract Documents.
- 4. Survey Staking.** Contractor is not responsible for providing the construction stakes for the Project. Contractor will coordinate directly with the Engineer for City-provided construction stakes. Contractor must submit a written request for staking to the Engineer at least four Working Days in advance of the date and time stakes are needed for the Work. Contractor must promptly notify the Engineer of any discrepancies found between City-provided staking and information provided by the Contract Documents. Contractor must preserve any City-provided construction stakes. If City is required to replace City-provided construction stakes, Contractor will be responsible for the cost thereof, which may be deducted from payments otherwise due to Contractor.
- 5 Close Out Requirements.** Contractor's close out requirements include the following, if applicable:
- 5.1** Contractor must replace, with thermoplastic, any existing striping within and adjacent to the Project site that is damaged during the Work. Partially damaged striping must be replaced in its entirety.

END OF SPECIAL CONDITIONS



TECHNICAL SPECIFICATIONS

FOR

SONOMA AVE PAVEMENT REHABILITATION – FARMERS LN TO HAHMAN DR

CONTRACT NO. C02261



Jim Bui
07/18/2025

2025

TABLE OF CONTENTS

Table of Contents	1
10 General Construction	1
10-3 MOBILIZATION	1
10-3.01 General	1
10-3.02 Payment.....	1
10-5 DUST CONTROL.....	1
10-5.01 General	1
10-5.02 Payment.....	2
12 Temporary Traffic Control.....	3
12-1 GENERAL	3
12-1.01 General	3
12-1.04 Payment.....	3
12-3 Traffic-Handling Equipment and Devices.....	3
12-3.01 General	3
12-4 Maintaining Traffic.....	4
12-4.01A General	4
12-4.02 Closure Requirements	4
12-4.04 Temporary Pedestrian Access Routes	6
13 Water Pollution Control	7
13-1 GENERAL	7
13-1.01 General	7
13-1.01B Definitions.....	7
13-2 Water Pollution Control Program	9
13-2.01C Submittals.....	9
13-2.04 Payment.....	9
13-3 Storm Water Pollution Prevention Plan	10
13-3.01A Summary.....	10
13-4 Job Site Management	11
13-4.03 Construction	11
13-4.03B: Spill Prevention and Control.....	11
13-4.03C Material Management.....	11
13-4.03D Waste Management.....	11
13-4.03E Nonstormwater Management.....	11
13-4.03F Sweeping.....	12
13-4.04 Payment.....	12
13-6 Temporary Sediment Control	13
13-6.03 CONSTRUCTION	13

13-6.03C Temporary Drainage Inlet Protection.....	13
13-6.04 PAYMENT	13
13-7 Temporary Tracking Control	14
13-7.01A General	14
13-7.01C Construction	14
13-7.03D Payment	14
14 Environmental Stewardship.....	15
14-10 Solid Waste Disposal and Recycling.....	15
14-10.01 General	15
14-10.02 Solid Waste Disposal and Recycling Report.....	15
14-10.03 Payment.....	15
15 Existing Facilities	16
15-1.03 Construction	16
15-1.03A General	16
15-2 Miscellaneous Facilities	16
15-2.02 REMOVE.....	16
15-2.08 RESET	16
15-2.09 PAYMENT	18
15-7 Utility Clearances	19
15-7.01 General	19
15-7.02 Payment.....	20
15-8 Tree Root Pruning	20
15-8.01 General	20
15-8.02 Payment.....	20
17 Earthwork and Landscape.....	21
17-2 Clearing and Grubbing	21
17-2.01 General	21
17-2.03 Construction	21
17-2.04 Payment.....	21
19 Earthwork.....	22
19-1 General.....	22
19-1.01 General	22
19-1.03 Construction	22
19-1.04 Payment.....	22
19-2 Roadway Excavation	22
19-2.03 Construction	22
19-5 Compaction.....	23
19-5.03 Construction	23
20 Landscape	24

20-1.02B Water:	24
20-2 IRRIGATION	24
20-2.01 GENERAL	24
26 Aggregate Bases	25
26-1.01 GENERAL	25
26-1.01A Summary	25
26-1.02 MATERIALS	25
26-1.02B Class 2 Aggregate Base	25
26-1.03 CONSTRUCTION	25
26-1.03E Compacting	25
26.104 PAYMENT	25
39 Hot Mix Asphalt	26
39-1 GENERAL	26
39-1.02 MATERIALS	26
39-2 HOT MIX ASPHALT	26
39-2.02 TYPE A HOT MIX ASPHALT	26
39-3 EXISTING ASPHALT CONCRETE	32
39-3.04 Cold Planing Asphalt Concrete Pavement	32
39A Hot Mix Asphalt Concrete Trench Paving	33
39A-1.01 Description	33
39A-2.01 Asphalts	33
39A-5.01 Spreading Equipment	33
39A-6.01 General Requirements	33
39A-6.03 Compacting	34
39A-8.02 Payment	34
40 Concrete Pavement	35
40-1 GENERAL	35
40-1.01 GENERAL	35
40-1.02 MATERIALS	37
40-1.03 CONSTRUCTION	39
40-1.04 PAYMENT	42
73 Concrete Curbs and Sidewalks	43
73-1 GENERAL	43
73-1.01 General	43
73-1.02 MATERIALS	43
73-2 CURBS	43
73-3 SIDEWALK, GUTTER DEPRESSION, ISLAND PAVING (MEDIAN CURB), CURB, RAMP, AND DRIVEWAY	43
73-3.03 Construction	43

73-3.04 Payment.....	44
78-2 Survey Monuments.....	46
78-2.01 General	46
80-1 Modular Bus Platform.....	47
80-1.01 GENERAL	47
80-1.02 MATERIALS.....	47
80-1.03 Shop Drawings	48
80-1.04 Construction	49
80-1.05 Warranty.....	49
80-1.06 Payment.....	50
80-2 BUS SHELTER AND BENCH	51
80-2.01 GENERAL	51
81 Miscellaneous Traffic Control Devices	52
81-3.01 General.....	52
81-3.02 Materials	52
81-3.02B Nonreflective Pavement Markers	52
81-3.02C Retroreflective Pavement Markers	52
81-3.03 Construction	52
82 Signs And Markers	53
82-1.01 General.....	53
82-2.04 Payment.....	53
84-2 Traffic Stripes and Pavement Markings.....	54
84-2.01 General.....	54
84-2.01A Summary	54
84-2.03 Construction	54
84-2.03C Application of Stripes and Markings.....	54
84-2.04A Measurement	54
84-2.04B Payment.....	55
84-7 Polymer Cement Surface System Pavement Markings [Not Used]	56
84-7.01 General.....	56
84-7.01A Summary	56
84-7.01A Submittals.....	56
84-7.02 Materials.....	56
84-7.02A General	56
84-2.03B Warranty.....	56
84-2.03B Chemical Admixtures/Pigments	56
84-7.03 Construction	56
84-7.03A General	56
84-7.03B Quality Assurance	57

84-7.03C Weather Limitations	57
84-7.03D Concrete Pavement Surface Preparation and Coordination.....	58
84-7.04E Curing and Opening to Traffic.....	58
84-7.04 Payment.....	58
87 Electrical Systems.....	59
87-1.01 GENERAL	59
87-1.02 DOCUMENTATION AND SUBMITTALS	59
87-1.03 DEPARTMENT ACCEPTANCE	59
87-1.04 METHODS AND MATERIALS.....	59
87-1.04A Concrete Pads, Foundations, and Pedestals	59
87-1.04B Pull Boxes.....	59
87-1.04C Conductors and Cables	59
87-1.04D Detectors.....	59
87-1.04E Excavating and Backfill for Electrical Systems	60
87-1.04F Traffic Signal Interconnect Systems.....	60
87-1.05 PAYMENT	60
90 Concrete.....	62
90-1.01 GENERAL	62
90-1.01C Submittals.....	62
90-1.01D Quality Assurance.....	62
112 Tree Protection	63
112-1.01 General	63
112-1.02 Scope.....	63
112-1.03 Payment.....	63
121 Notification	64
121-1.01 General	64
121-3.01 Payment.....	64
124 Material Recycling.....	65
124-1.01 Description.....	65
124-1.02 Payment.....	65
132 Water Distribution System.....	66
132-1.01 Description.....	66
132-1.11 Excavation, Backfill, and Resurfacing.....	66
132-1.15A Water Services.....	66
132-1.30 Payment.....	66

10 GENERAL CONSTRUCTION

10-3 MOBILIZATION

10-3.01 General: Mobilization shall conform to the Standard Specifications (Caltrans 2018 Specifications, latest revision), and any modifications herein.

Mobilization shall include the obtaining of all permits; moving onto the site with all equipment; and other construction facilities as required for the proper performance and completion of the work. Mobilization shall include demobilization as defined herein.

Your Mobilization shall include but not be limited to the following principal items:

1. Preparation of Contract.
2. Completion of all tasks and submittal of all documents (bonds, insurance, schedule, etc.) required as conditions of issuing the Notice to Proceed.
3. Obtaining all required permits, including a Caltrans encroachment permit for work near the intersection of Farmers drive.
4. Installation of project identification signs per Section 7-1.03A of these Special Provisions. You shall consult with the Engineer for placement.
5. Installing temporary construction water supply, power, wiring, and lighting facilities, as required.
6. Providing your own field office trailers if needed.
7. Moving onto the site(s) all your equipment required for operations.
8. Having all OSHA required notices and establishment of safety programs.
9. Attendance at Pre-Construction Conference with your principal construction personnel.

Demobilization shall include, but not limited to, removal of all equipment, unused materials, all temporary utilities, job trailers and all temporary communication facilities.

10-3.02 Payment: Full compensation for conforming to the provisions of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

10-5 DUST CONTROL

10-5.01 General: Sweeping, covering stockpiles, applying water, and/or dust palliative, to control dust caused by public traffic is not change order work.

All dust producing work and unpaved construction sites shall require a minimum watering in the middle and ending of each workday. The frequency of watering shall increase if dust is airborne. Watering shall not produce runoff.

You shall maintain dust control to the satisfaction of the Engineer, 7 days a week, 24 hours per day.

At the end of each workday, you shall thoroughly sweep all streets effected by the project to minimize airborne dust.

At the end of each work week, you shall sweep all streets in the work zone with a commercial street sweeping truck equipped with a rear pick up broom.

At the Engineer's discretion additional sweeping or watering may be required, including the use of a commercial street sweeping truck equipped with a rear pick up broom, at any time or place.

10-5.02 Payment: Full compensation for conforming to the provisions of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

Payment for **Mobilization (Not to Exceed 2% of Bid)** will be made per the **lump sum (LS)** stated in the Bid Schedule. The contract lump sum price shall include, but not be limited to, mobilization and demobilization, all necessary equipment, setting up and maintaining staging areas, construction water, power and temporary sanitary and washing facilities, acquiring all business licenses and permits as required for the projects, including from utility companies, private and public agencies, and the City, and complying with all the requirements specified in those licenses and permits and all labor, tools, equipment, materials and incidentals required to complete the work.

Partial payments for Mobilization will be made as follows:

- a) When 5 percent of the original contract amount is earned, 50 percent of the amount bid for mobilization will be paid.
- b) When 15 percent of the original contract amount is earned, 75 percent of the amount bid for mobilization will be paid.
- c) When 50 percent of the original contract amount is earned, 95 percent of the amount bid for mobilization will be paid.
- d) Upon completion of all work on the project, 100 percent of the amount bid for mobilization will be paid.

12 TEMPORARY TRAFFIC CONTROL

12-1 GENERAL

12-1.01 General: Construction area traffic control devices shall be installed and maintained in accordance with the applicable sections of these Special Provisions, the Standard Specifications, the current Edition of the California Manual on Uniform Traffic Control Devices (CA MUTCD), the Americans with Disabilities Act (ADA) and as directed by the Engineer.

12-1.04 Payment: Furnishing flaggers shall be considered as included in the contract lump sum price paid for [Bid Item 2] Traffic Control.

Payment for **Traffic Control** will be made per the **lump sum (LS)** as stated in the Bid Schedule. The contract lump sum price shall include, but not be limited to, preparation and implementation of a traffic and pedestrian control and construction phasing plan, and travel (haul) route plans, temporary striping and markers and temporary asphalt work as required by the Engineer to maintain driveway access, flaggers, lights, channelizers, temporary railing, temporary striping, barriers, portable changeable message signs, portable flashing lights, flashing arrow signs, including notification of residents and business and the preparation of the paving schedule, and all labor, tools, equipment, materials and incidentals required to complete the work. No additional compensation will be allowed therefor.

12-3 Traffic-Handling Equipment and Devices

12-3.01 General: Prior to commencing construction which will affect existing vehicular and pedestrian traffic, you shall submit for review by the Engineer, Traffic Control Plans on 11" x 17" sheets of paper which contains only information specifically related to work zone vehicular and pedestrian traffic control. Traffic Control Plans shall be prepared, sealed, and signed by a Professional Engineer registered in the State of California. If you propose to use the current edition of the CA MUTCD published by Caltrans in lieu of a traffic control plan, in specific work operations, they shall submit in writing for consideration which Typical Application Diagram will be used and how it will be applied for each work operation. Traffic Control Plans or proposals shall be submitted for review at least two weeks prior to implementation.

Traffic Control Plans shall contain a title block which contains your name, address, phone number, project superintendent's name, contract name, dates and hours traffic control will be in effect, and a space for review acknowledgment.

The content of the Traffic Control Plan shall include, but is not limited to, the following:

1. Adhere to the approved Caltrans Encroachment Permit for Farmer's Lane (SR-12).
2. Conform with the provided Temporary Traffic Control Plans.
3. Show location and limits of the work zone.
4. Give dimensions of lanes affected by traffic control that will be open to traffic.
5. Indicate signing, cone placement, and other methods of delineation and reference to appropriate City or Caltrans Standards.
6. Dimension location of signs and cone tapers.
7. Identify side streets and driveways affected by construction and show how they will be handled.
8. Show how pedestrian traffic will be handled through the construction site. Pedestrian pathways through the work zone shall be in compliance with the requirements of ADA during and after work hours.
9. Identify message board locations. A minimum of 3 changeable message boards shall be required. Location to be determined by Engineer.
10. Demonstrate how two-way traffic will be maintained.

No work except for installation of project identification signs will be allowed to commence prior to approval of the Work Zone Traffic Control Plans.

12-4 Maintaining Traffic

12-4.01A General

1. Work hours shall be limited to between 7:00 a.m. to 7:00 p.m., Monday through Friday.
2. Night and weekend work shall not be permitted.
3. The full width of the traveled way shall be open for use by public traffic on Saturday, Sundays and City-designated legal holiday(s), after 4:00 p.m. on Fridays and the day preceding City-designated legal holidays, and when construction operations are not actively in progress; unless work has specifically been authorized by the Engineer.
4. The location of traffic control signing, barricades, and other facilities shall be monitored frequently (four to five times per day) by you to verify their proper location. All traffic signal and other traffic control devices shall be maintained at all times.
5. You shall conduct these operations so as to cause the minimum obstruction and inconvenience to traffic and to places of business, multiple dwelling units and residences adjacent to the work. You shall notify the Engineer of his planned work and utility service interruption at least five working days in advance to allow time to notify residents and businesses.
6. When construction activities will prevent vehicle access to individual driveways you shall notify and receive permission from the affected businesses and residents. Attention is directed to Section 7-1.03, "Public Convenience". **Full access shall be provided to all driveways during non-working hours.**
7. At locations where traffic is routed perpendicular to trench excavation, the excavation shall be conducted in a manner to provide a surface reasonably satisfactory for traffic at all times. Substructure installation or construction shall be conducted on only one-half the width of the roadway at a time, and that portion of the roadway being used by traffic shall be kept open and unobstructed until the opposite side of the roadway is ready for use. Upon completion of the rough grading, the surface of the roadbed shall be brought to a smooth, even condition free from humps and depressions and made satisfactory for traffic.
8. You shall coordinate with the City and video detection camera equipment vendor, at no cost to the City, to reprogram video detection zones during all phases of construction, and be responsible for ensuring all detection zones are fully operational and effective during each phase of construction as shown on the traffic control plans.

You shall submit a trucking route along with the traffic controls plans for approval by the Engineer. The route must minimize traffic on residential streets that are not part of the project.

Existing pavement damaged by your operations and not shown to be replaced shall be replaced at your expense, per City Standards and to the satisfaction of the Engineer.

12-4.02 Closure Requirements: Attention is directed to Section 7-1.03, "Public Convenience", and to Section 5-1.05, "Order of Work," of these Special Provisions.

Exact locations of Project Identification signs and Advance Notice signs (Section 7-1.03, "Public Convenience") shall be determined in the field by the Engineer.

You shall maintain vehicle access to homes and other properties at all times while work is in progress.

You shall maintain two-way travel along the corridor at all times, irrespective of individual lane closures.

You shall not park construction vehicles, employee vehicles, stage materials or stockpiles in front of any business or residential driveway access and you shall maintain access to private parking lots within the block where work is in progress. Construction vehicles shall not be left running for any length of time if parked in front of a business or residential unit.

On identified local/residential streets you will normally be allowed use of each block (between nearest intersections) for their sole use, without the need to provide 2-way traffic through that

block. You will be required to maintain vehicle access to homes and other properties within the block where work is in progress.

You shall keep the City of Santa Rosa Fire Department informed regarding the closure of any traveled way. At a minimum, you shall call the Fire Department at (707) 543-3535 **and** the Communications Center at (707) 543-3666 **daily** to report any traveled way closure. This means immediately upon closure for that day and again immediately after removal of the closure. For closures over multiple days, the daily notification still applies. This requirement does not apply for single lane closures on multiple lane streets.

You shall notify Sonoma County Transit at (707) 585-7516, Superintendent of Golden Gate Transit at (415) 257-4442, Santa Rosa City Bus at (707) 543-3922, Sonoma County Airport Express at (707) 837-8700, the local Postal Service at (707) 528-2209 (730 2nd Street) and (707) 275-8777 (707 Hahman Drive) and Recology at (800) 243-0291 5 calendar days prior to any lane closures or restrictions in turning movements.

If you have been given an approved Traffic Control Plan that includes road closures, they shall maintain vehicular access to homes and other properties where work is in progress within the closure area.

Where necessary, and only after receiving written approval from the Engineer, you may temporarily suspend curb side parking in their immediate work zone. Notification to businesses and residents shall be hand delivered at least 72 hours prior to construction in the affected areas.

Notification shall be as follows:

1. A notice placed on the front door of each home or business where curb side parking will be suspended and attempt made to notify each business or resident verbally that work will be underway within the block and that curb side parking will be suspended during stated working hours and request that vehicles be parked out of the roadway by 8:00 a.m. Service of notice shall not bar use of cars within the block, as individual plans change and emergencies arise.
2. Type 1 barricades every 100 feet adjacent to the curb where parking will be suspended with a notice posted on the barricade stating specific dates and times that curb side parking will be temporarily suspended. If work will not take place in the posted area, then you shall remove "No Parking" notices.

You shall maintain vehicle access to all homes and other properties along the work zone. During paving operations, you will be allowed to temporarily suspend vehicle access to a limited number of driveways when approved by the Engineer. When approved by the Engineer and at least 72 hours prior to suspending access to any driveway, you shall give both written and verbal notice to the affected businesses and residents and place barricades adjacent to the driveways with posted notices stating the specific dates and times of the suspension for that area. The notice shall also indicate an alternate parking location. Suspension of access to driveway will be permitted only as approved by the Engineer and only between the hours of 8:00 am and 4:30 pm.

Cross streets will require maintenance of at least one-half (1/2) width of each street for traffic purposes, unless a parallel route is approved by the Engineer. Flagging will only be allowed between the hours of 8:30 am and 4:00 pm.

Barricades and flaggers shall be positioned to allow safe turns at intersections and curves.

You shall maintain traffic control as necessary and as directed by the Engineer for "cat-tracking" operations by City Forces. Flaggers, barricades, signing, etc., shall remain in place for protection of City personnel until such time as all temporary lane delineation is complete.

12-4.04 Temporary Pedestrian Access Routes

12-4.04A(1) Summary: You are directed to Chapter 6D, Pedestrian and Worker Safety, in the CA MUTCD, the improvement plans and these Special Provisions.

Pedestrians shall be provided with a safe convenient and accessible path that, at a minimum, replicates the most desirable characteristics of the existing sidewalk, path or footpath. At no point along the road shall the sidewalks on both sides of the road be closed at the same time.

You shall construct and maintain temporary pedestrian pathways through the work zone, where required, that shall be in compliance with the requirements of the Americans with Disabilities Act (ADA), and the CA MUTCD.

Pedestrian routes shall not be impacted for the purposes of any non-construction activities such as parking of vehicles or equipment, or stock piling of materials. Pedestrians shall not be led into conflicts with work site vehicles, equipment or operations.

Pedestrian routes shall be open and accessible at the end of the work day unless an alternate ADA compliant route has been approved by the Engineer. The construction of curb ramps and/or long sections of sidewalk do not alleviate you from this requirement.

13 WATER POLLUTION CONTROL

13-1 GENERAL

13-1.01 General

13-1.01A Summary: Water Pollution Control shall be performed in accordance with Section 13, "Water Pollution Control", of the Standard Specifications and these Technical Specifications. In addition, construction activities shall comply with:

The current California Water Quality Control Board, North Coast Region Order No. National Pollutant Discharge Elimination System Municipal Storm Water Permit, commonly referred to as the "Storm Water Permit". A copy of the Storm Water Permit is available for review at the City of Santa Rosa Transportation and Public Works Department, 69 Stony Circle, Santa Rosa, CA, and at www.srcity.org/stormwaterpermit.

The California Stormwater Quality Association Storm Water BMP Handbook for Construction (CASQA Handbook). BMPs shall be selected, installed and maintained in accordance with the latest edition. A copy of the handbook can be viewed at the City of Santa Rosa Department of Transportation and Public Works office at 69 Stony Circle or downloaded from CASQA, <http://www.casqa.org/>.

In this technical specification the CASQA Handbook BMP numbers are appended to the associated Standard Specification sections. If a conflict occurs the CASQA Handbook BMP's shall govern.

13-1.01B Definitions: Construction phase: The construction phase starts at the start of job site activities and ends at Contract acceptance.

13-1.01C Submittals

13-1.01C(4)(c) Water Quality Monitoring Reports: If the project is less than 1 acre you shall complete and sign the Storm Water Correction Notices (below) with the City as part of the Storm Water Permit.

13-1.04 Payment: **Water Pollution Control** will be made per the **lump sum (LS)** stated in the Bid Schedule. The contract lump sum price shall include, but not be limited to, implementation of temporary construction best management practices (BMP's) per the California Stormwater Quality Association (CASQA) Stormwater Best Management Practice Handbook, latest edition, in compliance with all applicable local permits and regulations including furnishing, installation, and maintenance and inspection of BMP's including and all labor, tools, equipment, materials and incidentals required to complete the work. No additional compensation will be allowed therefor.

STORM WATER CORRECTION NOTICE

FAILURE TO CORRECT BY DUE DATE MAY RESULT IN STOP WORK NOTICE!

PROJECT NAME: _____
JOB ADDRESS: _____
PROJECT / PERMIT #: _____ DATE: _____

☐ No storm water deficiencies identified.

I HAVE INSPECTED THIS PROJECT SITE. THE FOLLOWING ISSUES AND DEFICIENCIES HAVE BEEN IDENTIFIED AND REQUIRE CORRECTIVE ACTION:

STORMWATER BMPs:

- | | | | |
|---|--|---------------------------|-------------------------|
| <input type="checkbox"/> Storm Drain Protection: | Install | Maintain | Replace |
| <input type="checkbox"/> Perimeter Controls: | Install | Maintain | Replace |
| <input type="checkbox"/> Housekeeping: | Sweep | Clean | Remove Garbage & Debris |
| <input type="checkbox"/> Stockpiles: | Cover | Perimeter Controls | Remove |
| <input type="checkbox"/> Debris Bins: | Cover | Perimeter Controls | |
| <input type="checkbox"/> Tracking: | Clean-Up | Install Tracking Controls | |
| <input type="checkbox"/> Portable Toilet: | Secondary Containment Required | | |
| <input type="checkbox"/> Concrete: | Install BMPs for Pumper or Concrete Truck | | |
| | Cover / Maintain Concrete Washout Containers | | |
| <input type="checkbox"/> Sediment & Erosion: | Install Appropriate Controls | Dust Controls | |
| <input type="checkbox"/> Other: | | | |

***ALL DEFICIENCIES MUST BE CORRECTED PRIOR TO NEXT RAIN EVENT OR NO LATER THAN DUE DATE, WHICHEVER IS SOONER.**

DATE REQUIRED (SEE NOTE*): _____

INSPECTOR: _____ PH #: () _____

CONTRACTOR SIGNATURE: _____ DATE: _____

- Inspection Type:**
- | | |
|--|--|
| <input type="checkbox"/> Monthly (Oct 1 st -April 30 th) | <input type="checkbox"/> Deficiency Re-Inspection |
| <input type="checkbox"/> Pre-Rain (Sept 1 st -Oct 1 st) | <input type="checkbox"/> Following First 0.25" Rain
(within 2 business days) |

13-2 WATER POLLUTION CONTROL PROGRAM

13-2.01C Submittals: The program to control water pollution required to be submitted under this section of the Standard Specifications shall include a spill contingency plan that establishes clean-up procedures that will be followed in the event of a spill of potentially hazardous, toxic, or polluting materials.

13-2.04 Payment: The Water Pollution Control Program shall be considered as included in the contract lump sum price paid for [Bid Item 2] Water Pollution Control.

13-3 STORM WATER POLLUTION PREVENTION PLAN

13-3.01A Summary: This project is exempt from the State Water Resources Control Board General NPDES Permit for the Discharge of Storm Water related to Construction Activities (Construction General Permit) and not required to have a Storm Water Pollution Prevention Plan (SWPPP), therefore Section 13-3, Storm Water Pollution Prevention Plan, of the Standard Specifications does not apply to this project.

13-4 JOB SITE MANAGEMENT

13-4.03 Construction

13-4.03B: Spill Prevention and Control: You shall also comply with CASQA Spill Prevention and Control (BMP WM-4). If a spill occurs at the construction site and you do not take immediate and adequate steps to contain and clean up the spill, especially if rain is threatening or if a discharge to a storm drain or creek could occur, the City shall have the right, in its sole and absolute discretion, to clean up the spill using City forces or an independent contractor. The cost of any such cleanup, in addition to recovery of any penalty or fine imposed upon the City, plus an administrative charge of fifteen percent (15%) of the costs incurred by the City, shall be deducted from any amounts owed to you hereunder.

In the event there are insufficient amounts owed to you hereunder to cover the foregoing costs and charges, the City shall have the right to pursue any other remedy to recover same, including, but not limited to, proceeding against any surety or bond in favor of the City. The City's rights under this section are intended to be in addition to and not in lieu of any imposed by the City against you for violations of City Code Chapter 17-12, "Storm Water".

13-4.03C Material Management

13-4.03C(3) Stockpile Management: You shall also comply with CASQA Stockpile Management (BMP WM-3). Do not block storm water flows.

13-4.03D Waste Management

13-4.03D(1) General: You shall also comply with Waste Management/CASQA Solid Waste Management (BMP WM-5). You shall dispose of all trash, rubbish, and waste materials of any kind generated by you, subcontractor, or any company hired by you on a daily basis.

13-4.03D(3) Concrete Waste: You shall also comply with CASQA Concrete Waste Management (BMP WM-8). Ensure the containment of concrete washout areas and other washout areas that may contain pollutants so there is no discharge into the underlying soil and onto the surrounding areas.

13-4.03D(4) Sanitary and Septic Waste: You shall also comply with CASQA Sanitary and Septic Waste Management (BMP WM-9). Sanitation facilities must be maintained periodically by a licensed service to keep them in good working order and prevent overflows. Portable toilets are required to have secondary containment.

13-4.03D(5) Liquid Waste: Liquid waste includes water generated from excavation dewatering. Minimize transfer piping by locating containers near the excavation to be dewatered while protecting the containers from moving vehicles and equipment.

13-4.03E Nonstormwater Management

13-4.03E(1) Water Control and Conservation: You shall also comply with CASQA Water Conservation Practices (BMP NS-1 and NS-2).

13-4.03E(3) Vehicle and Equipment Cleaning: You shall also comply with CASQA Vehicle and Equipment Cleaning (BMP NS-8).

13-4.03E(4) Vehicle and Equipment Fueling and Maintenance: You shall also comply with CASQA Vehicle and Equipment Fueling (BMP NS-9), and CASQA Vehicle and Equipment Maintenance (BMP NS-10).

13-4.03E(7) Paving, Sealing, Saw cutting, Grooving, and Grinding Activities

As listed in Part 9, sections 4 and 5 of the Storm Water Permit, the following additional BMPs shall be implemented for street paving, repaving, reconstruction, patching, digouts or resurfacing.

1. Restrict paving and repaving activity to exclude periods of rainfall or predicted rainfall unless required by emergency conditions
2. Install BMPs at all susceptible storm drain inlets and manholes to prevent paving products and tack coat from entering
3. Prevent the discharge of release agents including soybean oil, other oils, or diesel to the storm water drainage system or watercourses
4. Minimize non-storm water runoff from water use for the roller and for evaporative cooling of the asphalt
5. Clean equipment over absorbent pads, drip pans, plastic sheeting or other material to capture all spillage and dispose of properly
6. Collect liquid waste in a container, with a secure lid, for transport to a maintenance facility to be reused, recycled, or disposed of properly per Section 13-4.03D(5)
7. Collect solid waste by shoveling and vacuuming or sweeping and securing in an appropriate container for transport to a maintenance facility to be reused, recycled, or disposed of properly per Section 13-4.03D(5)
8. Cover "cold-mix" asphalt (i.e., pre-mixed aggregate and asphalt binder) with protective sheeting during a rainstorm per Section 13-4.03C(3)
9. Cover loads with tarp before haul-off to a storage site, ensuring that trucks are not overloaded
10. Minimize airborne dust by using water spray during grinding per Section 14-9.03
11. Protect stockpiles with a cover or sediment barriers during a rain event and
12. Avoid stockpiling soil, sand, sediment, asphalt material and asphalt grindings materials or rubble in or near storm water drainage system or watercourses per Section 13-4.03C(1)

13-4.03F Sweeping: You shall also comply with CASQA Street Sweeping and Vacuuming (BMP SE-7).

13-4.04 Payment: Work for compliance with Job Site Management shall be considered as included in the contract lump sum price paid for [Bid Item 2] Water Pollution Control which includes all maintenance costs.

13-6 TEMPORARY SEDIMENT CONTROL

13-6.03 CONSTRUCTION

13-6.03C Temporary Drainage Inlet Protection: You shall also comply with CASQA Storm Drain Inlet Protection (BMP SE-10).

13-6.04 Payment: Temporary Sediment Control shall be considered as included in the contract lump sum price paid for [Bid Item 2] Water Pollution Control which includes all maintenance costs.

13-7 TEMPORARY TRACKING CONTROL

13-7.01A General: You shall also comply with Stabilized Construction Entrance and Exit (BMP TC-1), Entrance Outlet Tire Wash (BMP TC-3).

13-7.01C Construction: You shall also comply with CASQA Stabilized Construction Site Entrance / Exit (BMP TC-1).

13-7.03D Payment: The City does not pay 1/2 of that cost for maintaining a temporary construction entrance or roadway under section 9-1.04. You will be responsible for the total cost of maintaining a temporary construction entrance or roadway. Maintaining a temporary construction entrance or roadway shall be considered as included in the contract lump sum price paid for [Bid Item 2] Water Pollution Control.

14 ENVIRONMENTAL STEWARDSHIP

14-10 Solid Waste Disposal and Recycling

14-10.01 General: You shall dispose of all Portland cement concrete and asphalt concrete, generated from removal or demolition activities on the project, at a recycler for these materials.

All other excess materials from the project shall become your property and shall be properly disposed of by you, at your expense.

14-10.02 Solid Waste Disposal and Recycling Report: Submit a Solid Waste Disposal and Recycling Report prior to final acceptance of work performed under the Contract. Show the types and amounts of project-generated solid waste taken to or diverted from landfills or reused on the project.

Submit a Solid Waste Disposal and Recycling Report prior to Contract acceptance. Show the types and amounts of project-generated solid waste taken to or diverted from landfills or reused on the project.

You shall provide receipts verifying delivery and approximate quantity (in tons) of the material delivered to a material recycler.

14-10.03 Payment: Full compensation for conforming to the provisions of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

15 EXISTING FACILITIES

15-1.03 Construction

15-1.03A General: Existing facilities disturbed by construction shall conform to the applicable provisions of Section 5-1.36. All existing active utilities found to reside in excavated areas shall be supported in place with service maintained during construction. You shall be responsible for any damage caused by your operations and any needed repairs shall be completed to the Engineer's satisfaction.

Existing storm drains found to reside in excavated areas shall be supported, removed, or replaced at your option and at no additional cost to the City. You shall be responsible for maintaining the existing line and grade of the storm drains. If you elect to remove and replace, it shall be done per applicable City Standards and Specifications.

Existing utility trenches and/or structures that are in close proximity to proposed trenches shall be safeguarded in an appropriate manner from damage.

15-2 Miscellaneous Facilities

15-2.02 REMOVE

15-2.02A Traffic Stripes and Pavement Markings: All traffic stripes, pavement markings or any other traffic markings shall be removed by you to the satisfaction of the Engineer and in accordance with Sections 84 of the Standards, and the Plans.

15-2.02B Pavement Markers: All raised pavement markers shall be removed by you to the satisfaction of the Engineer and in accordance with Sections 82 "Signs and Markers" of the Standard Specifications, City Standards, and the Plans.

15-2.02C Asbestos Cement Pipe: You are advised that asbestos cement pipe (ACP), including an ACP water main, will likely be encountered on the project and must be cut, handled, and disposed of according to your State Licensing Law and all other applicable laws and regulations.

15-2.02D Reconstruct Sidewalk Drain: Reconstruct sidewalk drain shall be done in conformance with requirements of Section 73 of the City Specifications, City STD-406 "3" Sidewalk Drain" and as directed by the Engineer.

You shall remove portions of existing curb, gutter, and sidewalk, and the existing sidewalk drain and install new sidewalk drain, curb, gutter and sidewalk at the location designated and as directed by the Engineer.

15-2.02E Bus Stop Removals: You shall salvage and remove bus stop signs, signposts, benches, and trash receptacles as noted on the Plans and deliver to the City at the City's Municipal Services Center, 55 Stony Point Road. Where sidewalk panels to remain in place are damaged by bus stop removals, you shall restore damaged sidewalk panels by sawcutting sidewalk to the nearest scoremark or joint and replacing the entire affected sidewalk panel.

15-2.08 RESET

15-2.08A General: Reset existing City facility boxes and lids to grade. The City will furnish at no cost to you new material to replace existing boxes and lids that do not comply with current City Standards or damaged prior to your operations.

15-2.08B Adjust Frames, Covers, Grates, and Manholes: Existing manhole frames and covers, valve boxes, pull boxes, mainline cleanouts and monuments adjusted to grade shall conform to City Standards.

You shall accurately locate and record the location of existing and new manholes, valve boxes, mainline cleanouts, and monuments to be adjusted to grade and shall furnish the Engineer a copy of said record prior to starting construction.

All facilities on active systems shall be accessible at all times to City personnel unless otherwise stated in these Special Provisions or approved by the Engineer.

After placement of the finish course of asphalt concrete, you shall mark all overlaid manholes, valve boxes, mainline cleanouts and monuments, whether new or existing, with white paint by the end of that working day.

All new and existing manholes, valve boxes, mainline cleanouts and monuments shall be accessible within 48 hours after they are covered.

Final grade adjustments and installation of concrete collars shall be done on the same working day. Final paving around manholes, valve boxes, mainline cleanouts and monuments shall be completed the following working day.

All silt and debris shall be removed from finished structures. This shall include all existing silt and debris plus material caused by Your operation.

If new or existing water valve riser pipe needs to be extended after paving to conform to City STD-877 "Gate Valve", you shall use either a slip x slip glued PVC coupling or a transition coupling with sheer bands as directed by the Engineer. Upsizing the existing riser pipe to 8-inch will not be required unless otherwise directed by the Engineer. Any added extension must be a minimum of 12 inches. The lower section of riser pipe shall be adjusted to accommodate this requirement.

In the event that you encounter water valve boxes with round lids or sanitary sewer frame and covers with open pick holes which must be adjusted to grade. You are to provide a count to the Engineer a minimum of two days prior to paving to obtain replacements that complies with current City Standards. The City will provide replacements provided You are not required to replace them as part of the contract or due to damage by Your operations. Valve boxes and frames and covers on facilities to be abandoned shall not be included in the count provided to the Engineer. You shall be responsible for delivery of new frames, boxes, and covers from the City warehouse to the job site. Prior to removal of an existing manhole frame, a platform shall be constructed in the manhole above the top of the sewer to prevent any dirt or debris from falling into the sewer. The platform shall remain in place until all work on the manhole has been completed and the asphalt concrete has been placed around the manhole. Prior to the removal of the platform from the manhole, all dirt and debris shall be removed.

All grade rings shall be set in cement mortar the same day they are placed. All joints shall be smoothly plastered inside and out.

Existing grade rings removed in the adjustment of manhole frames shall become your property and if undamaged and thoroughly cleaned of mortar may be reused in the work. If not used, they shall be disposed of away from the site of work at your expense.

Manhole frames shall be reinstalled to align directly over the grade rings. Any frames misaligned by more than ½ inch shall be removed and reinstalled.

Existing Monuments adjusted shall conform to City Standards 280 to 284 and 78-2 Survey Monuments, of the specifications.

15-2.09 Payment: Payment for **Lower Manhole Frame and Cover** will be made per the contract unit price per **each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, adjusting the manhole frame and cover per the utility owner standards during paving operations including lowering of the manhole frame and cover and necessary removal of riser rings prior to paving and installing a temporary traffic rated cover, as well as all asphalt or concrete work related to the lowering including all labor, tools, equipment, materials and incidentals required to complete the work. No additional compensation will be allowed therefor.

Payment for **Lower Valve Box or Monument** will be made per the contract unit price per **each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, coordination with the utility owner and City prior to and during execution of the work, adjusting the valve box or monument frame and cover per utility owner standards and City standards including protecting the utility valve or monument during paving operations and lowering the valve box or monument frame and cover prior to paving, as well as all asphalt or concrete work related to the adjustment including all labor, tools, equipment, materials and incidentals required to complete the work. No additional compensation will be allowed therefor.

Payment for **Adjust Manhole Frame and Cover** will be made per the contract unit price per **each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, adjusting the manhole frame and cover per the utility owner standards during paving operations including raising the manhole frame and cover to finished grade after completion of paving including replacement of riser rings as well as all asphalt or concrete work related to the adjustment including all labor, tools, equipment, materials and incidentals required to complete the work. No additional compensation will be allowed therefor.

Payment for **Adjust Valve Box or Monument** will be made per the contract unit price per **each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, coordination with the utility owner and City prior to and during execution of the work, adjusting the valve box or monument frame and cover per utility owner standards and City standards including protecting the utility valve or monument during paving operations and raising the valve box or monument frame and cover to finished grade after completion of paving and all asphalt or concrete work related to the adjustment including all labor, tools, equipment, materials and incidentals required to complete the work. No additional compensation will be allowed therefor.

Payment for **Adjust Telephone Vault at Curb Ramp or Sidewalk** will be made per the contract unit price per **each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, adjusting the vault per the utility owner and City standards during concrete installation including coordination with the utility owner and City before and during the work, protection of the telecommunication or fiber optic conduit and cables during concrete demolition, compacting the base or subgrade as needed to match the new concrete grades and angles, and adjusting the vault frame and cover to finished grade, including all labor, tools, equipment, materials, and incidentals required to complete the work. No additional compensation will be allowed therefor.

Payment for **Adjust Television Pull Box at Curb Ramp or Sidewalk** will be made per the contract unit price per **each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, adjusting the pull box per the utility owner and City standards during concrete installation including coordination with the utility owner and City before and during the work, protection of the telecommunication or fiber optic conduit and cables during concrete demolition, compacting the base or subgrade as needed to match the concrete grades and angles, and adjusting the box frame and cover to finished grade, including all labor, tools, equipment, materials, and incidentals required to complete the work. No additional compensation will be allowed therefor.

Payment for **Adjust Electrical Pull Box at Curb Ramp or Sidewalk** will be made per the contract unit price per **each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, adjusting the pull box per the utility owner and City standards during concrete installation including coordination with the utility owner and City before and during the work,

protection of the electrical conduit and conductors, during concrete demolition, compacting the base or subgrade as needed to match the concrete grades and angles, and adjusting the box frame and cover to finished grade, including all labor, tools, equipment, materials, and incidentals required to complete the work. No additional compensation will be allowed therefor.

Payment for **Adjust Traffic Signal Pull Box at Curb Ramp or Sidewalk** will be made per the contract unit price per **each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, adjusting the pull box per the City standards during concrete installation including coordination with the City before and during the work, protection of the traffic signal conduit, conductors, and signal cables during concrete demolition, compacting the base or subgrade as needed to match the new concrete grades and angles, and adjusting the box frame and cover to finished grade, including all labor, tools, equipment, materials, and incidentals required to complete the work. No additional compensation will be allowed therefor.

Payment for **Relocate Traffic Signal Pull Box at Curb Ramp or Sidewalk** will be made per the contract unit price per **each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, relocating the traffic signal box during curb ramp installation to be immediately outside of the proposed detectable warning surface (tile) and curb ramp grade breaks or relocating the traffic signal box immediately outside of the sidewalk grade break per City standards, including coordination with the City before and during the work, including furnishing and installing any necessary conduit, conductors, or traffic signal cables, splicing, compacting the base or subgrade as needed to match the new curb ramp grades and angles, and adjusting the traffic signal box to finished grade, including all labor, tools, equipment, materials, and incidentals required to complete the work. No additional compensation will be allowed therefor.

15-3.03 Construction: All removed concrete shall become your property and shall be immediately off-hauled. None of the removed concrete shall be dumped or stockpiled on the work site. You shall properly dispose of all removed concrete at a recycler for this material. Burying of broken concrete within the limits of the project will not be allowed.

All concrete which is to be removed from sidewalk, curb, gutter and driveway areas shall be removed to the nearest score mark or construction joint as directed by the Engineer unless otherwise noted on Plans. The edge of existing concrete to remain shall be neat and free of defects. Saw cutting may be required to achieve this.

Concrete removal includes removal of any reinforcing steel embedded in the concrete and no additional allowance will be made for the removal of such steel.

Where new concrete is to join existing concrete, remove enough concrete to allow splicing of new reinforcement. Protect existing reinforcement to be incorporated into the new work from damage.

Irrigation facilities may be encountered during concrete removal and replacement. You shall exercise care in this area and repair any damage done by their operations at no additional cost to the City.

Landscaping and other surfaces or structures shall be restored to original condition at no additional cost to the City.

15-7 Utility Clearances

15-7.01 General: All items noted in this Section shall take place prior to any other construction activities.

Pothole information provided on the Plans shall be for reference use only and shall not be considered as accurate information for any other areas within the project limits.

You shall investigate, confirm and/or determine the exact locations of existing utilities, verify utility depths via potholing, and verify clearances between existing and proposed utilities at crossings and/or known potential conflicts. You shall determine elevations and alignments of existing utilities at connection points. You are hereby advised that there at least 11 utility laterals shown on the Plans requiring utility clearance and potholing. It is your responsibility to coordinate required utility-owner notification and clearance with Underground Service Alert (USA) prior to excavations or potholing.

You shall determine elevations and alignments of existing sewer laterals, at the back of sidewalk, if a new proposed sewer main is at a higher elevation than the existing sewer main.

You shall provide all relevant information in writing to the Engineer immediately upon discovery of any conflict. Any delay in notification to the Engineer may delay direction and/or corrective action and a delay claim due to this reason shall not be considered by the City. You shall not proceed with any work that is in conflict until direction is provided by the Engineer and shall redirect crews to other contract work. All the information required to be obtained per this Section and any other information not noted but relative to the project shall be provided to the Engineer on a set of Plans when the investigative effort is complete.

15-7.02 Payment

Payment for **Utility Clearances** will be made per the **lump sum (LS)** stated in the Bid Schedule. The contract lump sum price shall include, but not be limited to full compensation for furnishing all labor, materials, tools and equipment, and doing all the work involved in verifying utility clearances, including but not limited to potholing to verify potential conflicts, grades and alignments of existing facilities to be connected to; excavation; backfill; notification; and coordination and redirection of crews to other contract work, as specified herein. No additional compensation will be allowed therefor.

15-8 Tree Root Pruning

15-8.01 General: All tree roots two inches and greater which are encountered during excavation must be pruned by hand. The root shall be cut cleanly with a saw to avoid splits. When digging within the drip line of trees, you shall exercise extreme caution to avoid pulling on roots with excavation equipment. Hand dig around all roots greater than one inch in diameter. You shall notify the Engineer when encountering roots within the drip line of trees which are greater than one inch. If the Engineer elects to get direction from an arborist You shall redirect crews to other contract work after safeguarding the area.

15-8.02 Payment: Full compensation for conforming to the provisions of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

17 EARTHWORK AND LANDSCAPE

17-2 Clearing and Grubbing

17-2.01 General: Clearing, grubbing, and access shall be confined to the limits shown on the plans and shall not exceed the minimum necessary to complete operations.

You shall not remove any trees, brush, shrubs, or other natural objects outside the limits of construction as shown on the plans, unless directed by the Engineer.

Any trees, brush, shrubs, or other natural objects not ordered removed by the Engineer which have been removed, altered, or damaged shall be replaced in kind by you before completion of the project.

All unsuitable material shall be disposed of away from the site by you. You shall make all necessary arrangements for disposal of material.

17-2.03 Construction: The area to be cleared and grubbed shall be the area within the right-of-way shown on the plans, unless otherwise specified in the Special Provisions.

All stumps, large roots and other objectionable material shall be removed to a depth of three feet below finished grade in the area of construction. The resulting spaces shall be backfilled with material suitable for the planned use. Such suitable material shall be placed and compacted in layers as specified in Section 19.6 "Embankment Construction" of the Standard Specifications.

17-2.04 Payment: Full compensation for conforming to the provisions of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

19 EARTHWORK

19-1 General

19-1.01 General

1. Non-contaminated site: See section 19-2.03B, Surplus Material, of these Technical Specifications.

19-1.01A Summary: Earthwork shall also include excavation for trenching.

19-1.03B Unsuitable Material

Stabilization of unsuitable material shall comply with the following provisions:

1. Unsuitable material may be processed in place, may be excavated and placed on the grade or other locations suitable for further processing, or may be partially excavated and partially processed in place.
2. Processing may consist of drying to provide a stable replacement material or mixing with lime per Section 24.
3. Stabilized material shall be placed and compacted in layers as hereinafter specified for constructing embankments.

19-1.03B(1) Subgrade Stabilization Any area of the subgrade determined by the Engineer to be unsuitable shall be stabilized. Processing of unsuitable subgrade material is not allowed. The areas to be stabilized will be marked in the field by the Engineer after roadway excavation of the area is complete. Use of a pavement grinder shall be considered an acceptable method of excavation of areas requiring subgrade stabilization.

19-1.03 Construction

19-1.03C Grade Tolerance: When aggregate subbase or aggregate base are to be placed on the grading plane, the grading plane shall not vary more than 0.05' above or 0.1' below the grade established by the Engineer.

19-1.04 Payment: Full compensation for conforming to the provisions of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

19-2 Roadway Excavation

19-2.03 Construction

19-2.03A General: The Engineer shall provide reference points and cut sheets for the excavation of the roadway. You shall furnish an excavation and paving plan and a qualified grade setter to ensure the subgrade conforms to the lines and grades established by the Engineer.

For roadway reconstruction, Roadway Excavation shall be performed with a pavement grinder. No other construction equipment including rubber-tired equipment shall be allowed on the subgrade.

Roadway excavation and asphalt concrete base paving shall be completed for half the street width before beginning excavation of the remaining street.

You shall note that there are street trees near areas intended for roadway excavation. Your operation, including the size of the grinding equipment, shall be such, so as to ensure that existing street trees are not damaged. Where limited clearance under the street trees prevents the use of a grinder, excavation shall be performed by an alternate method as approved by the Engineer. Alternate methods may include jackhammering and removal of existing pavement and base materials by hand, or by use of smaller grinding equipment.

Where tree roots are encountered during roadway excavation, you shall cut the roots off six inches below the planned subgrade. Each cut shall be clean with no torn bark or splintered wood remaining on the root and shall be accomplished by use of a saw appropriate for the size of the root to be cut.

19-5 Compaction

19-5.03 Construction

19-5.03B Relative Compaction: Relative compaction of not less than 95 percent shall be obtained for a minimum depth of 0.5-foot below the grading plane for the full width of the planned pavement structural section, whether in excavation or embankment.

Relative compaction of not less than 95 percent shall be obtained for embankment under bridge and retaining wall footings without pile foundations within the limits established by inclined planes sloping 1.5:1 out and down from lines one foot outside the bottom edges of the footing.

20 LANDSCAPE

20-1.02B Water:

You shall obtain water according to section 6-4.01A, construction water of these Special Provisions.

20-2 IRRIGATION

20-2.01 General: Furnish all labor, materials, supplies, tools, and transportation; and perform all operations in connection with and reasonably incidental to the complete installation of the irrigation system as shown on the Project Drawings.

See "Irrigation Specifications and Details" plan sheet 20 of 20 for material, installation and testing specifications.

20-2.01D Payment: Payment for **Irrigation Modifications** shall be paid for at the contract **lump sum (LS)** price, which shall include full compensation for furnishing all labor, materials, tools and equipment including the copper and HDPE irrigation tubing, irrigation control valve, connections to existing irrigation, abandonment of downstream irrigation facilities and conforming to the requirements of the Special Provisions, Project Drawings, and no additional allowance will be made therefor.

26 AGGREGATE BASES

26-1.01 GENERAL

26-1.01A Summary: Aggregate base shall be Class 2 conforming to and placed in accordance with the requirements of Section 26 of the City Specifications.

Compacting shall commence immediately after spreading of the damp material and before the material has dried sufficiently to allow separation between the fine and coarse particles.

26-1.02 MATERIALS

26-1.02B Class 2 Aggregate Base: The minimum sand equivalent shall be 31 for any individual test.

26-1.03 CONSTRUCTION

26-1.03E Compacting: The surface of the finished aggregate base shall be firm and unyielding. Any visible movement vertically or horizontally of the aggregate base under the action of construction equipment or other maximum legal axle loads shall be considered as evidence that the aggregate base does not meet this requirement.

26.104 Payment: Full compensation for conforming to the provisions of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

39 HOT MIX ASPHALT

39-1 GENERAL

39-1.02 MATERIALS

39-1.02B Tack Coat

Non-Tracking Tack Coat Shall Meet or Exceed the Following:

Test	Test Method	Specifications
Viscosity, @ 25 DC, SFS	ASTM D244	20-100
Residue, wt%	ASTM D244	60 Min.
Settlement, % Max. Diff	ASTM D244	5.0 Max.
Sieve, wt%	ASTM D244	0.1 Max.
Storage Stability, 24 hr, %	ASTM D244	0.1 Max.
*Demulsibility, %	AASHTO T59	80 Min.

Test on Residue

*Penetration @ 25°C, 100g, 5 sec	AASHTO T49	10 Min - 30 Max
Solubility, %W	AASHTO T44	97.5 Min.
Ductility @ 25°C, 5 cm/min, cm	AASHTO T51	40 cm/Min.
Specific Gravity @ 15.5° C	AASHTO T295	Report
Softening Point, °C	AASHTO T53	52 Min.

Tack coat shall be applied to all HMA and concrete surfaces and allowed to break immediately in advance of placing Pavement Reinforcing Grid and prior to all lifts of HMA. Tack coat shall also be applied to all vertical mating surfaces and conforms to existing pavement, curbs, gutters, and construction joints, and allowed to break immediately in advance of placing all lifts of HMA. The tack coat shall be reapplied 1) where it becomes contaminated, 2) where it is significantly tracked (removed) from the surface, and/or 3) as otherwise directed by the Engineer.

39-2 HOT MIX ASPHALT

39-2.02 TYPE A HOT MIX ASPHALT

39-2.02A General

39-2.02A(1) Summary: Section 39 includes specific specifications for producing and placing Hot Mix Asphalt (HMA) by mixing aggregate and asphalt binder at a mixing plant and spreading and compacting the HMA mixture.

Asphalt concrete shall be placed in separate lifts as shown on the Plans.

Roadway excavation and asphalt concrete base paving shall be completed for half the street width before beginning excavation of the remaining street.

All existing asphalt concrete that is adhered to the top of gutters shall be removed prior to placement of new asphalt concrete surface in a manner satisfactory to the Engineer and that does not damage the gutter.

Asphalt concrete base shall be placed on the same day the area is excavated so that all areas will either have existing asphalt surface or new asphalt concrete base by the end of each working day. No subgrade areas shall be exposed or open to traffic during non-working hours.

Asphalt concrete base paving shall be accomplished by use of a paving machine. The asphalt mix shall be transferred from the trucks to the hopper of the paving machine by means of a shoulder machine equipped with a side caster. Any equipment used to transfer asphalt concrete

to the paving machine shall not exceed the load capacity of any surface it is driven over and shall not produce rutting or pumping of the existing roadway surface or newly placed asphalt concrete base at any time.

Construction vehicles/equipment shall not be allowed on the newly placed asphalt concrete base until the day after it is placed. Super Dumps or other trucks with liftable trailing load bearing axles shall not be allowed on the newly placed asphalt concrete base at any time. All trucks or other construction equipment to be driven on the newly placed asphalt concrete base shall not exceed the surface load bearing capacity and shall not produce rutting or pumping at any time.

All longitudinal surface paving joints shall fall on a lane line. Longitudinal Subsurface paving joints shall be offset by at least 6 inches.

No longitudinal vertical drop offs will be allowed between the lanes when the roadway is opened to traffic. Where a longitudinal vertical drop off occurs along the roadway crown between the existing street surface and the new asphalt concrete base, you shall grind a 10:1 taper in the existing surface to make a temporary conform to accommodate traffic. The temporary taper shall be ground after the asphalt concrete base paving has been completed each day.

Where a vertical drop off will occur between the top of the new asphalt concrete base and a valley gutter, driveway, or side street conform, you shall install a temporary 10:1 asphalt taper.

Where a vertical drop off would occur between the asphalt concrete base and a pedestrian ramp, you shall install a temporary 12:1 asphalt taper.

All ground edges adjacent to curb ramps and driveways shall have temporary asphalt concrete ramps (tapers) installed if the asphalt concrete surfacing cannot be placed back the same day the existing pavement is removed. Kraft paper or other bond breaker shall be placed under the conform ramps to facilitate removal when paving operations start.

Kraft paper or other bond inhibitor shall be placed under the temporary asphalt taper to facilitate removal when paving operations resume.

Temporary asphalt tapers and associated bond breaker material shall be removed prior to placement of the asphalt concrete surface lift. Where the bond breaker material adheres to the asphalt concrete base course it shall be fully removed with a method, approved by the Engineer that will in no way degrade the quality of the final product.

The Engineer shall provide reference points and cut sheets for the placing of asphalt concrete base and asphalt concrete surface.

You shall furnish an excavation and paving plan which shall include the following:

1. Requested location for survey staking of reference points
2. Asphalt plant supplying mix including aggregate source
3. Disposal site for spoils
4. Type of trucks and equipment to be used
5. Haul routes through adjacent residential streets
6. Staging locations
7. Sequencing
8. Taper grind locations

You shall set a string line based on the reference points to control the grade of the paving machine along the crown line. A rotary laser level may be used in lieu of a string line provided the level can be accurately set to the design centerline slope, and the detector is directly mounted to the paving machine screed to control the grade of the paving along the crown line. You shall also furnish a grade setter to ensure that the asphalt concrete base and asphalt concrete surface paving conforms to the lines and grades established by the Engineer.

A non-tracking tack coat shall be applied to all asphalt concrete and concrete surfaces and allowed to break immediately in advance of placing all lifts of asphalt concrete. Non-tracking tack shall be applied to horizontal surfaces shall be applied with a tack truck, at a minimum residual rate of 0.02 gal/sq yd. Unless otherwise shown on the Plans, tack coat shall also be applied to all vertical mating surfaces and conforms to existing pavement, curbs, gutters, and construction joints, and allowed to break immediately in advance of placing all lifts of asphalt concrete. The tack coat shall be reapplied 1) where it becomes contaminated, and 2) where it is significantly tracked (removed) from the surface.

The asphalt concrete base and asphalt concrete surface courses shall be allowed to cool to 160° F at mid depth before the roadway is opened to traffic each day.

At the end of each working day you shall place retro reflectorized signs and delineators, as required for night time use in accordance with the Standard Specifications and Section 12 of these Special Provisions to warn the public of the existing conditions.

At the end of each workday during paving operations the location of all valves, manholes, monuments and any other facility overlaid with asphalt concrete and required to be raised to grade shall be marked in white paint.

39-2.02A(2) Definitions: For these specifications, HMA and asphalt concrete shall be the same.

At your option, and at no additional expense to the City, a Caltrans approved Warm Mix Asphalt (WMA) technology may be added to the HMA. However, the asphalt concrete shall be manufactured at HMA temperatures (300F +/- 25F) at a dosage rate approved by the Engineer. All other HMA project specifications shall be adhered to.

Use Section 39-3 Method construction process of these specifications for HMA production and construction.

39-2.02B Materials

39-2.02B(3) Asphalt Binder: Asphalt binder in HMA must comply with the specifications for asphalts.

Asphalt binder to be mixed with aggregate for asphalt concrete surface, leveling and base shall be PG64-16 grade paving asphalt.

The amount of asphalt binder to be mixed with the aggregate shall be specified by the Engineer at the time of paving. Different asphalt binder content may be specified for each lift and each location. Liquid anti-stripping agent (LAS) shall be added to the asphalt binder at a rate of 0.5 to 1.0% by weight of asphalt binder as specified by the Engineer at the time of paving. The LAS shall be AD-here LOF 65-00 or equivalent, and shall be stored, measured, and blended with the asphalt binder in accordance with the anti-stripping agent manufacture's recommended practice. The LAS can be added at the asphalt plant or at the refinery. When added at the asphalt plant, the equipment shall indicate and record the amount of LAS added. If added at the refinery, the shipping ticket from the refinery shall certify the type and amount of LAS added.

39-2.02B(4) Aggregates

39-2.02B(4)a General: The aggregate grading of the various types of asphalt concrete shall conform to one of the following as directed by the Engineer:

Surface or Leveling Course..... ½-inch Coarse HMA Type A
Base Course.....¾-inch HMA Type A

Aggregates should be of high abrasion resistance and durability. Excessively soft and friable aggregates are not allowed.

The specified aggregate gradation must be determined before the addition of asphalt binder and includes supplemental fine aggregate.

Before the addition of asphalt binder and lime treatment, aggregate must have the values for the quality characteristics shown in the following table:

Quality characteristic	Test method	HMA Type A
Percent of crushed particles Coarse aggregate (% min.) One fractured face Two fractured faces Fine aggregate (% min) (Passing no. 4 sieve and retained on no. 8 sieve.) One fractured face	California Test 205	90 75 70
Los Angeles Rattler (% max.) Loss at 100 rev. Loss at 500 rev.	California Test 211	10 45
Sand Equivalent (min.) ^a	California Test 217	50 ^b
Fine aggregate angularity (% min.)	California Test 234	45
Flat and elongated particles (% max. by weight @ 5:1)	California Test 235	10

^a Reported value must be the average of 3 tests from a single sample.

^b Minimum Sand Equivalent of 45 for asphalt concrete base.

39-2.02B(4)b Aggregate Gradations: The proposed aggregate gradation must be within the TV limits for the specified sieve sizes shown in the following tables:

**Aggregate Gradation
(Percentage Passing)
HMA Types A**

3/4-inch HMA Type A

Sieve sizes	TV limits	Allowable tolerance
1"	100	--
3/4"	95–100	TV ± 5
3/8"	65–80	TV ± 5
No. 4	49–54	TV ± 5
No. 8	36–40	TV ± 5
No. 30	18–21	TV ± 5
No. 200	2.0–8.0	--

1/2-inch Coarse HMA Type A

Sieve sizes	TV limits	Allowable tolerance
3/4"	100	—
1/2"	94–100	--
3/8"	70–90	--
No. 4	55–61	TV ± 5
No. 8	40–45	TV ± 5
No. 30	20–25	TV ± 5
No. 200	2.0–8.0	--

39-2.02B(5) Reclaimed Asphalt Pavement: Reclaimed Asphalt Pavement (RAP) may be used at your option. If RAP is used, you shall provide the proposed mix design and the quality control for all HMA that includes RAP, in accordance with the following requirements:

1. You shall provide the Engineer with a mix design per California Test 384 for the proposed RAP HMA.
2. As part of the Engineer evaluation of RAP HMA, You and the Engineer shall perform bitumen ratio tests on at least six split samples of your RAP to establish correlation between respective binder ignition ovens.
3. RAP shall be processed from reclaimed Asphalt Concrete pavement only.
4. RAP pile(s) shall be separate from the stacker pile, not intermingled with other materials, and stored on smooth surfaces free from debris and organic material.
5. The project RAP pile shall be processed and mixed, identified, and of adequate quantity for the proposed project. "Live" piles shall not be permitted.
6. You shall sample the RAP pile and determine the bitumen ratio (using same binder ignition oven used in #2 above) and provide the test results to the City at least one week prior to producing RAP HMA.
7. A minimum of three samples shall be tested for bitumen ratio for RAP pile of 1500 tons, or portion thereof.
8. RAP pile shall be mixed such that individual bitumen ratio test results of RAP pile so not vary more than +/- 0.5%.
9. During RAP HMA production, RAP shall be sampled by you off of the belt (into the batch plant), per method established by the Engineer, and samples provided to the Engineer.
10. Bitumen ratio of RAP sampled off of the belt shall be 4.0% minimum, as determined by the Engineer binder ignition oven. City shall select binder content for RAP HMA mix per Specifications.
11. RAP content shall be no more than 20% by dry aggregate mass in the HMA. If proposing a change in the RAP content, you shall notify the Engineer. If the content changes more than 5%, you shall submit a new mix design.
12. Moisture content of RAP pile shall be 4.0% maximum and shall be tested the day prior to the day of paving and tested/monitored during each day of HMA production.
13. RAP pile(s) shall be protected from exposure to moisture.
14. RAP HMA shall comply with all the specifications for HMA.
15. If batch mixing is used, RAP shall be kept separate from the virgin aggregate until both ingredients enter the weigh hopper or pugmill. After introduction to the pugmill and before asphalt binder is added, the mixing time for the virgin aggregate and RAP shall not be less than five seconds. After asphalt binder is added, the mixing time shall not be less than 30 seconds.
16. If continuous mixing is used, the RAP shall be protected from direct contact with the burner flame with a device such as a shield, separator, or second drum.
17. If any of the above criteria are not satisfied, or if the RAP HMA test result determined by the Engineer are inconsistent, RAP HMA production shall stop for City projects until the issue(s) are corrected.

39-2.02B(6) Smoothness: Determine HMA smoothness with a straightedge or a profilograph. The completed surfacing shall be thoroughly compacted, smooth and free from ruts, humps, depressions or irregularities. Any ridges, indentations or other objectionable marks left in the surface of the asphalt concrete by blading or other equipment shall be eliminated by rolling or other means. The use of any equipment that leaves ridges, indentations or other objectionable marks in the asphalt concrete shall be discontinued, and acceptable equipment shall be furnished by you.

39-2.02B(6)(a) Straightedge: The HMA pavement top layer must not vary from the lower edge of a 12-foot long straightedge:

1. More than 0.01 foot when the straight edge is laid parallel with the centerline.
2. More than 0.02 foot when the straightedge is laid perpendicular to the centerline and

extends from edge to edge of a traffic lane.

3. More than 0.02 foot when the straightedge is laid within 24 feet of a pavement conform.

39-2.02B(6)(b) Profilograph: Under California Test 526, determine the zero (null) blanking band Profile Index (PI0) and must-grinds on the top layer of HMA Type A pavement. Take 2 profiles within each traffic lane, 3 feet from and parallel with the edge of each lane. A must-grind is a deviation of 0.3 inch or more in a length of 25 feet. You must correct must-grinds.

Profile pavement in the Engineer's presence. Choose the time of profiling. On tangents and horizontal curves with a centerline radius of curvature 2,000 feet or more, the PI0 must be at most 3 inches per 0.1-mile section. On horizontal curves with a centerline radius of curvature between 1,000 feet and 2,000 feet including pavement within the super elevation transitions, the PI0 must be at most 6 inches per 0.1-mile section.

Before the Engineer accepts HMA pavement for smoothness, submit written final profilograms. Submit 1 electronic copy of profile information in Microsoft Excel and 1 electronic copy of longitudinal pavement profiles in "erd" format or other ProVAL compatible format to the Engineer.

39-2.02B(6)(c) Smoothness Correction: If the top layer of HMA Type A pavement does not comply with the smoothness specifications, grind the pavement to within tolerances, remove and replace it, or place a layer of HMA. The Engineer must authorize your choice of correction before the work begins.

Corrected HMA pavement areas must be uniform rectangles with edges:

1. Parallel to the nearest HMA pavement edge or lane line
2. Perpendicular to the pavement centerline

Measure the corrected HMA pavement surface with a profilograph or a 12-foot straightedge and correct the pavement to within specified tolerances. If a must-grind area or straight edged pavement cannot be corrected to within specified tolerances, remove and replace the pavement. On all ground areas, apply fog seal coat per Standard Specifications Section 37-4, "Fog Seal and Flush Coats."

39-2.02B(7) Acceptance Criteria Testing: The acceptance testing requirement for Sand Equivalent shall be 50 (minimum) for asphalt concrete surface and 45 (minimum) for asphalt concrete base. HMA shall meet the following requirements.

Aggregate Micro-Deval (ASTM D6928-10) ¹	Tensile Strength Ratio, TSR (ASTM D7870) ²
≤16.0%	Not Required
16.1-18.0%	70 (minimum)
18.1-21.0%	80 (minimum)

¹ Asphalt concrete with an aggregate Micro-Deval loss greater than 21.0% shall be removed and replaced at your expense. In addition, no single source of asphalt concrete aggregate shall have a Micro-Deval loss greater than 21.0%.

² TSR testing shall be performed on re-compacted asphalt concrete (per ASTM D7870), obtained from field cores, and tested within 30 days of asphalt concrete placement. Specimens tested shall include 1 unconditioned sample, and 2 conditioned samples as follows:

- a) 20.0 hour Adhesion cycle @ 60°C
- b) 3500 cycles @ 40 psi and 60°C

A single TSR test shall not represent more than 750 tons of asphalt concrete.

Asphalt concrete not meeting the above requirements shall be removed and replaced at your expense.

Test sections shall be approved on the basis of the attainment of 93% relative compaction and a satisfactory surface condition following final rolling. The number of coverages required shall be the minimum number required to obtain 93% relative compaction. Relative density shall be the ratio of in-place density (ASTM Test Method D2950) to test maximum density (California Test 309, Method of Test for Determining Theoretical Maximum Specific Gravity and Density of Hot Mix Asphalt) determined during production paving.

The HMA may be cored during paving of the test sections, and the in-place density for each test section shall be the average of three core densities determined per California Test 308.

39-2.02D Payment: **Hot Mix Asphalt Pavement Surface Course (4 inch depth)** will be made per the contract unit price **Ton (TON)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, furnishing, placing, rolling, and compacting hot mix asphalt pavement in lifts as specified and to the depth indicated on the Plans, including all required surface preparation, compaction testing and proof rolling, tack coat between lifts and adjacent vertical concrete surfaces, the installation and removal of temporary asphalt concrete ramps to provide public access to driveways and roadways, including all labor, tools, equipment, materials and incidentals required to complete the work. Measurement for payment will be based on weight tickets of delivered and placed material to be submitted to the Engineer. No additional compensation will be allowed therefor.

Hot Mix Asphalt Pavement Base Course (4 inch depth) will be made per the contract unit price **ton (TON)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, furnishing, placing, rolling, and compacting hot mix asphalt pavement in lifts as specified and to the depth indicated on the Plans, including all required surface preparation, compaction testing and proof rolling, tack coat between lifts and adjacent vertical concrete surfaces, the installation and removal of temporary asphalt concrete ramps to provide public access to driveways and roadways, including all labor, tools, equipment, materials and incidentals required to complete the work. Measurement for payment will be based on weight tickets of delivered and placed material to be submitted to the Engineer. No additional compensation will be allowed therefor.

39-3 EXISTING ASPHALT CONCRETE

39-3.04 Cold Planing Asphalt Concrete Pavement

39-3.04D Payment: **Cold Mill Asphalt Pavement (8 inch depth)** will be made per the contract unit price **square yard (SY)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, cold milling and disposal of asphalt concrete (AC) pavement to the depth specified on the Plans, cleaning surfaces, layout work, profile milling and disposal of asphalt pavement at crosswalks to ensure a maximum 5% running slope for ADA compliance at crosswalks, and protection of any adjacent PCC pavement, curbs or gutters outside the paving limits including all labor, tools, equipment, materials and incidentals. No additional compensation will be allowed therefor.

39A HOT MIX ASPHALT CONCRETE TRENCH PAVING

39A-1.01 Description: Hot mix asphalt concrete surfacing and asphalt concrete base and the placing thereof shall conform to the requirements of the Standard Specifications, Section 39 of the City Specifications and these Technical Specifications.

39A-2.01 Asphalts: Temporary paving on all utility trenches and any other excavated areas shall be 1/2-inch maximum, medium grade aggregate hot mix asphalt concrete installed a minimum of two inches thick **placed each day** over the work.

Temporary paving around edges of steel plates shall be a hot mix 1/2-inch maximum, medium graded aggregate.

The amount of asphalt binder to be mixed with the aggregate will be specified by the Engineer at the time of paving. Different asphalt binder content may be specified for each lift and each location. Asphalt concrete trench paving shall be per Section 39-1.02E for surface and base requirements.

Cutback shall not be stockpiled or used anywhere on the job site.

39A-5.01 Spreading Equipment: When trench width is three feet or less, the asphalt concrete used for trench paving may be deposited directly from the haul vehicle into the trench. The asphalt shall then be raked smooth prior to compaction.

39A-6.01 General Requirements: Areas outside of reconstruction or overlay limits shall receive permanent trench paving per City STD-215, the modified detail on the Plans or as specified herein.

Areas requiring permanent trench paving per City STD-215 shall have a minimum surface A.C. thickness of 0.35 feet and will use the 6" thick AC alternative in Note 1 of Standard 215.

The Contractor shall provide compaction of backfill and base material as the job progresses. All trench back-fill required per STD-215 on all trenches within the project shall use aggregate base class 2 material as required in Section 26. Temporary paving, as specified in Section 39A-2.01, shall be placed over the work each day, leaving not more than 25 feet unpaved. This temporary paving shall be removed for final street reconstruction and/or trench paving. The 25 feet of unpaved trench shall be covered with skid resistant steel plates (with a coefficient of friction of 0.35 or greater per CTM342), capable of sustaining normal (H20) traffic loads without shifting or bouncing and shall be secured per Caltrans requirements. Plates that have areas where the skid resistant material is missing shall not be used and must be removed from the job site. Hot mix asphalt concrete shall be placed and compacted around all edges of steel plates with a sufficient width and gradual slope in order to provide a smooth transition to existing pavement. The Contractor shall only be allowed to plate one lateral trench at a time.

Temporary and permanent asphalt trench paving shall be even and smooth riding.

The Contractor shall monitor and maintain all temporary paving to the satisfaction of the Engineer.

Asphalt concrete used for temporary trench paving shall be removed and disposed of in accordance with Section 124 "Material Recycling" of these Technical Specifications.

Any existing manholes or valves that are encountered within the trench paving limits must be adjusted to grade per the requirements of Section 15 of these Technical Specifications. The Contractor is responsible for all coordination with the various utility company owners and their representatives, as well as the cost to adjust the various utilities to grade.

39A-6.03 Compacting: Compaction shall be in accordance with Section 39-6.03 of the City Specifications, except as modified below.

The basis for approval shall be the attainment of 93% relative compaction and satisfactory surface condition following final rolling. The number of coverages required shall be the minimum number required to obtain 93% relative compaction, in accordance with Section 39-3.04 of these Technical Specifications.

39A-8.02 Payment: Full compensation for furnishing and installing temporary and permanent trench paving asphalt shall be considered as included in the prices paid for the various contract items of work and no additional allowance will be made therefor.

Asphalt concrete base used in the Permanent Trench Paving structural section is considered as included in the prices paid for various contract items of work and no additional allowance will be made therefore.

40 CONCRETE PAVEMENT

40-1.01 GENERAL

40-1.01A Summary: Portland cement concrete (P.C.C.) pavement shall be constructed in accordance with Section 40 "Concrete Pavement" of the Standard Specifications, the details shown on the Plans, these Special Provisions, and as directed by the Engineer.

Traffic shall not be allowed on new P.C.C. streets until the P.C.C. has attained a minimum compressive strength of 3,500 pounds per square inch (psi). Track-mounted construction equipment will not be allowed on the new P.C.C streets at any time.

All concrete to be removed shall be disposed by you, away from the site of work. All removed concrete shall become your property and shall be immediately off-hauled. None of the removed concrete shall be dumped or stockpiled on the work site. You shall dispose of all removed concrete at an appropriate recycler for this material. Your attention is directed to Section 124, Material Recycling, of these Special Provisions.

You shall furnish an excavation and paving plan which shall include the following:

Define each paving phase using a map showing what ½ width road sections will be demolished and repaved.

Note: The paving plan must conform to the traffic phasing plan and be sequenced in such a way that the streets will be open to two-way traffic during the time that the one half is being reconstructed.

For each concrete paving phase, you shall provide:

1. Provide a map showing what ½ width road sections will be demolished and repaved.
2. Schedule showing when roadway will be out of service to traffic, show excavation, paving and curing dates
3. Requested location for survey staking of reference points
4. P.C.C. pavement plant supplying mix including aggregate source
5. Disposal site for spoils
6. Type of trucks and equipment to be used
7. Haul routes through adjacent residential streets
8. Staging locations
9. Sequencing

40-1.01B Definitions

The following definitions are added under this section of the Standard Specifications:

Contraction Joints: Joints constructed in concrete pavement by saw cutting to a specified depth at specific locations.

Isolation Joints: Joints constructed to isolate structures within or adjacent to the concrete pavement.

40-1.01C Submittals

40-1.01C(4) Mix Design: At least two weeks prior to the placement of the concrete, you shall submit for review and approval, a strength-maturity calibration curve per ASTM C1074 for all proposed mixtures and a copy of the mix design proportions and proposed admixture(s) for all proposed mixtures together with all supporting technical data. Submittal must be reviewed and approved by the City of Santa Rosa Material Lab before concrete can be placed.

All proposed concrete mixtures shall indicate proportions including all material weights, volumes, density (unit weight), water-to-cementitious materials ratio, and void content. The mix design shall specify an average compressive or flexural strength that meets or exceeds the acceptance criteria for the specified strength.

40-1.01C(7) Test Strips: A colored pigment designed for the integral coloring of concrete shall be added to the concrete mix to match the color of the existing concrete pavement, or as directed by the Engineer. The pigment shall contain pure concentrated mineral pigments specifically processed for mixing into concrete and complying with ASTM C979. The colored pigment shall be manufactured by Davis Colors, or an approved equal. You shall provide 1 to 2 lbs./cu. yd. of Davis color 880 (Pewter) added to the concrete mix to color new concrete. The specific color to be used and the pigment dosage rate to be added to the mix may be adjusted as approved by the Engineer based on field poured test panels provided by you.

Two weeks prior to the start of work, you shall submit a color chart, or sample chip set, to the Engineer for determining the pigment color(s) to be used for the test panels. Within two weeks of start of work, and a minimum of three months prior to the start of P.C.C. construction, you shall pour the test panels using the pigment color(s) chosen from the submittals. The first test panel set shall consist of four (4) separate minimum size 2.5 x 2.5-foot panels with a minimum thickness of three inches.

The test panels shall be poured adjacent to one another at a location on the project chosen by the Engineer. The concrete mix used for the test panels shall be "ready mix" concrete from the same supplier and batch plant that will be used to supply concrete for P.C.C. pavement. Concrete from other suppliers or field mixed concrete will not be allowed for pouring test panels. The submitted pigment color shall be added to the concrete mix by the supplier at the batch plant for each test panel. The test panels shall have a medium broom finish and be cured with the same non-pigmented curing compound complying with ASTM C309, Type 1, Class B that will be used on the P.C.C. pavement. Do not cure with plastic sheeting, membrane paper, or intermittent wetting and drying.

The test panels shall be used to find a color for the finished concrete that matches the color of the existing concrete pavement. After a test panel is accepted by the Engineer, the pigment color, dosage rate and curing method used for that test panel shall be applied to all concrete mix for P.C.C. pavement.

40-1.01C(10) Construction Details: You shall submit project-specific plans and details, including placement of joints in paving, locations of utilities within paving limits, and joints between paving and adjacent work or existing facilities. Jointing details for intersections also shall be included in the construction details.

Maximum joint spacing shall be stated on the Plans for all concrete construction shown on the plans. If these details are not furnished by the Engineer, you are to furnish construction details of concrete joints and end of work details for approval by the Engineer.

40-1.01C(12) Grade Tolerance: The aggregate base or asphalt concrete to receive P.C.C. pavement, immediately prior to placing, shall conform to the compaction and elevation tolerances specified, and shall be free of loose or extraneous material. Aggregate base or asphalt concrete shall be uniformly moist, and any excess water standing in pools or flowing on the surface shall be removed prior to placing concrete.

40-1.01D Quality Assurance

40-101D(8) Department Acceptance

40-1.01D(8)(c) Acceptance Testing

40-1.01D(8)(c)(iii) Smoothness: Pavement smoothness requirements specified in Section 40-1.01D(8)(c)(i) will not apply to the pavement surface unless otherwise specified.

If using a straightedge to measure smoothness, the surface must be within 0.02 foot of the straightedge's lower edge. As an alternative, the inertial profiler could be used.

When a straightedge 12-feet-long is laid on the finished surface and parallel with the centerline, the concrete surface shall not vary more than 0.01-foot from the lower edge of the straightedge. The transverse slope of the finished surface shall be uniform to a degree such that no depressions greater than 0.02-foot are present when tested with a straightedge 12-feet-long laid in a direction transverse to the centerline and extending from edge to edge of a 12-foot lane.

Smoothness is often expected to fall out of compliance when matching existing infrastructure, meeting non-uniform grades, or promoting necessary drainage.

40-1.01D(8)(c)(iv) Thickness: Core pavement as directed by the Engineer for verifying P.C.C. pavement thickness, unless Engineer approves alternative method for verifying thickness.

The average P.C.C. pavement thickness must not be deficient by more than 0.02 foot with no individual thickness deficient by more than 0.05 foot. At least two thickness measurement will be made for each day's placement. The day's placement shall be removed and replaced if P.C.C. pavement thickness is deficient in any individual core by 0.10 foot or more.

Clean and dry core holes. Coat the core hole walls with epoxy adhesive conforming to Section 95-1.02D "Epoxy Adhesive for Bonding Freshly Mixed Concrete to Hardened Concrete" of the Standard Specifications. Fill core holes with non-shrink, hydraulic cement grout or concrete pavement mixture. Cores may be placed back in the original holes if coated with epoxy and approved by the Engineer.

40-1.02 MATERIALS

40-1.02A General: For streets and parking lot pavement the minimum allowable average strength of the concrete per ASTM C78, or California Test Method 523, is 550 psi at 28 days age. The average must be calculated using at least three replicate specimens.

Rapid strength concrete shall only be used for high early strength where specifically required by the Special Provisions or shown on the plans. Rapid strength concrete pavement shall be tested per California Test Method 524 and sampled per California Test Method 539. The rapid strength concrete must not have an opening modulus of rupture of less than 400 psi and a 3-day modulus of rupture of not less than 500 psi.

For streets and parking lot pavement, develop and provide a correlation curve between flexural strength and compressive strength using the same mix design, if a compressive strength is not already provided on the plans or these specifications.

40-1.02B Concrete

40-1.02B(2) Cementitious Material: All P.C.C. pavement shall be constructed conforming to the provisions in Section 90 "Concrete" of the Standard Specifications.

Cement shall be Portland cement Type II, Type III, or V conforming to ASTM C150 or Portland cement Type IP, IL, or IS conforming to ASTM C595.

40-1.02B(3) Aggregate: Aggregates used in the concrete mix shall conform with ASTM C33 Standard Specification for Concrete Aggregates and ASTM C1778-16 Standard Guide for Reducing the Risk of Deleterious Alkali-Aggregate Reaction in Concrete.

You shall submit the aggregate source in your mix design. If the aggregate source is on the Caltrans Innocuous Aggregates for Concrete List, no mitigation will be required. If the aggregate source is not on the Caltrans Innocuous Aggregates for Concrete List, then the aggregate sources should be tested in accordance with ASTM C1260 Standard Test Method for Potential Alkali Reactivity of Aggregates. If expansion in ASTM C1260 testing exceeds 0.10% in 14 days, ASTM C1567 Standard Test Method for Determining the Potential Alkali-Silica Reactivity of Combinations of Cementitious Materials and Aggregate should be used to select the required supplementary cementitious material (SCM) dosage required to mitigate expansion.

40-1.02B(5) Supplementary Cementitious Materials: The following supplementary cementitious materials (SCM) listed below are permitted in the P.C.C. pavement mix. SCMs shall adhere to the following test methods and classifications listed below:

1. Fly Ash: ASTM C618 / AASHTO M 295, Class F.
2. Slag Cement: ASTM C989 / AASHTO M 302, Grade 100 or 120.
3. Raw or calcined natural pozzolans: AASHTO M 295, Class N.

If used, the percentage of SCM's allowed in the concrete mix shall adhere to the following ranges below based on the percentage of the ingredients by the total weight of cementitious material used in the batch for concrete:

1. Class F Fly Ash: 15% - 35%.
2. Slag Cement (GGBFS): 25% - 70%.
3. Natural Pozzolans: 5% - 15%.

40-1.02B(5) Chemical Admixtures: If used, chemical admixtures shall comply with ASTM C494. Additional Permitted admixtures include the following below:

1. Hydration Stabilizers: As required to extend working time.
2. Super-Absorbent Polymers (SAP): Allows for increased water-cement ratio to aid in workability and curing while eliminating need for water reducers and viscosity modifiers.
3. Air Entraining Admixtures: ASTM C260.
4. Pigment: ASTM C979.

40-1.02B(6) Water: Water used in the concrete mix shall conform with ASTM C1602 Standard Specification for Mixing Water Used in the Production of Hydraulic Cement Concrete.

40-1.02B(7) Curing Materials: Non-pigmented curing compound must comply with ASTM C309, Type 1, Class B.

40-1.02C Reinforcement, Bars, and Baskets

40-1.02C(1) General: Reinforcing materials shall be required as shown on the plans. Prior to use of additional reinforcing materials such as macro-fibers, tie bars, dowel bars, plate dowels, or diamond dowels you shall first request approval from the Engineer. If used reinforcing materials must also conform to the following requirements below:

1. Macro-fibers: Per manufacturer's recommendations.
2. Reinforcing bars and wire mesh:
 - a. Distributed rebar/mid-panel reinforcement is not necessary when pavement is jointed to form short panel lengths. The use of distributed steel reinforcement will not add to the load-carrying capacity of the pavement and should not be used in anticipation of poor construction practices or soil conditions.
3. Tie bars shall be deformed steel bars conforming to ASTM A615, ASTM A616, or ASTM A617.
4. Dowels:
 - a. Dowel bars: Complying with ASTM A615, ASTM A616, or ASTM A617.
 - b. Plate dowels: Per manufacturer's recommendations, at the direction of the Engineer.

40-1.02E Joint Filler: Pre-molded joint filler or bituminous-type joint material used for isolation and/or expansion joints as shown on the Plans. Isolation or Expansion Joint Material shall comply with ASTM D994, D1751, or D1752.

Joint filler is not required for contraction and construction joints on this project.

You shall submit all joint fillers to the Engineer for review and approval.

40-1.02G Joint Sealer: Joint Sealer for isolation and/or expansion joints must comply with Section 41-5 "Joint Seals" and be on the Caltrans Authorized Materials List for silicone joint sealant: (<https://mets.dot.ca.gov/aml/SiliconeJointSealsList.php>).

You shall submit all joint sealers to the Engineer for review and approval.

40-1.02H Forms: Forms shall be comprised of steel or wood capable of resisting deformation during edge compaction and to maintain grade. Wood forms shall have a minimum nominal thickness of 2-inches.

Forms shall be clean and free of debris, rust, and hardened concrete.

Forms shall be treated with a bond breaker prior to use.

Forms shall be free from warp.

40-1.03 CONSTRUCTION

40-1.03A General

40-1.03A(1) Construction Equipment: Concrete pavement shall be spread, screeded, shaped, slip formed, and/or consolidated by one or more self-propelled machines. These machines shall perform in a manner so that the completed pavement will conform to the required cross section with a minimum amount of handwork. Consolidate the concrete with internal vibrators or other method authorized by the Engineer.

Self-propelled slip form paving machines shall be vibratory and shall be calibrated per the equipment manufacturer.

Each vibrator must have a vibration rate from 5,000 to 8,000 cycles per minute. The amplitude of vibration must cause perceptible concrete surface movement at least 1 foot from the vibrating element. Use a calibrated tachometer to measure the frequency of vibration.

40.1.03A(2) Quality Assurance and Weather Limitations: You shall have a subscription to a weather service to obtain forecasts for wind speed, ambient temperature, humidity, and cloud cover. You shall also maintain an on-site weather station with an anemometer, temperature, and humidity sensors for current site conditions.

Do not place concrete pavement when the ambient temperature is below 45°F, or is expected to fall below 32°F within 48 hours of placement, unless otherwise permitted in writing by the Engineer.

Do not place concrete pavement when the ambient temperature is above 95°F unless otherwise permitted in writing by the Engineer.

Do not place concrete pavement when the wind, heat or humidity do not allow enough time to place, properly joint, compact, edge, finish and cure before the surface dries.

40-1.03B Joints

40-1.03B(1) General: Joints shall be installed at locations and to depths shown on the Plans or your submitted construction details as approved by the Engineer.

Spacing between joints shall not exceed 15 feet unless approved by the Engineer.

Larger horizontal dimension of each slab panel shall not exceed 150 percent of smaller horizontal dimension, unless shown on the plans or approved by the Engineer.

Concrete pavement joints need to mesh with the traffic control plan and final pavement delineation for joints to be either coincidental with or split the middle of the final traffic lane lines to extent feasible.

Joints in newly placed P.C.C. pavement shall align with joints in older adjacent concrete to extent feasible. Joints abutting curbs and other fixed concrete shall be installed within 10 degrees of perpendicular to the older concrete, to extent feasible. If not feasible, efforts shall be made to ensure a sympathy crack does not form in the new plastic concrete at these locations through isolation and reinforcement.

40-1.03B(2) Construction Joints: Construction joints must be vertical.

Install transverse construction joints whenever placing is suspended for 30 minutes or whenever concrete is no longer workable.

Before placing fresh concrete against hardened concrete, existing concrete pavement, or structures, apply curing compound to the vertical surface and allow it to dry.

As shown on the Plans, at joints between new P.C.C. pavement and asphalt concrete pavement, apply a tack coat to the vertical edge of the P.C.C. pavement prior to placing asphalt concrete pavement.

Use a metal or wooden bulkhead to form transverse construction joints. If dowels are described, the bulkhead must allow dowel installation.

40-1.03B(3) Contraction Joints: Spacing between contraction joints shall not exceed 15 feet unless approved by the Engineer. Larger horizontal dimension of each slab panel shall not exceed 150 percent of smaller horizontal dimension, unless shown on the plans or approved by the Engineer.

Contraction joints shall be saw cut and placed after concrete has hardened sufficiently to prevent extensive raveling, but before cracking occurs (including plastic shrinkage cracks that may not be immediately discoverable). The use of early-entry sawing is permitted with approval of the Engineer and verification that random cracking does not occur.

Contraction joint depth shall be a minimum of 33 percent of pavement thickness for conventional sawing or 2 inches for early-entry sawing.

40-1.03B(4) Isolation Joints: Use isolation joints when abutting fixed structures. Place isolation material before concrete is placed and to a minimum depth of the pavement section. Before placing concrete at isolation joints, saw cut the existing concrete face (where applicable) to make a clean, flat, vertical surface and secure the joint filler.

40-1.03D Dowel Bar Placement: Dowels or other load-transfer units of an approved type shall be placed across joints in the manner as shown on the plans. They shall be of the dimensions

and spacing as shown on the plans and constructed to the manufacturer's recommendations and accepted in the field by the Engineer.

You shall submit the proposed method of using wire basket supports including shop drawings with proposed method of anchoring the baskets for acceptance by the Engineer prior to placement. The proposed method of establishing the assembly locations on the subgrade shall be submitted for acceptance as well.

40-1.03F Placing Concrete

40-1.03F(1) General: Spreading, compacting and shaping shall also conform to the provisions in Section 40-1.03F "Placing Concrete" of the Standard Specifications. You shall provide a paving screed capable of extending a minimum of thirty (30) feet. Concrete can be placed with a laser screed with approval of Engineer, provided it meets the minimum extension length requirement.

Immediately in advance of placing concrete, side forms shall be trued and maintained to the required line and grade for a distance sufficient to prevent delay in placing concrete. However, the grade adjacent to the existing (or replaced) curb and gutter should not extend more than approximately 1/4-inch above the gutter lip after final finishing.

Verify surface elevations to ensure required thickness of concrete pavement. The base material must meet 0.02 foot tolerance of the grades shown on the plans.

Any changes of thicknesses must be approved by the Engineer.

40-1.03J Protecting Concrete Pavement: Maintain the concrete pavement temperature above freezing temperatures until the concrete compressive strength exceeds 3,000 psi.

Protect pavement surface from abrasion, discoloration, debris, and sediments.

Clean and repair pavement that has been damaged, soiled, discolored, or contaminated.

Construct crossings for traffic convenience. Rapid strength concrete may be used for crossings if authorized by the Engineer with an approved mix design.

Traffic may be allowed on the concrete pavement once the concrete has attained 3,500 psi compressive strength, verified through either breaking concrete specimens or based on maturity method.

40-1.03K Early Use of Concrete Pavement: You may request early traffic opening for residential light-duty vehicles when the concrete has attained a compressive strength of 2,500 psi with approval by the Engineer. This early opening must not damage the concrete pavement.

40-1.03N Correcting Noncompliant Pavement Work: Damaged pavement may be either repaired, or removed and replaced at the discretion of the Engineer at your cost.

40-1.03H Finishing: In advance of curing operations, the pavement surface shall be finished to grade and cross section with a float, and troweled smooth. Concrete adjacent to the joints and lip of gutter shall be finished with an edger tool.

The surface of the pavement shall be a brush or broom finish, applied when the water sheen can no longer be seen. Bleed water shall not be finished into the concrete surface. The equipment shall operate transversely across the pavement surface, providing corrugations that are uniform in appearance and approximately 1/16 of an inch in depth. The texturing equipment shall not tear or unduly roughen the pavement surface during the operation. Any imperfections resulting from the texturing operation shall be corrected.

Fixed forms shall not be removed in less than 12 hours after the finishing has been completed.

40-1.03I Curing: The concrete shall be cured using the same methods used during implementation of Section 40-1.01C(7) "Test Strips" of these Special Provisions using the same non-pigmented curing compound that complies with ASTM C309, Type 1, Class B. Apply curing compound with mechanical sprayers. Application shall provide uniform coverage without streaks or blotchiness. Reapply curing compound to saw cuts and disturbed areas.

The surface of the freshly placed P.C.C. pavement shall be kept damp until curing takes place. This may require water-fogging or misting if the evaporation rate, calculated in accordance with ACI 305.1 Specification for Hot Weather Concreting, exceeds 0.15 lbs/ft²/hr. Curing compound shall be applied immediately after the final finishing operation and must follow the Manufacturer's guidelines for both timing and dosage for a broomed finish. The P.C.C. pavement shall not be left exposed for more than 30 minutes during the curing period before a curing compound is applied. Cure the P.C.C. pavement exposed area using the curing compound method with non-pigmented curing compound that complies with ASTM C309, Type 1, Class B. If side forms are removed within 72 hours of the start of curing, then the pavement edges must also have curing compound applied or be kept moist.

Where Polymer Cement Surface System (PCSS) Pavement Markings in accordance with Section 84-7 are proposed for high-visibility crosswalks, you shall not spray or utilize curing compounds within the PCSS footprint. You shall only provide moist curing with clean, potable water. Inadvertent overspray of curing compounds shall be completely removed from the proposed PCSS footprint.

40-1.03P Operational Constraint: You shall complete each concrete installation location such that the concrete reaches 3,000 psi within 3 days (72 hours) and can be opened to residential traffic.

If the paving is not progressing at a rate that will permit the restoration of traffic within the specified time period, you shall take appropriate temporary measures, acceptable to the Engineer, to open the road to traffic. These temporary measures shall be at your expense.

40-1.04 Payment: **Bonded Concrete Overlay on Asphalt (8-inch thick)** will be made per the contract unit price **square yard (SY)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, furnishing, forming, placing and finishing the bonded concrete overlay on asphalt as specified and to the depth indicated on the Plans, including surface preparation, reinforcement, admixtures, concrete jointing, the installation and removal of temporary asphalt concrete ramps to provide public access to driveways and roadways, including all labor, tools, equipment, materials and incidentals required to complete the work. No additional compensation will be allowed therefor.

73 CONCRETE CURBS AND SIDEWALKS

73-1 GENERAL

73-1.01 General: This work shall consist of curbs, sidewalks, and their appurtenances, such as gutters, driveways, island paving, curb ramps, and gutter depressions.

73-1.02 MATERIALS

73-1.02A General: Preformed expansion joint filler for sidewalks must comply with ASTM D8139 "Standard Specification for Semi-Rigid, Closed-Cell Polypropylene Foam, Preformed Expansion Joint Fillers for Concrete Paving and Structural Construction". Preformed expansion joint filler for sidewalks shall be 3/8" thick, full sidewalk depth joint filler Nomaflex by Nomaco, Inc. or approved equal.

Bar reinforcement for bus stop sidewalk shall be comprised of deformed bars in accordance with Section 52 "Reinforcement".

73-1.02C Color: A colored pigment designed for the integral coloring of concrete shall be added to the concrete mix. The pigment shall contain pure concentrated mineral pigments specifically processed for mixing into concrete and complying with ASTM C979. The colored pigment shall be Davis Colors color #860, applied in a dosage of 1/3 pound per 94 pound sack of cement (approximately 2 pounds per cubic yard of concrete for a 6 sack mix), or L. M. Scofield color #SG860 applied in a dosage to produce an equivalent color, or an approved equal.

73-2 CURBS

73-2.03 Construction

Curb construction shall be in accordance with Section 73-1.05 of the City Standards.

Curb and Gutter construction shall be in accordance with City STD-241 "Curb and Gutter".

Median curb construction shall be in accordance with City STD-242 "Street Median Curb".

Concrete which is to be removed from curb, gutter, sidewalk and driveway areas shall be removed to the nearest construction joint or as directed by the Engineer.

Curb and gutter and median curb shall be cured in accordance with the requirements of Section 90-1.03B of the Standard Specifications except that you may substitute a pigmented sealer upon the approval in writing of such substituted sealer by the Engineer.

All oil, paint, tire marks, and other discoloring shall be removed from the curb and gutter by sandblasting prior to acceptance by the Engineer. Cement mortar will not be an acceptable substitute for sandblasting. Vandalism to uncured concrete surface shall be removed. If it cannot be removed from the surface, then the vandalized concrete shall be removed and replaced to the nearest score mark.

73-3 SIDEWALK, GUTTER DEPRESSION, ISLAND PAVING (MEDIAN CURB), CURB RAMP, AND DRIVEWAY

73-3.03 Construction

Sidewalk construction shall be in accordance with City STD-237 "Replacement of Sidewalk".

Sidewalk at bus stops shall be in accordance with City STD-237 "Replacement of Sidewalk", Tolar Drawings No. 48729-03 "Santa Rosa Bus Stop Shelter", and the Plans.

Valley Gutter construction shall be in accordance with City STD-243 "Standard Valley Gutter".

Curb ramps shall be constructed in accordance with the details and at the locations shown on the Plans per Caltrans Standard Plan A88A "Curb Ramp Details" except the thickness of minor concrete shall be 4" minimum.

Driveways construction shall be in accordance with City STD-250A "Multi-Residential and Commercial Curb Cuts" or STD-250B "Residential Curb Cuts" along with City STD-251 "Driveway Conform P.C.C. & A.C.".

Sidewalk, gutter depression, median curb, curb ramp, and driveway shall be constructed in accordance with per Section 73-1.07.

Non-walkable surfaces installed in conjunction with a curb ramp installation shall be comprised of cobblestones set in the surface of a concrete mortar. Materials for mortar shall conform to the Section 51-1.02F "Mortar" of the Standard Specifications. Cobblestones shall be smooth, rounded in shape, water-worn stone. The size of the stone shall not be less than four (4) inches or larger than six (6) inches in diameter and shall have no fractured sides. The stone color shall be varying in natural notes, ranging from medium-dark grays to light-medium brown tans. The contractor shall furnish samples of the rock for approval by the Engineer. Only rocks meeting the Engineer's approval shall be used.

All concrete which is to be removed from sidewalk and driveway areas shall be removed to the nearest transverse score mark across the full width of sidewalk or construction joint or as directed by the Engineer.

Soft or spongy base or subgrade material shall be removed and replaced with suitable material as required by the Engineer.

Sidewalks, gutter depression, median curb, curb ramps, and driveways shall be cured in accordance with the requirements of Section 90-1.03B of the Standard Specifications except that you may substitute other than pigmented sealer upon approval in writing of such substituted sealer by the Engineer.

All oil, paint, tire marks, and other discoloring shall be removed from the Sidewalks, gutter depression, median curb, curb ramps, and driveways by sandblasting prior to acceptance by the Engineer. Cement mortar will not be an acceptable substitute for sandblasting. Vandalism to uncured concrete surface shall be removed. If it cannot be removed from the surface, then the vandalized concrete shall be removed and replaced to the nearest scoremark.

73-3.04 Payment: PCC Vertical Curb will be measured by the **linear foot (LF)** as stated in the Bid Schedule, measured along the face of curb as installed.

PCC Curb and Gutter will be measured by the **linear foot (LF)** as stated in the Bid Schedule, measured along the face of curb as installed. No deduction in measured length of curb and gutter to be paid for will be made for curb ramps and driveways.

PCC Valley Gutter will be measured by the **square foot (SF)** as stated in the Bid Schedule, as measured in the field. This measurement includes the curb and gutter related to construction of the PCC Valley Gutter as shown on the Plans and Standard Plans.

PCC Curb Ramp will be measured by the **square foot (SF)** as stated in the Bid Schedule, as measured from between the outside borders of the curb ramp. This measurement includes necessary vertical curb, retaining curb, sidewalk conform panels, and detectable warning surfaces related to the curb ramp work. Measurement includes curb and gutter in front of the curb ramp and sidewalk conforms.

PCC Sidewalk and **PCC Sidewalk Bus Stop** will be measured by the **square foot (SF)** as stated in the Bid Schedule, as measured from between back of curb to back of walk.

PCC Retaining Curb will be measured by the **linear foot (LF)** as stated in the Bid Schedule, as measured in the field along the face of curb.

Payment for Vertical Curb, Curb and Gutter, and Valley Gutter will be paid per the contract unit price. The contract unit price shall include, but not be limited to, necessary removals and disposal, sawcutting of minor concrete and asphalt concrete, disposal of unsuitable base and subgrade, grading, preparing the subgrade, furnishing and compacting the aggregate base, formwork, doweling into the existing concrete, furnishing and placing minor concrete, furnishing and placing curing compound, asphalt concrete plugs, pavement conform grading, resetting of valve boxes or pull boxes to finished grade, and landscape/hardscape replacement as shown on the Plans and as directed by the Engineer including all labor, tools, equipment materials and incidentals. No additional compensation will be allowed therefor.

PCC Curb Ramp will be paid per **square foot (SF)**. The contract unit price shall include, but not be limited to, necessary removals and disposal, sawcutting of minor concrete and asphalt concrete, disposal of unsuitable base and subgrade, grading, preparing the subgrade, furnishing and compacting the aggregate base, formwork, doweling into the existing concrete, furnishing and placing minor concrete, furnishing and installing mortar and cobblestones where required, furnishing and placing curing compound, asphalt concrete plugs, pavement conform grading, furnishing and installing detectable warning surface, relocating stop sign and sign post outside the painted crosswalk per City Standards, resetting of valve boxes and pull boxes to finished grade that are not paid for under other Bid Items, resetting of sign posts to finished grade, and landscape/hardscape replacement as shown on the Plans and as directed by the Engineer including all labor, tools, equipment materials and incidentals. No additional compensation will be allowed therefor.

PCC Sidewalk will be paid per **square foot (SF)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, necessary removals and disposal, sawcutting of minor concrete, disposal of unsuitable base and subgrade, grading, preparing the subgrade, furnishing and compacting the aggregate base, formwork, doweling into the existing concrete, furnishing and placing minor concrete, expansion joint filler where required, furnishing and placing curing compound as shown on the Plans and as directed by the Engineer including all labor, tools, equipment materials and incidentals. No additional compensation will be allowed therefor.

PCC Sidewalk Bus Stop will be paid per **square foot (SF)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, necessary removals and disposal, sawcutting of minor concrete, disposal of unsuitable base and subgrade, grading, preparing the subgrade, furnishing and compacting the aggregate base, formwork, doweling into the existing concrete, furnishing and placing minor concrete, furnishing and placing rebar, expansion joint filler, furnishing and placing curing compound as shown on the Plans and as directed by the Engineer including all labor, tools, equipment materials and incidentals. No additional compensation will be allowed therefor.

Payment for **PCC Retaining Curb** will be paid per **linear foot (LF)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, necessary removals and disposal, sawcutting of minor concrete and asphalt concrete, removing and resetting concrete wheel stops as needed, disposal of unsuitable base and subgrade, grading, preparing the subgrade, furnishing and compacting the aggregate base, formwork, doweling into the existing concrete, furnishing and placing minor concrete, furnishing and placing rebar, furnishing and placing curing compound, restoring full depth parking lot asphalt concrete surfacing and base as needed, restoring parking lot striping as needed, pavement conform grading, installing weep holes at the interval shown on the Plans, or every 25' if not shown, and as directed by the Engineer including all labor, tools, equipment materials and incidentals. No additional compensation will be allowed therefor.

78-2 SURVEY MONUMENTS

78-2.01 General: Survey monuments shall conform to City Standards 280 to 282. The exact location of the monument will be established by the Engineer. The monument will be approved after it is constructed then center point stamped by the Engineer.

Damaged Monuments will be replaced per City Standard and existing components of the damaged monument may not be allowed.

80-1 MODULAR BUS PLATFORM

80-1.01 GENERAL

80-1.01A General: You shall furnish and install two (2) pre-fabricated bus platforms in accordance with the Plans, approved shop drawings, and these Special Provisions. You shall be responsible for field fitting and modifying the bus platform layout as-needed to meet existing roadway and sidewalk conditions, and as directed by the Engineer.

Modular bus platforms shall be Vectorial® modular bus platforms by Zicla. The modular bus platform system shall be comprised primarily of various pre-fabricated interlocking plastic modules that can be arranged to create a combination bus platform and bicycle lane. The modular platform system may also include other plastic appurtenances such as delineators.

You shall adjust platform layout dimensions in increments of 1.15 feet in length or width as needed to conform to existing site constraints. You shall provide mechanical anchoring to the PCC pavement via concrete anchors.

Prior to ordering the pre-fabricated bus platforms you shall submit shop drawings to the City for approval.

80-1.02 MATERIALS

80-1.02A Plastic Modules: The vectorial system consists primarily of various plastic modules that are comprised of a mixture of industrial and post-consumer plastic waste, primarily PVC. The plastic modules should be weather resistant and suitable for installation in a roadway environment. The plastic modules should include perforations to permit stormwater conveyance through the modular bus platform.

Below are the primary module types and options. The Contractor's shop drawings shall clearly indicate the module type and options used including a bill of materials prior.

The various plastic modules types include:

- Main module (weight: $h_1 = 19 \text{ lb } 13 \text{ oz}$, $h_2 = 23 \text{ lb } 9 \text{ oz}$)
- Main module with hinge (weight: $h_1 = 20 \text{ lb } 12 \text{ oz}$, $h_2 = 26 \text{ lb}$)
- Sidewalk Ramp (weight: $33 \text{ lb } 1 \text{ oz}$)
- Road Ramp (weight: varies)
- Straight Curb (weight: $h_1 = 16 \text{ lb } 8 \text{ oz}$, $h_2 = 21 \text{ lb } 13 \text{ oz}$)
- Left and right curbs (weight: $h_1 = 18 \text{ lb } 4 \text{ oz}$, $h_2 = 24 \text{ lb } 11 \text{ oz}$)

Module Colors:

- Black
- Green
- White
- Yellow
- Red

Module surface:

- Non-slip surface
- Warning surface
- Direction surface

Module height:

- Option $h_1 = 5 \frac{33}{64}$ " or option $h_2 = 7 \frac{3}{32}$ "

Retroreflectivity:

- Curbs must be retroreflective and be visible by motorists and nighttime
- Retroreflectivity shall be accomplished by application of retroreflective white or yellow tape suitable for roadway installation

80-1.02B Appurtenances: The modular bus platform may include various appurtenances in addition to the plastic modules including but not limited to delineators and railing. These appurtenances shall be of a similar material as the plastic modules and be furnished from the same vendor supplying the plastic modules to ensure compatibility with the plastic modules.

80-1.02C Pavement Anchors: You shall provide mechanical anchors for attaching the plastic modules to the PCC pavement. Mechanical anchors shall be suitable for installation in a roadway and be capable of restraining the bus platform from vehicular collisions, including collisions by buses without breaking or allowing the bus platform to move.

Mechanical anchors including required adhesives shall be selected from the manufacturer's approved list for installation using a "Definitive / Irreversible" configuration for a "Rigid / Concrete" location.

The Contractor shall submit shop drawings for the PCC pavement anchors to the Engineer for approval prior to ordering.

The Contractor is responsible for determining the correct quantity and location of mechanical fasteners based on the approved shop drawings in accordance with the manufacturer's recommendations.

80-1.02D Storage and Handling: The plastic modules shall be suitable for repeated installation, uninstallation, and storage as required by the project. You shall ensure delivery of all plastic modules and appurtenances to the site, including adequate storage and protection to prevent vandalism or inadvertent damage. Damaged plastic modules or appurtenances shall be replaced at your sole expense.

The manufacturer may provide plastic modules on pallets suitable for lifting by a forklift. Pallets should not weigh more than 1,000 kgs (2,204 lbs) to avoid damage to the plastic modules.

80-1.02E Additional Parts: As a pre-fabricated system, it is your responsibility to determine the need for spare parts including additional plastic modules or anchoring materials as needed to account for damage during handling or installation. Spare parts or additional materials shall be included in your costs to furnish and install the modular bus platform, and the City will not reimburse you for the need for spare parts or additional materials unless at the specific written request of the City.

80-1.03 Shop Drawings

80-1.03A General: For the purposes of bidding, shop drawings and a schedule of materials is included for your reference.

Prior to ordering the modular bus platform system, you shall prepare site-specific shop drawings that account for minor variations in field conditions.

80-1.03B Coordination With Jointing Plan: Shop drawings including the anchoring diagram should be modified in conjunction with the manufacturer to minimize the anchoring of mechanical fasteners within 4 inches of PCC pavement joints. You shall be responsible for preliminary selection of installation location to minimize conflicts between mechanical fasteners and your final jointing plan.

This may include adjusting the final longitudinal location of the bus platform up to 6 inches in either direction.

If required due to conflicts with your final jointing plan, you shall coordinate the need for additional anchor locations with the manufacturer.

80-1.03C Coordination With Striping Plans: You shall be responsible for coordinating with the Engineer and requesting the Engineer update or revise the striping plans based upon your preliminary and final bus platform layout.

80-1.04 Construction

80-1.04A General: You shall install the pre-fabricated modular bus platform system in accordance with the Plans, your approved shop drawings, these Special provisions, and the manufacturer's recommendations. If there should exist a conflict between the manufacturer's recommendations and these Plans or Special Provisions you shall immediately notify the Engineer for clarification.

Installation will include necessary staking and layout for the bus platform. You shall be required to conduct field cutting and fitting per the shop drawings and as needed to fit the existing field conditions. Cut materials should have a clean and neat edge, free of burrs or defects. Materials that are incorrectly cut or damaged during field fitting may be rejected by the Engineer and shall be replaced by you at your sole expense.

Prior to drilling the PCC pavement surface to receive mechanical anchors or fastening the anchors to the PCC pavement surface, you shall request inspection of the final platform layout for compliance with the project plans. You shall notify the Engineer at least 48 hours prior to the need for inspection. Installation of the bus platform without the Engineer's approval may require complete removal and re-installation at the Engineer's sole discretion and at your sole expense.

Interlocking plastic modules should be fully interlocked with adjacent modules and installed flush with the pavement surface, providing for a smooth walking surface. Vertical displacement between installed plastic modules shall be in conformance with required ADA Standards for walking surfaces. At no time shall vertical displacement between plastic modules present a tripping hazard to pedestrians or a cycling hazard to bicycle users.

If not pre-installed by the manufacturer, you shall furnish and install retroreflective traffic tape on the face of the perimeter curb modules as shown on the Plans and approved Shop Drawings. This shall include necessary cleaning and surface preparation of the plastic curbs to receive the retroreflective traffic tape or any required adhesives per the tape manufacturer.

80-1.05 Warranty

80-1.05A General: You shall provide the City with a five (5) year warranty on the fully installed modular bus platform system warranting the system to be free from defects in materials or workmanship while operating under normal roadway conditions.

If the plastic modules pre-maturely fade in color or deform in shape, you shall be responsible for furnishing and replacing the faded or deformed modules at your sole expense.

If the mechanical anchors become separated from the PCC pavement surface causing vertical displacement or lateral displacement of the plastic module, you shall be responsible for re-anchoring the affected tile at your sole expense.

This warranty period will begin from the time the installation is completed and accepted by the Engineer.

80-1.06 Payment: Payment for **Modular Bus Platform System by Zicla** will be made per **Each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, furnishing and installing the pre-fabricated plastic modules and appurtenances, preliminary layout, preparation of shop drawings, required spare parts, final layout, field fitting and cutting of plastic modules, applying retroreflective tape as needed, surface preparation to receive anchoring system, and mechanically anchoring to the PCC pavement surface, and all labor, tools, equipment, materials and incidentals required to complete the work. No additional compensation will be allowed therefor.

80-2 BUS SHELTER AND BENCH

80-2.01 GENERAL

80-2.01A General: You shall furnish and install bus shelters and bus benches in accordance with the Plans, approved shop drawings, and these Special Provisions. You shall be responsible for field fitting and modifying the bus shelter and bench layout as-needed to meet existing sidewalk conditions as required for ADA path of travel, and as directed by the Engineer.

Pre-fabricated bus shelters and benches shall be per Tolar Manufacturing Company Inc. of Corona, CA "Santa Rosa Bus Stop Shelter with Bench" Drawing No. 48729-03.

Prior to ordering the pre-fabricated bus shelters or benches you shall submit shop drawings to the City for approval.

Work for concrete sidewalk for the bus shelter shall be in accordance with Section 73-3 of these Special Provisions. You shall coordinate your layout for the placement of bus stop shelters and benches to ensure mechanical anchor layout is compatible with your reinforced concrete sidewalk layout.

80-2.01B Materials: The following are the material descriptions provided by the manufacturer:

Bus Shelter

8' Signature Series Radius Roof Transit Shelter (48729-03) featuring Signature series extrusion, aluminum roof panels secured with gasketed pressure ribs, perforated aluminum at the rear wall, substitute 3/8" polycarbonate for perforated aluminum in the end walls, multi channel support posts, adjustable leveling shoes, spun escutcheon shoe covers, Tolar USC RMS 80F (3390010 15902- 908) providing dusk to dawn solar powered LED illumination under the shelter roof, mounting kit, 20 gallon smooth side pole mount trash receptacle (1578-01) with hinged and covered lid, durable baked powder coat finish in RAL 7036 Platinum Grey and RAL 5005 Signal Blue (See 15107), stainless steel anchors and all installation hardware

Bench

4' perforated metal bench no back one seat delineator (12092-121)

80-2.01C Payment: Reinforced concrete sidewalk associated with bus stop shelters will be paid for under [Bid Item 24] PCC Sidewalk Bus Stop.

Bus Stop Shelter will be made per the contract unit price **Each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, required layout work, preparation of shop drawings, furnishing and installing pre-fabricated bus stop shelter and appurtenances including waste receptacle, and mechanical anchoring including all labor, tools, equipment, materials and incidentals required to complete the work. No additional compensation will be allowed therefor.

Bus Stop Bench will be made per the contract unit price **Each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, required layout work, preparation of shop drawings, furnishing and installing pre-fabricated bus stop bench, and mechanical anchoring including all labor, tools, equipment, materials and incidentals required to complete the work. No additional compensation will be allowed therefor.

81 MISCELLANEOUS TRAFFIC CONTROL DEVICES

81-3.01 General: Raised pavement markers shall be placed at the locations shown on the Plans and in accordance with the applicable provisions of Section 81 of the Standard Specifications, these Special Provisions, and the City of Santa Rosa Traffic Standards. Attention is directed to Section 15 “Existing Facilities” of these Special Provisions.

81-3.02 Materials: All raised pavement markers (RPMs) shall conform to the most current State Specifications.

81-3.02B Nonreflective Pavement Markers: All non-reflective pavement markers shall be ceramic.

81-3.02C Retroreflective Pavement Markers: Blue reflective raised pavement markers are to be placed per City STD -857 for each fire hydrant within the construction limits of the project. Where a hydrant, whether existing or new, is located at the corner of two streets, a blue RPM shall be placed in each street.

81-3.03 Construction: Existing raised pavement markers to remain, which are damaged by you, shall be replaced as determined by the Engineer, at your expense. This includes areas outside the immediate project limits.

The exact locations and limits of raised pavement markers will be determined in the field by the Engineer.

You shall provide, install and maintain temporary markers on the same day that the existing permanent markers are removed, or as directed by the Engineer, and maintain this delineation until new permanent markers are in place. Temporary markers on non-ground surfaces shall be plastic adhesive retroreflective delineators.

Existing raised pavement markers conflicting with the proposed striping shall be removed immediately prior to placement of new markers.

Existing raised pavement markers to remain, which are damaged by you, shall be replaced.

Holes left in the pavement due to the removal of raised pavement markers shall be filled with enough adhesive to replace any asphalt which comes off with the removal of the pavement marker, leaving a level driving surface.

Permanent raised pavement markers shall be installed within 5 days following final pavement operations. Temporary markings shall be in place the same day of pavement operations.

Raised pavement markers shall be installed the day following pavement overlay.

82 SIGNS AND MARKERS

82-1.01 General

This work shall consist of installation, removal, and relocation of roadside signs as shown on the plans, where directed by the Engineer, and shall conform to the City Specifications.

Signs and hardware which are not to be mounted on traffic signal mastarms or poles shall be provided and installed by you at the locations shown on the plans per Part II of the City Traffic Standards.

Existing signs which are not on traffic signal mastarms or poles shall be relocated as shown on the Plans by you.

New signs and brackets to be mounted on traffic signal mastarms and poles shall be provided and installed by the City.

Existing signs on traffic signal mast arms and poles will be relocated by the City.

Where signs are shown on the plans as relocated or removed, the sign post and foundation shall be removed if no longer in use. Existing sign posts removed from sidewalks shall be ground flush with the existing sidewalk surface, and the void filled with grout.

Salvaged signs shall be returned to the City of Santa Rosa Sign Shop at 55 Stony Point Road. All poles being removed and not relocated shall become your property.

82-2.04 Payment: **Remove Sign and Post** will be made per the contract unit price **each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, removal of existing street signs and sign posts as shown on the Plans, restoration of existing sidewalk or landscaping where sign post was removed, and either delivery and furnishing of salvageable signs and sign posts in good repair to the City's corporation yard, or disposal of signs and sign posts in unsuitable repair, including all labor, tools, equipment, materials and incidentals. No additional compensation will be allowed therefor.

Install Sign on Existing Post will be made per the contract unit price **each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, furnishing and installing street signs on existing posts as shown on the Plans in conformance with the CA MUTCD and City Standards, including all labor, tools, equipment, materials and incidentals. No additional compensation will be allowed therefor.

Install Sign and Post will be made per the contract unit price **each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to, furnishing and installing street signs and sign posts as shown on the Plans in conformance with the CA MUTCD and City Standards and minor concrete or landscaping work to install the sign post, including all labor, tools, equipment, materials and incidentals. No additional compensation will be allowed therefor.

84-2 TRAFFIC STRIPES AND PAVEMENT MARKINGS

84-2.01 General

84-2.01A Summary: Attention is directed to Section 12 “Temporary Traffic Control” and Section 15 “Existing Facilities” of these Special Provisions. Traffic stripes and pavement markings shall conform to the applicable provisions of Section 84 of the Standard Specifications, The City Traffic Standards, and these Special Provisions and shall be placed at the locations shown on the Plans.

You shall provide and install temporary retro-reflective pavement markings on the same day as the existing permanent markings are removed or destroyed, or as directed by the Engineer, and maintain them until the new permanent markings are in place.

Temporary striping on all ground surfaces shall be paint (white and/or yellow) with retro-reflective glass beads or an approved equivalent and shall be installed the same day as the existing permanent striping is removed, or as directed by the Engineer. Temporary striping shall be maintained until new permanent striping is in place.

Existing pavement markings, including crosswalks, disturbed by construction activities shall be replaced in their entirety.

All striping to be replaced shall match existing sections in kind unless approved by the Engineer.

You shall remove all existing traffic striping and pavement marking in conflict with proposed improvements, as shown on the Plans, and as directed by the Engineer, and shall be responsible for the proper disposal of their grindings away from site work.

Permanent traffic stripes and pavement markings shall be installed after all iron has been raised for that particular street section, but no more than five days after final paving for that section of roadway.

Existing stripes and pavement markings to remain, which are damaged by the work shall be replaced at your expense. This includes areas outside the immediate project limits.

Painted curbs which are damaged or replaced as part of the work shall be repainted to match existing conditions.

84-2.03 Construction

84-2.03C Application of Stripes and Markings

84-2.03C(4) Contrast Striping and Markings

White striping and markings placed on P.C.C. pavement shall have a black contrasting color in conformance with the CA MUTCD.

Contrast striping consists of black striping placed below white striping and visible on each side of a white stripe. All white 4”, 6”, and 8” thermoplastic lines shall receive a painted black stripe centered beneath it in widths of 6”, 8, and 10”, respectively.

Contrast markings consist of black paint centered beneath the marking such that a 1” black border is visible on all sides.

Apply contrast stripe paint in one coat.

Do not use glass beads or other reflective elements in contrast striping material.

84-2.04A Measurement: **Thermoplastic Traffic Stripe (Various Details)** will be measured by the **linear foot (LF)** installed per the Standard Plan detail or Plan detail and accepted by Engineer. No deductions in length will be made for gaps in the details or patterns, except for gaps at intersection. For details or patterns with multiple stripes the length will be measured along the center of the pattern only. Measurement includes all raised plastic markers included in the striping detail.

Thermoplastic Bicycle Buffer and **Thermoplastic Bicycle Buffer with Chevron Markings** will be measured by the **linear foot (LF)** installed per the Plan detail and accepted by Engineer. No deductions in length will be made for gaps in the details or patterns, except for gaps at intersection. For details or patterns with multiple stripes the length will be measured parallel to the nearest curb line. Measurement includes all raised plastic markers included in the striping detail.

Thermoplastic White Basic Crosswalk will be measured by the **linear foot (LF)** installed and accepted by Engineer. Measurements will be taken along each edge of a basic crosswalk.

Thermoplastic Green Bike Lane, Thermoplastic White Continental Crosswalk, and Thermoplastic Pavement Markings will be measured by the **square foot (SF)** installed per the Standard Plans, as shown on the Plans, and accepted by Engineer.

4" White Stripe will be measured by the **linear foot (LF)**.

Painted Pavement Markings will be measured by the **square foot (SF)** installed per the Standard Plans as shown on the Plans and accepted by Engineer.

Fire Hydrant Blue Marker will be measured by **each (EA)** installed per the CA MUTCD as shown on the Plans and accepted by Engineer.

84-2.04B Payment: Thermoplastic Traffic Stripes (Various Details), Thermoplastic Green Bike Lane, Thermoplastic Bicycle Buffer, Thermoplastic Bicycle Buffer With Chevron Markings, Thermoplastic White Basic Crosswalk, and Thermoplastic White Continental Crosswalk shall include, but not be limited to, furnishing and installing thermoplastic pavement striping and raised plastic markers per the Standard Plans and as shown on the Plans, black contrasting striping over P.C.C. pavement, any temporary pavement striping, any necessary cat tracks, dribble lines and layout work, and preparing surfaces to receive stripes, including full compensation for furnishing all labor, materials, tools, equipment, and incidentals. No additional compensation will be allowed therefor.

Payment for Thermoplastic Pavement Markings shall include, but not be limited to, furnishing and installing thermoplastic pavement markings per the Standards Plans and as shown on the Plans, black contrasting striping over P.C.C. pavement, any temporary pavement markings, any necessary cat tracks, dribble lines and layout work, preparing surfaces to receive markings, including full compensation for furnishing all labor, materials, tools, equipment and incidentals. No additional compensation will be allowed therefor.

4" White Stripe shall include, but not be limited to, furnishing and installing painted pavement striping and raised plastic markers per the Standard Plans and as shown on the Plans, any temporary pavement striping, any necessary cat tracks, dribble lines and layout work, and preparing surfaces to receive stripes, including full compensation for furnishing all labor, materials, tools, equipment, and incidentals. No additional compensation will be allowed therefor.

Painted Pavement Markings shall include, but not be limited to, furnishing and installing painted pavement markings per the Standards Plans and as shown on the Plans, any temporary pavement markings, any necessary cat tracks, dribble lines and layout work, preparing surfaces to receive markings, including full compensation for furnishing all labor, materials, tools, equipment and incidentals. No additional compensation will be allowed therefor.

Fire Hydrant Blue Marker shall include, but not be limited to, furnishing and installing fire hydrant blue markers per the CA MUTCD and as shown on the Plans, any necessary cat tracks, dribble lines and layout work, and preparing surfaces to receive markers, including full compensation for furnishing all labor, materials, tools, equipment and incidentals. No additional compensation will be allowed therefor.

84-7 POLYMER CEMENT SURFACE SYSTEM PAVEMENT MARKINGS

84-7.01 General

84-7.01A Summary: Section 84-7 includes specifications for installing the Endurablend™ polymer cement surface system (PCSS) pavement markings. You shall install PCSS pavement markings where shown on the Plans for high-visibility crosswalks.

84-7.01A Submittals: At least three (3) weeks before use, submit the following for approval:

1. Certificate of Material Compliance.
2. A color and pattern sample.
3. Training record from the manufacturer for a minimum of one (1) of your employees that will be onsite on a continuous basis when PCSS is installed.
4. Manufacturer's instructions for placing PCSS pavement markings.
5. Safety Data Sheet (SDS)
6. 3-year replacement warranty for Endurablend™ polymer cement surface system pavement markings.

84-7.02 Materials

84-7.02A General: The PCSS material used shall be the Endurablend™ polymer cement surface system pavement markings and must comply with the specifications shown in the following table:

Polymer Cement Material Properties

Description	Test Method	Value
Compressive Strength, (at 28 days) 2" Cube	ASTM C-109	> 3,100 PSI
Tensile Strength	ASTM C-190	> 700 PSI
Bond Strength with Asphalt	ASTM C-1583	> 250 PSI
Bond Strength with Concrete	ASTM C-1583-13	> 250 PSI
Applied Skid Resistance	ASTM E-303	> 60

The material shall be delivered to site in weatherproof containers and stored in a covered and ventilated location.

84-2.03B Warranty: You shall provide a 3-year replacement warranty for the PCSS pavement markings. The 3-year replacement warranty must cover defects in workmanship, colorfastness, and attachment. The 3-year warranty period starts the day after Contract Acceptance.

84-2.03B Chemical Admixtures/Pigments: Any chemical admixtures and/or color pigments used, the dosage rates and the conditions for use in the PCSS shall be approved by the manufacturer.

84-7.03 Construction

84-7.03A General: PCSS pavement marking system shall be installed for high-visibility crosswalks at locations indicated on the Plans and in accordance with the manufacturer's recommendations. You shall protect surrounding pavement surfaces when applying PCSS pavement markings.

84-7.03A(1) Stenciled Pavement: The PCSS pavement marking system shall be comprised of an Endurablend colored base coat and stenciled top coat installed on the P.C.C. pavement for the entire area of the crosswalk to serve as a contrasting background, followed by an installation of Enduramark white paint to serve as the traffic control device.

The base coat may be applied by squeegee or roto-stator spray equipment. When spraying, the apparatus shall be a device approved by the manufacturer and have the capability of mixing the

materials at a rate to insure continuous spray operations. Concrete pavement may require shot blasting to roughen the surface to ensure proper bonding. The base coat provides a grout line color plus seals the surface.

Once the base coat has cured, apply the specified stencil pattern and spray the top coat. Remove the stencil when the top coat has reached the proper consistency and allow coating to cure. Cure to traffic time is approximately 2 hours at 70 degrees. The total cured thickness of the base coat and top coat should be a minimum of 90 mils.

Your equipment shall be capable of handling and transferring the dry materials and liquids to the approved mixer without causing spillage, segregation, or contamination.

The integral color of the base coat or "grout" shall be white.

The integral color of the top coat or "brick" pattern shall be "red", Pantone Matching System, PMS Color 485. The dimensions and pattern of the top coat stencil shall be a "Running Bond" (4" x 7 ¾" brick). The pattern shall be placed such that the long dimension of the brick pattern shall be parallel to the direction of vehicle travel.

Enduramark white paint shall be used for the continental crosswalk pattern above the top coat and installation shall be in accordance with the Plans, Caltrans Standard Plans, and CA MUTCD.

84-7.03B Quality Assurance

84-7.03B(1) Qualified Staff: You shall use personnel trained by the manufacturer to apply Endurablend™ polymer cement surface system pavement markings. The training shall include a minimum of two (2) hours to include material storage, surface preparation, material handling, mixing, placement, and material exposure safety.

It shall be your responsibility to ensure the installation adheres to the manufacturer's minimum installation qualifications. Below is a sample reference of installers pre-approved by the manufacturer:

Address	Telephone
Pavement Surface Coatings LLC 11 Eagle Rock Ave, East Hanover, NJ 07936	Michael Plath: (973)580-2809 Corporate Telephone: (866) 215-6120
Chrisp Company 43650 Osgood Rd. Fremont, CA 94539	Roger Weisbrod Office: 510-656-2840 Mobile: 510-715-8471 Email: rweisbrod@chrisp.com
Sterndahl Enterprises 11861 Branford St. Los Angeles, CA 91352	Denny Sterndahl Office: 818-834-8199 Mobile: 818-612-4595 Email: Denny@sterndahl.com

84-7.03B(2) Quality Control: Within 30 days of application, test the skid resistance of the pavement markings under ASTM E303. The markings shall have a minimum skid resistance value of 60 (British Pendulum Number).

If the pavement markings have insufficient skid resistance, you shall remedy the pavement markings surface to the satisfaction of the Engineer including possible complete removal and re-installation at your sole cost.

84-7.03C Weather Limitations

84-7.03C(1) Required Conditions: PCSS shall only be placed when all of the following conditions are met:

1. The pavement surface is dry.

2. Ambient and substrate temperatures are 50° F (10° C) and rising and expected to remain above 50° F (10° C) for 6 hours minimum.
3. There is no forecast of temperatures below 35° F (2° C) within 24 hours from the time of placement.
4. The weather is not foggy or rainy. When rain appears imminent, all placement operations shall cease, and the work shall not be resumed until the threat of rain has passed.

84-7.03C(2) Cold Weather Requirements: When the ambient temperature is below 50° F (10° C), but will remain above 40° F (5° C) during product installation and for the following 6 hours, your certified installer can install the PCSS at their discretion with the approval of the Engineer.

Care should be taken when placing the PCSS when the substrate temperature exceeds 130° F (50° C). Application temperatures of the substrate above 130° F (50° C) should be closely monitored for performance during the course of the application. Any observable defects occurring as a result of extreme temperature should be cause for immediate halting of placement operations.

84-7.03C(3) Hot Weather Requirements: Where the ambient paving air temperature is going to exceed 90° F (32° C) then the use of cold water and ice should be considered for the blending operation. Where the provision of cold water or replacing part of the water requirement with ice is not possible, then the use of a retarder should be used with the mix.

84-7.03D Concrete Pavement Surface Preparation and Coordination: The substrate that is to receive the PCSS system shall be cleaned of sand, dirt, dust, rock, or any other debris that could prevent proper adhesion. Cleaning shall be accomplished by power broom, scraping, blowing, washing, water or shot blasting (considered on aged concrete) or other approved methods necessary to assure bonding between the PCSS surface course and the substrate. PCSS operations shall not be started until the surface is in a condition as recommended by the manufacturer.

Where PCSS pavement markings are planned to be installed over Concrete Pavement in accordance with Section 40, you shall not utilize curing compounds in the footprint of the PCSS. Where curing compounds of adjacent concrete pavement surfaces are inadvertently applied onto the PCSS footprint, you shall completely remove all overspray of curing compounds prior to installation of PCSS.

84-7.04E Curing and Opening to Traffic: You shall take care to protect the PCSS surface course from traffic until the area is sufficiently cured. Curing time will vary depending on ambient and surface temperatures. The PCSS shall not be opened to traffic until it has reached sufficient compressive strength that the surface will not be damaged by vehicular traffic and the area has been approved for opening by the Engineer.

84-7.04 Payment: Payment for Continental Crosswalk (Polymer Cement Surface System) shall include, but not be limited to, furnishing and installing polymer cement surface system (PCSS) pavement markings system as shown on the Plans, any temporary pavement striping, any necessary cat tracks, dribble lines and layout work, and preparing surfaces to receive PCSS, quality assurance and quality control, and replacement warranty, including full compensation for furnishing all labor, materials, tools, equipment, and incidentals. No additional compensation will be allowed therefor.

87 ELECTRICAL SYSTEMS

87-1.01 General: All traffic signal work shall be performed in conformance with the provisions in Division X Electrical Work, including Section 86 “General” and Section 87 “Electrical Systems” of the Standard Specifications, and these Special Provisions.

Traffic Signal Modifications (Various Intersections) shall include all work and materials required to install the traffic signal modifications shown on the plans, including removal of existing equipment, preservation of existing, and installation of new traffic signal and electrical systems.

Not all existing wires or interconnect may be shown on the plans and may be shallow. Depths must be verified by you by means of potholing, as needed, prior to any work.

87-1.02 Documentation and Submittals: Complete specifications on all materials to be used shall be submitted to the Engineer for approval prior to start of construction, and shall include mechanical, electrical and physical drawings.

87-1.03 Department Acceptance: The functional test for each traffic signal system and lighting system shall consist of not less than 48 hours of continuous, satisfactory operation. If unsatisfactory performance of the system develops, the conditions shall be corrected and the test shall be repeated until the 48 hours of continuous, satisfactory operation is obtained.

87-1.04 Methods and Materials

87-1.04A Concrete Pads, Foundations, and Pedestals: You shall construct foundations for street lights at the locations shown on the plans per City STD.-620A, the Caltrans Standard Specifications, and these special provisions.

Minor Portland cement concrete shall be produced from commercial quality aggregates and cement and shall contain not less than six sacks of cement per cubic yard and with a minimum 28-day compressive strength of 3000 psi.

87-1.04B Pull Boxes: Pull boxes shall conform to STD 730 of the City Traffic Standards and these Special Provisions.

All existing pull boxes to receive new conductors and/or conduits shall be cleaned out, all existing grout removed, and the bottoms re-grouted with a drain hole or the boxes replaced to meet current City Standards.

Pull boxes shall be labeled depending on their purpose:

1. Service
2. Traffic Signal
3. Street Lights
4. Interconnect
5. Fiber

87-1.04C Conductors and Cables: All conductors for traffic signal or street lighting systems shall conform to Part IV-G of the City Traffic Standards.

87-1.04D Detectors: Inductive loop detectors shall conform to Part IV-H of the City Traffic Standards.

Detector handholes shall be Type A installed per State STD ES-5D.

Any existing traffic signal detectors shown on the Plans to remain that are damaged shall be replaced at your expense within five (5) working days or as directed by the Engineer.

87-1.04E Excavating and Backfill for Electrical Systems: Dispose of surplus excavated material from the work area as they are generated.

Native material shall not be used as trench backfill.

87-1.04F Traffic Signal Interconnect Systems: The Contractor shall disconnect, remove, store, re-install, and test traffic signal interconnect system during construction as shown on the plans and described herein.

Scheduling the Work. Prior to disconnection of existing traffic signal interconnect cable, Contractor shall coordinate with City Engineer 10 business days prior to planned disconnect.

Document Pre-Construction Configuration. Contractor shall document existing connections to verify locations for cables to be landed after roadway work has been completed.

Remove Cables. Contractor shall remove interconnect cables along Sonoma Avenue in all segments that include underground work as directed by City Engineer and as shown on the plans.

Store Cables. Contractor shall store interconnect cable in a secure location, either off-site or on-site in location approved by City Engineer.

Re-install Cables. Contractor shall reinstall cables into conduits to revert to pre-construction interconnect configuration. If any conduits are damaged during construction, contractor shall install new conduit at Contractor's expense prior to installation of existing cable.

Functional Testing. The functional test for each traffic signal interconnect system shall consist of not less than 48 hours of continuous, satisfactory operation. If unsatisfactory performance of the system develops, the conditions shall be corrected, and the test shall be repeated until the 48 hours of continuous, satisfactory operation is obtained.

87-1.05 Payment: **Traffic Signal Detector Loops (Type A) and Traffic Signal Detector Loops (Type D)** will be made per **each (EA)** as stated in the Bid Schedule. The contract unit price paid shall include, but not be limited to, removal and disposal of any existing loop detector wire or conduit, sawcutting asphalt pavement or PCC curb and gutter and installation of various Caltrans loop detectors per the Type and size shown on the Plans and per Caltrans Standard Plan ES-5B and ES-5D including furnishing and installing all necessary wiring, conductors, lead-in cable, conduit, sealant, and concrete work to connect to the traffic signal system, including all labor, tools, equipment, materials and incidentals.

You shall test proper compatibility, operation, and detection of the loop detectors with a test vehicle prior to completion of the work. If needed, you shall make adjustments to the existing traffic signal system for proper operation after coordination with the Engineer.

No additional compensation will be allowed therefor.

Payment for **Relocate Pedestrian Lighting** will be made per **each (EA)** as stated in the Bid Schedule. The contract unit price shall include, but not be limited to salvaging and relocating existing pedestrian lighting pole and luminaire to accommodate installation of the proposed curb ramp footprint, furnishing and installing required reinforced concrete footings, furnishing and installing electrical conduit and conductors, splicing conductors, removal of existing pull boxes, furnishing and installing new pull boxes, minor concrete work, coordination with the Engineer and private property owner for site layout, and includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals. No additional compensation will be allowed therefor.

Payment for **Traffic Signal Modifications (Various Intersections)** will be made per the **lump sum (LS)** stated in the Bid Schedule. The contract lump sum price shall include, but not be limited to adjustment and relocation of pedestrian push buttons to be ADA compliant as shown on the

Plans, furnishing and installing push button assembly (PBA) posts, furnishing and installing electrical conduit and conductors, installing new foundations for relocated poles, splicing conductors, removal of existing pull boxes, furnishing and installing new pull boxes, minor concrete work and includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals. No additional compensation will be allowed therefor.

Payment for **Traffic Signal Interconnect System** will be made per the **lump sum (LS)** stated in the Bid Schedule. The contract lump sum price shall include, but not be limited to documenting existing cable configuration, disconnecting, removing, storing, re-installing, and testing traffic signal interconnect cables as shown on the Plans and described herein, and includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals. No additional compensation will be allowed therefor.

90 CONCRETE

90-1.01 GENERAL

90-1.01C Submittals

90-1.01C(6) Mix Design: The proportions of the water, sand and aggregate shall be regulated so as to produce a plastic, workable and cohesive mixture.

90-1.01D Quality Assurance

90-1.01D(2) Cementitious Material Content: Concrete shall contain a minimum of 564 pounds of cementitious material per cubic yard. The amount of cement by weight of the specified cementitious material shall be 75 to 85 percent.

90-1.01D(5) Compressive Strength: The 28-day compressive strength of concrete shall be 4000 pounds per square inch (psi) or greater.

90-1.01D(6) Curing Compound: Concrete shall be cured per Section 90-1.03B of the Standard Specifications. Pigmented curing compound or any other material that will leave a noticeable residue shall not be allowed.

90-1.02E(2) Chemical Admixtures: An admixture shall not be used to reduce the amount of cementitious material content.

112 TREE PROTECTION

112-1.01 General: The following requirements apply for work any property upon which a protected tree is located.

Protected tree means any tree, including a Heritage tree, designated to be preserved on the plans, or as directed by the Engineer. Heritage tree is any of the trees listed under Section 17-24.010 of the City of Santa Rosa Tree Ordinance.

112-1.02 Scope: Before the start of any clearing, excavation, construction or other work on the site, every protected tree shall be securely fenced off at the protected perimeter. Protected perimeter shall be either the root zone or other limit as directed by the Engineer. Such fences shall remain continuously in place for the duration of all work undertaken in connection with this project. The area so fenced off shall not be used as a storage area, altered, or disturbed except as may be permitted under this section.

If any of the site work encroaches upon the protected perimeter of a protected tree, special measures shall be utilized as approved by the Engineer to ensure that the roots obtain oxygen, water, and nutrients as needed. Any excavation, cutting, filling, or compaction of the existing ground surface within the protected perimeter, if authorized by the Engineer, shall be minimized and subject to such conditions as may be imposed by the Engineer. No significant change in existing ground level shall be made within the drip line of the protected tree except as directed by the Engineer and as shown on the plans. No burning or use of equipment with an open flame shall occur near or within the protected perimeter. All brush, earth, and other debris shall be removed in a manner which prevents injury to the protected tree.

No oil, gas, chemicals, or other substances that may be harmful to trees shall be stored or dumped within the protected perimeter or any other location on the site from which such substances might enter the protected perimeter.

Underground trenching for utilities shall avoid major support and absorbing tree roots of protected trees. If avoidance is impracticable, tunnels shall be made below the roots. Trenches shall be consolidated to serve as many units as possible. Trench within the drip line of the tree shall be avoided and only be done at the approval and direction of the Engineer.

No concrete or asphalt paving shall be placed over the root zones of protected trees. No artificial irrigation shall occur within the root zone of oaks.

No compaction of the soil within the root zones of protected trees shall occur.

112-1.03 Payment: Full compensation for conforming to the provisions of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

121 NOTIFICATION

121-1.01 General: You shall notify the Engineer of any work to be performed on any given workday either on the afternoon of the prior working day or before 8:30 a.m. on the given working day. Any work completed for which the Engineer has not received prior notification of its scheduling MAY NOT BE ACCEPTED FOR PAYMENT.

121-3.01 Payment: Full compensation for conforming to the provisions of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

124 MATERIAL RECYCLING

124-1.01 Description: You shall dispose of all portland cement concrete and asphalt concrete, generated from removal or demolition activities on the project, at a recycler for these materials. You shall provide receipts verifying delivery and approximate quantity (in tons) of the material delivered to a material recycler.

All other excess materials from the project shall become your property and shall be disposed of by you, at your expense.

124-1.02 Payment: Full compensation for material recycling as specified herein shall be considered as included in the contract prices paid for various items of work, and no additional compensation will be allowed therefor.

132 WATER DISTRIBUTION SYSTEM

132-1.01 Description: Water Distribution System and related appurtenances shall conform to the requirements as specified in the City of Santa Rosa Water Distribution System Construction Standard Specifications Section 132, the Project Plans, and modifications herein.

132-1.11 Excavation, Backfill, and Resurfacing: You shall remove and replace sidewalk and planter strips as required for all water work to the nearest transverse score mark on both sides and full sidewalk width. All areas of sidewalk removed for construction shall be backfilled and compacted level with temporary asphalt concrete or covered with 1-inch-thick plywood, laid flat with ADA compliant temporary asphalt concrete taper on both ends.

132-1.15A Water Services: New service laterals shall be installed with a minimum horizontal clearance of 3 feet from gas laterals. Water services shall be installed via 'open trench' construction methods only, unless otherwise specified herein. Cement treated base and/or lime treated subbase will likely be encountered during excavation. The 1.5" dual water service located at approximately Station 11+35 shall be replaced in addition to the 1.5" dual water service shown to be replaced on the Plans at Station 13+35.

132-1.15B Adjust Water Vault and Water Components To Grade: Existing water vault box and cover and water components shall be adjusted to conform to finished grades where shown on plans in accordance with Section 15, "Existing Facilities," of the Standard Specifications and to these Special Provisions.

Waste materials generated while adjusting the water vault box, cover and water components to grade shall be completely removed and disposed of in accordance with Section 5-1.20B(4) "Contractor-Property Owner Agreement," of the Standard Specifications.

Replaced hose bibs, check valve, copper piping and fittings shall be in accordance with City Standard 879. The existing meter shall be removed and reinstalled following the replacement of the water components.

All existing water facilities not being replaced shall be protected in place.

132-1.30 Payment: 1.5" Dual Water Service shall be paid for at the contract price **each (EA)**, which price shall include full compensation for furnishing all labor, materials, tools, equipment, incidentals, and doing all work involved in combination water service installation, including but not limited to: excavation and disposal of excavated materials; dewatering and disposal of trench groundwater; contamination awareness; saddle and valve; proper size penetration in main; water service tubing and fittings *as required*; manifold; meter boxes and lids to grade; meter shut off valves; copper and HDPE domestic water tubing downstream of water meter, tie-ins to existing service lines; meter transfers; placing and compacting all required bedding and backfill; trench plates *as needed*; testing and chlorination; temporary trench paving; as specified herein, and no additional allowance will be made therefor.

1" Reduced Pressure Backflow Preventor shall be paid for at the contract price **each (EA)** for the specified types and sizes, which price shall include full compensation for furnishing all labor, materials, tools, equipment, incidentals, and doing all work involved in backflow device installation, including but not limited to: excavation and disposal of excavated material; dewatering and disposal of trench groundwater; contamination awareness; removing and replacing concrete *as required*; removal and disposal of old backflow and tubing; backflow device; fittings *as required*; enclosure *if required*; insulated cover *if required*; placing and compacting all required bedding and backfill; testing and chlorination; restoration/reconstruction of landscaping/irrigation *as needed*; as specified herein, and no additional allowance will be made therefor.

Adjust Water Vault and Water Components to Grade will be paid for at the contract price **lump sum (LS)**, which price shall include full compensation for furnishing all labor, materials, tools and equipment, and doing all the work involved in adjusting the water vault box and cover to grade as herein specified, including, required excavation and backfill, concrete, grade rings/pad, cover/lid, removing and replacing water components at adjusted height, meter transfer; placing and compacting all required bedding and backfill; trench plates *as needed*; testing and chlorination, removing silt and debris; as specified herein, and no additional allowance will be made therefor.

Abandon or Remove Water System Components shall be paid for at the contract price **lump sum (LS)**, including furnishing all labor, materials, tools and equipment, incidentals, and doing all work involved in abandoning and/or removal of water system components, including but not limited to: potholing other than as specified in Section 15 to facilitate the progress of work; excavation and disposal of excavated materials; dewatering and disposal of trench groundwater; contamination awareness; abandonment and/or removal and disposal of old sections of main and fittings; abandonment of pipe ends 2-inch and larger; removal and/or abandonment of valves; removal of old tees and installing like size ductile iron pipe with couplers when water main is to remain active; removal of valve boxes and risers; removal of thrust blocks; removal and disposal of abandoned blow offs and appurtenances; abandoning unused or replaced water services on existing main; removing and disposing of meter boxes and lids, valves, saddles, curb stops and installing a full circle clamp; installing blind flanges if required; placing and compacting all required bedding and backfill including control density fill if required; trench plates as needed; temporary trench paving; removal and replacement of sidewalk and driveways as needed; restoration/reconstruction of landscaping/irrigation and fencing as needed; as specified herein, and no additional allowance will be made therefor.